# STATE OF FLORIDA DEPARTMENT OF TRANSPORTATION TECHNICAL REPORT COVERSHEET

#### DRAFT LEVEL 1 CONTAMINATION EVALUATION SCREENING REPORT

Florida Department of Transportation

District 1

SR 789 (Ringling) Bridge

Limits of Project: from Bird Key Drive to Sarasota Harbour West

Sarasota County, Florida

Financial Management Number: 436680-1-22-01 & 436680-1-32-01

ETDM Number: 14384

Date: May 2023

The environmental review, consultation, and other actions required by applicable federal environmental laws for this project are being, or have been, carried out by the Florida Department of Transportation (FDOT) pursuant to 23 U.S.C. § 327 and a Memorandum of Understanding dated May 26, 2022 and executed by the Federal Highway Administration and FDOT.

# TABLE OF CONTENTS

EXEC	UTIVE	E SUMMARY E	-1
1.0	PRO	JECT SUMMARY1	-1
1.1	Pro	ject Description1	-1
1.2	Pur	rpose & Need1	-3
1	.2.1	BRIDGE DEFICIENCIES:1	-3
1	.2.2	MODAL INTERRELATIONSHIPS:1	-4
1	.2.3	SAFETY:1	-4
1.3	Pur	pose of CSER1	-4
2.0	LAND	D USES	:-1
3.0	HYDF	ROGEOLOGIC SETTING	-1
3.1	Geo	ography3	-1
3.2	Geo	ologic Overview	-1
3.3	Hyd	drogeologic Overview3	-1
3.4	Soi	I Survey3	-1
4.0	LEVE	ELICSER METHODOLOGY4	-1
4.1	Ove	erview4	-1
4.2	Reę	gulatory Agency Database Review4	-1
4.3	Sup	oplemental Regulatory Database Review4	-2
4.4	FDI	EP Contamination Locator Map (CLM)4	-3
4.5	FD	OT Efficient Transportation Decision Making (ETDM)4	4
4.6	Inte	erviews4	4
4.7	His	torical Aerial Photographs4	-5
4.8	Sar	nborn Fire Insurance Maps4	-6
4.9	FD	OT Bridge Structure Survey / Sampling4	-6
4.10	0 Site	e Reconnaissance4	-7
5.0	SITE	IMPACT EVALUATIONS	-1
6.0		CLUSIONS	
Pro	ject Im	pacts Summary6	-1
7.0	RECO	OMMENDATIONS	-1

# LIST OF FIGURES

Figure 1-1 Project Location Map	1-2
Figure 3-1 Topographic Map	3-2
Figure 3-2 NRCS/USDA Soils Map	3-3
Figure 4-1 Site Locations	4-8
Figure 4-2 Land Use and Photo Log Summary	4-8

## LIST OF TABLES

Table E-1 Level I CSER Matrix Summary	. E-1
Table 4-1 Environmental Database Summary	4-2
Table 4-2 Aerial Photo/Historical Land Use Review	4-5
Table 4-3 Project Corridor Reconnaissance Summary	4-7
Table 5-1 Level I CSER Matrix Summary	6-1

## LIST OF CSER APPENDICES

- Appendix A Environmental Data Report (EDR)
- Appendix B Select Documents from FDOT ETDM-EST, FDEP CLM, and Oculus Database Search
- Appendix C Historical Aerial Photographs; EDRI
- Appendix D Sanborn Fire Insurance Map Report
- Appendix E Asbestos Survey & Metals-Based Paint Coatings Sampling Reports
- Appendix F Current Land Use and Risk Assessment
- Appendix G Photo Log Summary

The preferred alternative replaces the existing twin bridges with a single bridge. The single bridge typical section includes two 10.5-ft wide travel lanes, a dedicated 11-ft transit lane, 2.5-ft inside shoulder, 5.5-ft bike lane, and 14-ft shared use path in each direction. The total width of the bridge is 114 ft 3-in.

The new bridge will transition to a curb and gutter roadway typical section that includes two 10.5-ft wide travel lanes, a dedicated 11-ft transit lane, and 5-ft bike lane in each direction, separated by a median with Type E curb and gutter. This section of roadway also includes a 10-ft shared-use path on both sides of the roadway that connects to the bridge. The design speed is 40 mph with a posted and target speed of 35 mph.

The limits of the improvements are from Bird Key Drive to Sarasota Harbour West in Sarasota County. The purpose of the study is to address structural integrity and operational deficiencies. SR 789 is classified as an Urban, Minor Arterial and consists of a four-lane, divided typical section between Bird Key Drive and Sarasota Harbour West, a distance of 0.741 miles. SR 789 serves as the only connection from downtown Sarasota to St. Armands Key and Lido Key. Although SR 789 is designated as a north-south route, within the project limits SR 789 runs in a generally east-west direction.

The existing twin bridges cross the Coon Key Waterway, a navigable waterway without a defined channel. Per the FDOT Design Manual (FDM), a minimum six-foot vertical clearance is required. The existing concrete multi-beam bridges were constructed in 1958. The bridges are spaced 100 feet apart and each bridge is approximately 1,006'-10" long (21 spans of 48 feet each). Each bridge has two twelve-foot travel lanes and a five-foot wide sidewalk on both sides. There are currently no shoulders or designated bicycle facilities across the bridges.

The Level I Contamination Screening Evaluation Report (CSER) that was conducted showed a total of seven (7) sites within specified distances of the edge of the project right-of-way, as summarized in Table E-1 that follows:

		-	
Risk	Number of Sites	Site Identification & Description	Source to R/W Distance
		Bird Key Municipal Park	Adjacent
	4	Sarasota Harbour East & West (Townhomes)	Adjacent
No		Sidewalk refurbishment & staging area	Within
		Harris Residence, 243 Robin Dr.	>1,000 feet
	2	Sarasota Yacht Club (SYC), 1100 John Ringling Blvd	300 feet
Low		Plymouth Harbor, 20-story condominium at 700 John Ringling Blvd	350 feet
Medium	1	SR 789 Ringling Bridge (both spans)	Within
High	0	No Properties / Structures Identified	NA

Table E-1 Level I CSER Matrix Summary

Based on the proximity of the underground storage tanks (UST) at the Sarasota Yacht Club (SYC) and the above ground storage tank (AST) at Plymouth Harbor relative to the Project Corridor, either property represents a Low risk to soil and/or groundwater quality along the project corridor with any real sense of practicality. Based upon two reports of Asbestos Survey and Metals-Based Paint Coatings Sampling (one for each bridge), metals-based paint coatings were identified on the pile jackets of both bridge structures, which presents a Medium risk.

# 1.0 PROJECT SUMMARY

## 1.1 **Project Description**

The preferred alternative replaces the existing twin bridges with a single bridge. The single bridge typical section includes two 10.5-ft wide travel lanes, a dedicated 11-ft transit lane, 2.5-ft inside shoulder, 5.5-ft bike lane, and 14-ft shared use path in each direction. The total width of the bridge is 114 ft 3-in.

The new bridge will transition to a curb and gutter roadway typical section that includes two 10.5-ft wide travel lanes, a dedicated 11-ft transit lane, and 5-ft bike lane in each direction, separated by a median with Type E curb and gutter. This section of roadway also includes a 10-ft shared-use path on both sides of the roadway that connects to the bridge. The design speed is 40 mph with a posted and target speed of 35 mph.

The limits of the improvements are from Bird Key Drive to Sarasota Harbour West in Sarasota County (see **Figure 1-1**). The purpose of the study is to address structural integrity and operational deficiencies. SR 789 is classified as an Urban, Minor Arterial and consists of a fourlane, divided typical section between Bird Key Drive and Sarasota Harbour West, a distance of 0.741 miles. SR 789 serves as the only connection from downtown Sarasota to St. Armands Key and Lido Key. Although SR 789 is designated as a north-south route, within the project limits SR 789 runs in a generally east-west direction.

The existing twin bridges cross the Coon Key Waterway, a navigable waterway without a defined channel. Per the FDOT Design Manual (FDM), a minimum six-foot vertical clearance is required. The existing concrete multi-beam bridges were constructed in 1958. The bridges are spaced 100 feet apart and each bridge is approximately 1,006'-10" long (21 spans of 48 feet each). Each bridge has two twelve-foot travel lanes and a five-foot wide sidewalk on both sides. There are currently no shoulders or designated bicycle facilities across the bridges.



Figure 1-1 Project Location Map

Note: Map not to scale

## 1.2 Purpose & Need

The purpose of the project is to address structural integrity and operational deficiencies of the SR 789 bridges [Structure Numbers 170022 and 170951]. The ultimate goal of the project is to identify the optimal solution for a bridge structure in need of repair due to deteriorating conditions and to accommodate greater multimodal transportation access. The project will evaluate twin bridge and single bridge alternatives for the reconstruction/rehabilitation, with consideration of bicycle/pedestrian and transit facilities, of approximately 0.741 miles of roadway that provides a connection between nearby neighborhoods and recreational facilities (Ringling Bridge Causeway Park, Bird Key Park and the Sarasota Yacht Club). The need for the project is based on the following criteria:

## 1.2.1 BRIDGE DEFICIENCIES:

The current concrete multi-beam bridge is the second bridge that has existed at this location, with the original bridge replaced in 1958. Several sections of the deck were replaced on the northbound bridge in 2016 along with other repair-type work throughout the years. The SR 789 bridges, located between downtown Sarasota and St. Armands Key and Lido Key, are more than fifty-years old, the typical expected design life for transportation infrastructure, and are operationally deficient, particularly for transit. SR 789, including the bridges, is identified as a constrained roadway by the Sarasota / Manatee Metropolitan Planning Organization (MPO), meaning it does not preclude any type of improvement in the future, but it identifies that the corridor has physical, or policy challenges associated with a widening/capacity project.

Based on a January 2021 FDOT bridge inspection report, the SR 789 bridges received a sufficiency rating of 77.0 (northbound) and 77.8 (southbound) on a scale of 0-100. Sufficiency rating is essentially an overall rating of a bridge's fitness to remain in service. A bridge with a sufficiency rating of 80 or less is generally eligible for bridge rehabilitation funding. The bridge conditions are as follows:

## <u>Northbound</u>

- Overall Condition: Fair
- Deck: Fair
- Superstructure: Satisfactory
- Substructure: Satisfactory
- Deck Geometry Appraisal: Basically intolerable requiring a high priority replacement
- Countermeasures have been installed to mitigate an existing problem with scour.

## Southbound

- Overall Condition: Good
- Deck: Satisfactory
- Superstructure: Good
- Substructure: Satisfactory
- Deck Geometry Appraisal: Basically intolerable requiring a high priority replacement
- Countermeasures have been installed to mitigate an existing problem with scour.

## 1.2.2 MODAL INTERRELATIONSHIPS:

SR 789 (Ringling) serves as the primary connection between downtown Sarasota and St. Armand's Key and Lido Key and is frequently used by bicyclists and pedestrians due to the adjacent parks and recreational facilities [Bird Key Park South / Bird Key Park, West MURT Bird Key / Coon Key Phase I, John Ringling Trail and Longboat Key Trail Corridor]. While there are five-foot wide sidewalks on both sides of the bridges, there are currently no shoulders or designated bicycle facilities across the bridges. Due to the minimal sidewalk width, there are often conflicts between pedestrians and bicyclists. Overall, the proposed project intends to enhance mobility by evaluating alternatives for reconstruction/rehabilitation with consideration of bicycle/pedestrian and transit facilities on approximately 0.741 miles of roadway on SR 789.

## 1.2.3 **SAFETY**:

Serving as part of the emergency evacuation route network designated by the Florida Division of Emergency Management and City of Sarasota, SR 789 plays a critical role in facilitating traffic during emergency evacuation periods as the primary connection between downtown Sarasota and St. Armand's Key and Lido Key. The entire project corridor is located in the City of Sarasota's Hurricane Storm Surge Category "A."

The City of Sarasota Climate Adaptation Plan (December 4, 2017) studied and evaluated climate threats to public infrastructure to understand how sea level rise, storm surge, extreme precipitation, and extreme heat might impact the City of Sarasota's transportation network; stormwater management, water supply, and wastewater systems; public lands; and critical buildings. Thirty-four transportation assets were evaluated of which 15 were deemed most vulnerable, including SR 789 [Project ID T15, pg. 31]. When prioritizing transportation vulnerabilities, the SR 789 bridge received a risk score of 64.4 (on a scale of 0-100). The potential reconstruction and/or rehabilitation of SR 789 bridge would make it more resilient to climate vulnerabilities.

## 1.3 Purpose of CSER

The purpose of this Contamination Screening and Evaluation Report (CSER) is to present methods and findings of a contamination screening evaluation for the project along SR 789 from Bird Key Drive to Sarasota Harbour West on Coon Key. This report identifies and evaluates known or potential contamination issues on properties along or near the existing right-of-way of SR 789 (project corridor) from MP 1.206 south to 1.947. This CSER also presents recommendations for supplemental sampling and analysis of soil and/or groundwater samples at select locations along the project corridor.

# 2.0 LAND USES

Both current and historical land use are important factors in evaluating whether soil and/or groundwater quality may have been affected along the project corridor. Evaluating the past land use of a given property can assist in determining whether chemical constituents may have been used or are present on a particular parcel. Current land use records, as typically supplied by local governmental agencies may also provide environmental professionals with additional information regarding target area for potential contamination.

Based on a reconnaissance of the project corridor and immediate surrounding area, existing land use on Bird Key includes a municipal park (Bird Key Park) along the north shore of Bird Key, and single-family residential property along the south side of the corridor. Existing land use on Coon Key includes the Sarasota Yacht Club (SYC) along with multi-family living at Plymouth Harbor and Sarasota Harbour. Present-day land use along the project corridor and surrounding area are described in greater detail later in this report.

# 3.0 HYDROGEOLOGIC SETTING

## 3.1 Geography

Sarasota County is located along the west side of peninsular Florida and is relatively flat. The ground surface along the project corridor ranges from about 4 to 7 feet above mean sea level (msl) (**Figure 3-1**), not including the elevated pavement of the twin spans of the 2-lane bridges.

## 3.2 Geologic Overview

According to the Geologic Map of the State of Florida (FGS Map Series 146, 2001), the project right-of-way lies within a mapped area identified as **Holocene sediments** (map symbol Qh). According to the FGS, Holocene sediments in Florida occur near the present coastline at elevations generally less than 5 feet (1.5 meters). The sediments include quartz sands, carbonate sands and muds, and organics. Collectively, these surficial soils and sediments overlay the Tamiami Formation of Pliocene age and elements of the Hawthorn Group (Miocene age). Portions of the Hawthorn Group typically include laterally discontinuous lenses that consist of permeable carbonate sediments that are informally referred to as the "intermediate aquifer". Along the west flank of Florida, the Hawthorn group is underlain by the Suwannee Limestone (Oligocene) and Avon Park (Eocene). These thick, laterally continuous formations serve as a significant groundwater resource for Florida, including Sarasota County. The Floridan Aquifer System is generally recognized as including the Suwannee Limestone (where present), along with the Avon Park Formation.

## 3.3 Hydrogeologic Overview

The surficial aquifer within this project area consists of saturated unconsolidated sands. Locally, the surficial aquifer is of limited value with regard to water supply. Generally, the surficial aquifer is not considered as a resource for municipal drinking water. The Floridan Aquifer is comprised of several massive limestone formations, and represents a significant groundwater resource for drinking water, irrigation, agricultural, and industrial purposes. According to recent potentiometric surface maps published by the Southwest Florida Water Management District, the potentiometric surface of the Floridan Aquifer is about 2 to 3 feet above mean sea level. The vertical hydraulic gradient in the project corridor is negligible. No site-specific data was collected for the purposes of this CSER.

## 3.4 Soil Survey

As mapped by the United States Department of Agriculture, Natural Resources Conservation Service (NRCS; formerly the Soil Conservation Service, or SCS) two (2) soil types were identified along the project corridor (**Figure 3-2**). On both Bird Key and Coon Key, these soil types were identified as **Canaveral fine sand**, **0 to 5 percent slopes** (map symbol 6) and **St. Augustine fine sand** (map symbol 39).

Figure 3-1 Topographic Map



Source: GIS Information (ESRI), Soils Information (SCS/USGS)



Figure 3-2 NRCS/USDA Soils Map

Source: GIS Information (ESRI), Soils Information (SCS/USGS)

According to the USDA – SCS report written for Sarasota County, Canaveral fine sand is nearly level, somewhat poorly drained to moderately well drained soil found on low dune-like ridges and side slopes bordering sloughs and mangrove swamps with smooth to convex slopes. The soil profile typically consists of an approximate 7-inch thick dark gray to gray fine sand with up to 10% shell content. The underlying soils are comprised of light gray, yellowish brown, pale brown to light gray fine sand with up to 40% shell content. The (pre-development) water table ranges from about 12 to 40 inches below ground surface. Permeability is very rapid and available water capacity is very low.

The USDA – SCS also reports that St. Augustine fine sand is found on former tidal areas, marine terrace flats and rises, generated from sandy mine spoil or earthy fill. The typical soil profile is comprised of fine sand to a depth of 80 inches below ground surface (bgs) and is generally somewhat poorly drained. The reported depth to water ranges from about 18 to 36 inches bgs, and the available water storage is reported as being low. Soils may include brown to gray fine sand and sandy clay loam with variable shell content.

# 4.0 LEVEL I CSER METHODOLOGY

## 4.1 Overview

The methodology for this Level I CSER included the following tasks:

- Document review using Sarasota County Property Appraiser database;
- Review of governmental regulatory databases for permits, reports, and/or violations associated with environmental issues;
- Review of environmental database resources maintained by the FDOT Efficient Transportation Decision Making – Environmental Screening Tool (ETDM – EST);
- Review of Contamination Locator Map (CLM), as maintained by the Florida Department of Environmental Protection (FDEP);
- Obtaining and reviewing historical aerial photographs, topographic maps and soil surveys to evaluate historic land use, specifically as it pertains to the potential for whether soil and/or groundwater quality may have been affected;
- Conduct a visual survey of the project corridor to verify information obtained from the governmental environmental database review and establish current land use; and,
- Determine the potential for whether soil and/or groundwater quality at properties within the project corridor may have been affected and assigning a risk rating for each such property as classified by the FDOT (i.e. NO, LOW, MEDIUM, or HIGH risk).

## 4.2 Regulatory Agency Database Review

An environmental database search was requested from Environmental Data Resources, Inc. (EDRI) to identify sites along, and in close proximity to the project corridor, and whether these sites may be associated with suspected or documented use, storage, or release of chemicals and compounds that may affect soil and/or groundwater quality. The regulatory review of federal, state, and local environmental records uses an integrated geographic information database. The search was conducted as a preliminary screening tool to identify facilities that are registered with various environmental agencies. A copy of the Environmental Data Report (EDR) that was provided by EDRI is included in **Appendix A**. Results of the are presented in **Table 4-1**.

Environmental Database Summary				
Site Identification				Detabase Listings
CSER	EDR	Name	Address	Database Listings
6	1	Sarasota Yacht Club	1100 John Ringling Blvd	LUST, UST, Fin. Assure
7	2	Plymouth Harbor	700 John Ringling Blvd	UST, AST, Asbestos, Fin. Assure NPDES
9	3	Harris Residence	243 Robin Drive	UST, LUST
Nataa				

 Table 4-1

 Environmental Database Summary

Notes:

Environmental Data Report (EDR) included in Appendix A.CSER Site ID numbers correspond with photos included in Appendix G.AST:Aboveground Storage TankFin. Assure:Demonstration of Financial Assurance to FDEPLUST:Leaking Underground Storage TankNPDES:National Pollution Discharge Elimination SystemUST:Underground Storage Tank

## 4.3 Supplemental Regulatory Database Review

In addition to the regulatory agency database review that was completed using the EDR, a supplemental review of available FDEP records was completed using the Public Access Portal, Oculus Document Management System. Select documents that were obtained from this review are summarized below, and are included in **Appendix B**.

## EDR Site No. 1. Sarasota Yacht Club, 1100 John Ringling Boulevard

FDEP FIN 58-8516507. Former UST's located adjacent to southern end of former in-ground swimming pool, located about 300 feet south of Project Corridor ROW. The SYC was demolished and re-built in 2009 (see Photos 7A, 7B & 7C); this work included removing the inground swimming pool and building a new pool at the north end. The location of where the original UST's were located was south of the original in-ground pool (Photo 7C, 2006 and 2019). Documents on file with the FDEP show that "during 2002, a 2,000-gallon gasoline underground storage tank (UST) and a 4,000-gallon diesel UST were removed at the SYC, and replaced by a single 12,000-gallon gasoline UST." During the closure of these UST's a petroleum discharge was discovered and reported to the Sarasota County Environmental Services (SCES). Following a contamination assessment, consultants for the SYC recommended that the soil and groundwater that had been affected by the petroleum release be excavated and disposed of, which was completed by 2008. On August 1, 2008, the FDEP issued a Site Rehabilitation Completion Order (SRCO) stating that the SYC is "released from any further obligation to conduct site rehabilitation at the facility for petroleum product contamination associated with the discharge...". The tank registration documents show that the SYC currently owns and operates a single 12,000-gallon 2-chamber UST that stores diesel (dockside) and unleaded gasoline

(clubhouse side). This tank is situated near the location of the tanks that were removed in 2008, about 350 feet south of the Project Corridor ROW. The present-day location of the UST is less than 20 feet from Sarasota Bay; the direction of groundwater flow in the ephemeral water table / surficial aquifer is likely toward the Bay, away from the project corridor. The most recent document readily available through the FDEP, as dated 12-April-2018 states that the facility is "in compliance" with regards to requirements for petroleum storage systems. The environmental work that has been completed at the SYC with regards to the former and new UST does not appear to be listed or identified in either FDOT's ETDM – EST, or on FDEP's Contamination Locator Map (CLM), as discussed below.

## EDR Site No. 2. Plymouth Harbor, 700 John Ringling Boulevard

**FDEP FIN 58-9500095**. Plymouth Harbor facilities includes a diesel-powered emergency generator, located about 350 feet south of Project Corridor ROW. The generator was originally supplied with diesel fuel stored in a 2,000-gallon UST that was replaced in 1997 with a 3,000-gallon above-ground storage tank (AST). Ultimately, the facility expanded the fuel storage capacity with the installation of an 8,000-gallon AST in September 2018. Inspection records and documents on file with the FDEP show that there have not been reported leaks or releases, and that the facility has been in compliance for quite some time. With regards to the NPDES listing for this property, there was a series of stormwater retention ponds that collect stormwater runoff from the paved parking areas. These features are shown in **Photos 8A, 8B, 8C & 8D**. Overflow from these ponds does not appear to flow onto the project corridor. This property does not appear in either FDOT's ETDM – EST, or in FDEP's CLM, as discussed below.

## EDR Site No. 3. Harris Residence – 243 Robin Drive

**FDEP FIN 58-9401473**. Documents on file with the FDEP show that in May 1994 a single 300gallon home heating oil UST was removed and disposed of. About 12 years later, laboratory analysis of select soil samples showed fuel-affected soil in the back yard. The soil was apparently removed shortly thereafter. In a 1-page status report dated July 2008, it is reported that the facility (UST) has been removed, a cleanup had been completed, and that there are no further pending issues regarding this matter (**Photos 5A & 5B**). The environmental work that has been completed at this property with regards to the former UST does not appear to be listed or identified in either FDOT's ETDM – EST, or on FDEP's Contamination Locator Map (CLM), as discussed below.

## 4.4 FDEP Contamination Locator Map (CLM)

The Contamination Locator Map (CLM), as maintained by the FDEP was reviewed for mapped sites along or in close proximity to the project corridor. Select documents and maps opened with the CLM are included in **Appendix B**. A review of FDEP's CLM showed that there are no mapped sites or properties along the project corridor or within 500 feet of the ROW. The nearest mapped sites identified using the CLM include:

Jack Graham, Inc. at 2 Marina Plaza • FDEP Facility ID No. 64182742 Located about 1.1 miles east of eastern end of project corridor Isolated from project corridor by Sarasota Bay No documents listed or included in Oculus database • Foxy Lady (Former Chevron) at 481 John Ringling Blvd FDEP Facility ID No. 9700801 Located about 0.3-mile west of western end of project corridor Site is located on St. Armands Key On-going groundwater monitoring program Separated from project corridor by saltwater channel Petroleum discharge dated June 1997; Current Priority Score identified as 07; Most recent document dated August 5, 2020 regarding request for additional documentation, mapping presenting petroleum-based analytes. Exxon – St. Armands at 1 N. Blvd of Presidents FDEP Facility ID No. 8520819 Located about 0.4-mile west of western end of project corridor Site is located on northwest quadrant of St. Armands Circle Separated from project corridor by saltwater channel Site identified as participating in Low-Scored Site Initiative (LSSI)

Most recent groundwater quality assessment report dated February 2012

## 4.5 FDOT Efficient Transportation Decision Making (ETDM)

As maintained by the FDOT, the ETDM was used to provide an overview of the project corridor, and to access to the Environmental Screening Tool (EST). The map developed by FDOT showing the EST is included in **Appendix B**. As shown, there are no mapped sites identified on the ETDM – EST map along the project corridor.

## 4.6 Interviews

At the time of the site reconnaissance, contact was made with management of Plymouth Harbor regarding the UST and AST listings reported in the EDR database. According to the EDR, a 2,000-gallon UST was installed in June 1987, and was replaced with a 3,000-gallon AST in May 1997. The 3,000-gallon AST was replaced again in August 2018 (**Photo 8C**) with a substantially larger AST. On January 27, 2020 a brief follow-up interview was held via telephone with management of Plymouth Harbor. When management was asked, there were no known issues regarding the closure of either the 2,000-gallon UST or the 3,000-gallon AST. The reason given for installing a substantially larger AST was reportedly to accommodate recent changes to state law regarding fuel reserves required for emergency generators at residential facilities in the event of prolonged power outages. Insofar as the management at Plymouth Harbor was aware, there are no outstanding issues regarding the closed UST or either AST.

## 4.7 Historical Aerial Photographs

Historical aerial photographs were obtained from three (3) sources included in the EDRI, and one additional source:

- EDRI 1948 through 2017 as provided by the USDA, FDOT, and USGS
- Google Earth 2006, 2009, and 2019 (current)

Historical aerial photographs of the project corridor and surrounding area included in the EDRI are included in **Appendix C**. Both historical and current land use along the project right-of-way were reviewed in determining the risk for whether soil and/or ground water quality may have been affected, as summarized in **Table 4-2**, below.

Year	Color / Condition	Description / Interpretation
1948	Black & White Fair	Single-span bridge between Bird Key and Coon Key has already been built and is in service. There is a boat launch and dock at the location of the Sarasota Yacht Club (SYC). The Boat launch includes one small building and a relatively short single dock that extends into the bay.
1957	Black & White Fair	Single-span bridge still present. Land development has begun on Bird Key. Boat launch on Coon Key has been expanded to include a second dock that extends out into the bay, along with slips along the waterfront; this property now more closely resembles a marina as opposed to a boat launch. Saltwater canals have also been cut into Coon Key.
1962	Black & White Good	Original single-span bridge has been removed and replaced with twin 2-lane spans. Single-family residential properties have been built along south side of ROW on Bird Key. Vegetation growth on Coon Key. No appreciable change in the configuration of the marina.
1969	Black & White Good	No changes evident to Little Ringling Bridge since previous image. Substantial single-family residential development on Bird Key. Multi-family residential complex has been built along northern and southern sides of Coon Key. There is also a tall residential building on the southern tip of Coon Key. The configuration and size of the docks and the buildings at the SYC have been enlarged.
1971	Black & White Good	No changes are evident to Little Ringling Bridge since previous image. Unpaved beach access and vehicle pathways are visible on the north shore of Bird Key. The docks at the SYC have been lengthened and are of the same size as one another.
1979	Black & White Poor / Grainy	No changes are evident to Little Ringling Bridge or in land use on Bird Key or Coon Key since previous image.

 Table 4-2

 Aerial Photo/Historical Land Use Review

Year	Color / Condition	Description / Interpretation
1985	Black & White Good	No changes are evident to Little Ringling Bridge since previous image. A third dock has been added at the marina on Coon Key. The vehicle paths on the north shore of Bird Key have been paved.
1998	Black & White Good	No changes are evident to Little Ringling Bridge or to land use
1998	False Color Fair to Poor	on Bird Key or Coon Key since previous image.
2007	Color Fair	
2010	Color (light) Fair	
2013	Color (light) Fair	No changes are evident to Little Ringling Bridge or to land use on Bird Key or Coon Key since 1998.
2017	Color Good	
2019	Color / Good See Photo 1 – Appendix G	

1) Historical aerial photos are included in Appendix C.

## 4.8 Sanborn Fire Insurance Maps

Sanborn Fire Insurance Maps were obtained from EDRI (**Appendix D**). As reported by EDRI, the complete holdings of the Sanborn Library collection have been searched; there are no buildings and/or structures identified along the project corridor within the mapped areas on historical Sanborn Fire Insurance Maps. Several structures do exist however, within the unmapped portions of the corridor.

## 4.9 FDOT Bridge Structure Survey / Sampling

Asbestos surveys were conducted at Bridge Number 170951 (Ringling Bridge) eastbound and Bridge Number 17002 (Little Ringling Bridge) westbound, along SR 789 over Coon Key Waterway (**Photos 6A, 6B & 6C**). The asbestos survey was performed to determine the presence, if any, of asbestos-containing materials (ACM). In addition to the asbestos survey, sampling of the bridge paint coatings was conducted with laboratory analysis for heavy metals. No regulated asbestos-containing materials were found within the materials tested at Bridge Number 170951 or Bridge Number 170022, located along SR 789 over the Coon Key Waterway. The presence of metals in the paint coatings was identified on the pile jackets on both bridge structures. Renovation or demolition of the bridge will present a potential exposure to workers and will require methods to ensure that workers are not exposed to levels above the OSHA permissible exposure limits in accordance with 29 CFR Subpart Z, and to ensure that

any regulated metals are not spread to uncontrolled areas.

Complete copies of the Asbestos Survey and Metals-Based Paint Coating Sampling Reports for Bridge Number 170022 and Bridge Number 170951 are provided in **Appendix E**.

## 4.10 Site Reconnaissance

The current land use along the project corridor was evaluated during a visual inspection on January 25, 2020. The reconnaissance of the project corridor included a systematic visual inspection of each parcel of land, documenting land use and conditions commonly associated with land use that may affect soil and/or groundwater quality. Typical physical indicators of land use that may affect soil and/or groundwater quality include: underground or aboveground storage tanks, fill ports, and/or vent pipes; industrial drums; chemical containers; monitor wells; refuse; signs of illicit dumping; solid waste; distressed vegetation; and/or noxious odors. Certain types of businesses are commonly associated with use of materials that, if released or discharged may affect soil and/or groundwater quality either on their property or the project corridor. These facilities may include: vehicle re-fueling stations; dry cleaning facilities; agriculture support operations; landfills; stormwater percolation/retention ponds, paint stores; and so forth.

During the site reconnaissance, the actual locations of properties that were identified in the local, state, and federal environmental agency database searches were verified either way. A summary of properties identified during the site reconnaissance are included in **Appendix F**. For ease of discussion, these properties are identified by estimated Mile Post (MP) from Bird Key Drive (MP 1.206) to Sarasota Harbour West (MP 1.947) and address. Seven properties, areas, and/or structures along the Project Corridor were identified during the site reconnaissance, as summarized and described in **Table 4-3** and shown on **Figure 4-1**. Select site photos documenting current land use of these properties are included in **Appendix G**. Photo locations and orientations are shown on **Figure 4-2**.

Site Identification	Location and Description		
1. Bird Key Park	Along northwestern side of Bird Key; MP 1.206; Municipal park located at northern end of project corridor ( <b>Photo 2</b> )		
2. SR 789	Sidewalk refurbishment ( <b>Photo 8A</b> ) & staging area ( <b>Photo 4</b> ). The staging area was located on the causeway between Coon Key and St. Armands Key, and is not within the project corridor.		
3. Sarasota Harbour	Multi-family Residential Townhouses ( <b>Photo 5</b> ) On northwest side of Coon Key; MP 1.583 to MP 1.947 Southern entrance represents southern end of project corridor		
4. Harris Residence	UST listed in EDR at 243 Robin Drive; located > 1,000 feet from project corridor. ( <b>Photo 9</b> )		

 Table 4-3


 Project Corridor Reconnaissance Summary

5. SR 789 Bridges	FDOT Structure No. 170022 ( <b>Photo 3</b> ) FDOT Structure No. 170951
6. Sarasota Yacht Club	1100 John Ringling Blvd; Private yacht club. Includes UST about 300 feet from project corridor. ( <b>Photo 6</b> )
7. Plymouth Harbor	700 John Ringling Blvd; 20-story condominium, including AST about 350 feet from project corridor. ( <b>Photo 7</b> )

Figure 4-1 Site Locations



Figure 4-2 Land Use and Photo Log Summary



SR 789 (John Ringling Causeway) PD&E Study FPID(S): 436680-1-22-01 & 436680-1-32-01 Draft Contamination Screening Evaluation Report May 2023

# 5.0 SITE IMPACT EVALUATIONS

Based on data collected from the document review, aerial photographs detailing historical land use, and the site reconnaissance, the risks of potential impacts to soil and/or groundwater quality have been rated along the project right-of-way. As identified in Part 2, Chapter 20 of the PD&E Manual issued by the FDOT dated July 2020, the standardized rating system devised for evaluating the risk to soil and/or groundwater quality along the project right-of-way includes four (4) levels of risk, as described in greater detail below. This system expresses the degree of concern for the potential of contamination issues. Known conditions may not necessarily present a "high" cause for concern if regulatory agencies are aware. Also, actual soil and/or groundwater quality issues may vary widely between what is on the adjoining property and the project right-of-way. Groundwater quality issues are subject to the rate, direction of groundwater flow, as well as the degree of contamination and mobility of specific chemicals that are dissolved in the groundwater.

Any site that is recognized by the FDEP as being "contaminated" due to the documented presence of impacts will be rated as at least a "medium" or "high" because these sites will likely affect National Pollutant Discharge Elimination Systems (NPDES) dewatering efforts within 500 feet of the site. Such sites can create a contamination-related impact to construction by requiring additional efforts related to permitting processes, effluent treatment, and discharge monitoring.

## NO Risk Site

A review of available information on the property and a review of the conceptual or design plans indicates there is no potential contamination impact to the project. It is possible that contaminants have been handled on the property. However, findings from the Level I evaluation indicate that contamination impacts are not expected.

CSER Site 1. Bird Key Municipal Park – Site is rated as NO RISK due to no history of any hazardous or petroleum-related products on-site (**Photos 2A & 2B**).

CSER Site 2. Sidewalk Refurbishing & Staging Area - Site is rated as NO RISK due to no history of any hazardous or petroleum-related products on-site (**Photos 3A, 3B & 3C)**.

CSER Site 3. Sarasota Harbour East & West (Townhouses) – Site is rated as NO RISK due to no history of any hazardous or petroleum-related products on-site (**Photos 4A & 4B**).

CSER Site 4. Harris Residence, 243 Robin Dr. – Site contained one 300-gallon underground storage tank for storage of fuel oil for on-site heat. A discharge was reported in 1994 due to the presence of soil contamination. Cleanup status listed in 2006 is No Further Action (NFA) required. The tank is currently listed as 'removed''. Site is rated as NO Risk due to the absence of petroleum product and the distance to the ROW exceeds 1,000 feet (**Photos 5A & 5B**).

## LOW Risk Site

A review of available information indicates that past or current activities on the property have an ongoing contamination issue; the site has a hazardous waste generator identification (ID) number, or the site stores, handles or manufactures hazardous materials. However, based on the review of conceptual or design plans and/or findings from the Level I evaluation, it is not likely that there would be soil any contamination impacts to the project.

CSER Site 6. Sarasota Yacht Club (SYC), 1100 John Ringling Blvd.- storage of marine/coastal fuel, with report of former discharge of unleaded gasoline in 2002. Impact was to local groundwater. Site was remediated and issued a Site Rehabilitation Completion Order by the FDEP in 2008. Site is rated as LOW Risk due to the presence of petroleum product and proximity of underground storage tanks to ROW (Photos **7A**, **7B & 7C**).

CSER Site 7. Plymouth Harbor, 20-story condo, 700 Ringling Blvd.- presence of aboveground storage tank containing ultra-low sulfur diesel. System was placed in service in 2018. No report of discharge to soil or groundwater. Site also contains an abandoned in-place underground storage tank. Site is rated as LOW Risk due to the presence of petroleum product and proximity of underground storage tanks to ROW (**Photos 8A, 8B, 8C & 8D**).

## **MEDIUM Risk Site**

After a review of conceptual or design plans and findings from a Level I evaluation, a potential contamination impact to the project has been identified. If there is insufficient information (such as regulatory records or site historical documents) to make a determination as to the potential for contamination impact, and there is reasonable suspicion that contamination may exist, the property should be rated at least as a "Medium". Properties used historically as gasoline stations and which have not been evaluated or assessed by regulatory agencies, sites with abandoned in place underground petroleum storage tanks, or currently operating gasoline stations should receive this rating.

CSER Site 5. S.R. 789 Ringling Bridge Structures - Metals-based paint coatings were identified on the pile jackets of both bridge structures (170022 and 170951), which will pose a potential exposure for workers. Renovation or demolition activities will require methods to avoid exposure to levels above the OSHA permissible exposure limits in accordance with 29 CFR Subpart Z, and to ensure that any regulated metals are not spread to uncontrolled areas (**Photos 6A, 6B & 6C**).

## HIGH Risk Site

After a review of all available information and conceptual or design plans, there is appropriate analytical data that shows contamination will substantially impact construction activities, have implications to ROW acquisition or have other potential transfer of contamination related liability to the FDOT.

No properties or structures are within the project area that are rated as HIGH RISK.

# 6.0 CONCLUSIONS

## Project Impacts Summary

Using data collected prior to the field inspection with regards to known permits and/or releases, along with observations made during the field inspection, the following matrix of potential effects to soil and/or groundwater quality was developed for the project corridor. The Level I CSER that was conducted showed a total of seven (7) sites within specified distances of the edge of the project right-of-way, as summarized below, in **Table 5-1**.

Risk	Number of Sites	Site Identification & Description	Source to R/W Distance
		Bird Key Municipal Park	Adjacent
	4	Sarasota Harbour East & West (Townhomes)	Adjacent
No		Sidewalk refurbishment & staging area	Within
		Harris Residence, 243 Robin Dr.	>1,000 feet
		Sarasota Yacht Club (SYC), 1100 John Ringling Blvd	300 feet
Low	2	Plymouth Harbor, 20-story condominium at 700 John Ringling Blvd	350 feet
Medium	1	SR 789 Ringling Bridge (both spans)	Within
High	0	No Properties / Structures Identified	Within

Table 6-1 Level I CSER Matrix Summary

No estimated costs are applicable for the four (4) sites designated as No risk, and no remediation costs are estimated for the two (2) sites designated as Low risk due to the existing conditions of both sites. Only CSER site # 5, Bridge 170022 and Bridge 170951, will require remediation measures during retrofitting or demolition activities. Remediation will include the proper removal and disposal of all metal-based paint coatings if disturbed, and dust control during demolition of the concrete structure. Remediation costs are estimated to range from \$25,000 to \$50,000.

# 7.0 RECOMMENDATIONS

Based on the conclusions of the Level I CSER, the following recommendations have been made with regards to potential impacts along the project corridor and right-of-way:

Only one site is evaluated above **NO** and **LOW** risks. The twin 2-lane concrete bridge spans of SR 789 between Bird Key and Coon Key (CSER Site No. 5), represents a **MEDIUM Risk** within the context of this CSER. Although neither bridge (northbound or southbound spans) were identified in the EDR, on FDOT's ETDM-EST, or FDEP's CLM, these structures have been identified as containing heavy metals in metals-based coatings (MBC's). The presence of metals was identified on the pile jackets on both bridge structures.

Renovation or demolition of the bridge will present a potential exposure to workers and will require methods to ensure that workers are not exposed to levels above the OSHA permissible exposure limits in accordance with 29 CFR Subpart Z, and to ensure that any regulated metals are not spread to uncontrolled areas.

# CSER APPENDIX A

## **Little Ringling Bridge**

SR 789 Bird Key Dr to Sarasota Harbor West Sarasota, FL 34236

Inquiry Number: 5931196.2s January 10, 2020

# The EDR Radius Map<sup>™</sup> Report with GeoCheck®



6 Armstrong Road, 4th floor Shelton, CT 06484 Toll Free: 800.352.0050 www.edrnet.com

FORM-LBD-DVV

## TABLE OF CONTENTS

### SECTION

#### PAGE

Executive Summary	ES1
Overview Map	2
Detail Map	3
Map Findings Summary	4
Map Findings	8
Orphan Summary	34
Government Records Searched/Data Currency Tracking	GR-1

## **GEOCHECK ADDENDUM**

Physical Setting Source Addendum	A-1
Physical Setting Source Summary	A-2
Physical Setting Source Map	A-6
Physical Setting Source Map Findings	A-7
Physical Setting Source Records Searched	PSGR-1

*Thank you for your business.* Please contact EDR at 1-800-352-0050 with any questions or comments.

#### **Disclaimer - Copyright and Trademark Notice**

This Report contains certain information obtained from a variety of public and other sources reasonably available to Environmental Data Resources, Inc. It cannot be concluded from this Report that coverage information for the target and surrounding properties does not exist from other sources. NO WARRANTY EXPRESSED OR IMPLIED, IS MADE WHATSOEVER IN CONNECTION WITH THIS REPORT. ENVIRONMENTAL DATA RESOURCES, INC. SPECIFICALLY DISCLAIMS THE MAKING OF ANY SUCH WARRANTIES, INCLUDING WITHOUT LIMITATION, MERCHANTABILITY OR FITNESS FOR A PARTICULAR USE OR PURPOSE. ALL RISK IS ASSUMED BY THE USER. IN NO EVENT SHALL ENVIRONMENTAL DATA RESOURCES, INC. BE LIABLE TO ANYONE, WHETHER ARISING OUT OF ERRORS OR OMISSIONS, NEGLIGENCE, ACCIDENT OR ANY OTHER CAUSE, FOR ANY LOSS OF DAMAGE, INCLUDING, WITHOUT LIMITATION, SPECIAL, INCIDENTAL, CONSEQUENTIAL, OR EXEMPLARY DAMAGES. ANY LIABILITY ON THE PART OF ENVIRONMENTAL DATA RESOURCES, INC. IS STRICTLY LIMITED TO A REFUND OF THE AMOUNT PAID FOR THIS REPORT. Purchaser accepts this Report "AS IS". Any analyses, estimates, ratings, environmental risk levels or risk codes provided in this Report are provided for illustrative purposes only, and are not intended to provide, nor should they be interpreted as providing any facts regarding, or prediction or forecast of, any environmental risk for any property. Only a Phase I Environmental St Assessment performed by an environmental professional can provide information regarding the environmental risk for any property. Additionally, the information provided in this Report is not to be construed as legal advice.

Copyright 2020 by Environmental Data Resources, Inc. All rights reserved. Reproduction in any media or format, in whole or in part, of any report or map of Environmental Data Resources, Inc., or its affiliates, is prohibited without prior written permission.

EDR and its logos (including Sanborn and Sanborn Map) are trademarks of Environmental Data Resources, Inc. or its affiliates. All other trademarks used herein are the property of their respective owners.

A search of available environmental records was conducted by Environmental Data Resources, Inc (EDR). The report was designed to assist parties seeking to meet the search requirements of EPA's Standards and Practices for All Appropriate Inquiries (40 CFR Part 312), the ASTM Standard Practice for Environmental Site Assessments (E 1527-13), the ASTM Standard Practice for Environmental Site Assessments for Forestland or Rural Property (E 2247-16), the ASTM Standard Practice for Limited Environmental Due Diligence: Transaction Screen Process (E 1528-14) or custom requirements developed for the evaluation of environmental risk associated with a parcel of real estate.

#### TARGET PROPERTY INFORMATION

#### ADDRESS

SR 789 BIRD KEY DR TO SARASOTA HARBOR WEST SARASOTA, FL 34236

#### COORDINATES

Latitude (North):	27.3237640 - 27° 19' 25.55"
Longitude (West):	82.5674170 - 82° 34' 2.70"
Universal Tranverse Mercator:	Zone 17
UTM X (Meters):	344922.1
UTM Y (Meters):	3023101.0
Elevation:	4 ft. above sea level

#### USGS TOPOGRAPHIC MAP ASSOCIATED WITH TARGET PROPERTY

Target Property Map: Version Date: 5676072 SARASOTA, FL 2012

#### **AERIAL PHOTOGRAPHY IN THIS REPORT**

Portions of Photo from: Source:

20150510, 20150511 USDA

# <u>Target Property Address:</u> SR 789 BIRD KEY DR TO SARASOTA HARBOR WEST SARASOTA, FL 34236

Click on Map ID to see full detail.

## 

MAP ID	SITE NAME	ADDRESS	DATABASE ACRONYMS	RELATIVE ELEVATION	DIST (ft. & mi.) DIRECTION
1	SARASOTA YACHT CLUB	1100 JOHN RINGLING B	LUST, UST, Financial Assurance	Higher	20, 0.004, SW
2	PLYMOUTH HARBOR ON S	700 JOHN RINGLING BL	UST, AST, ASBESTOS, Financial Assurance, NPDES	Higher	488, 0.092, SW
3	HARRIS RESIDENCE	243 ROBIN DR	LUST, UST	Higher	1166, 0.221, East

#### TARGET PROPERTY SEARCH RESULTS

The target property was not listed in any of the databases searched by EDR.

#### DATABASES WITH NO MAPPED SITES

No mapped sites were found in EDR's search of available ("reasonably ascertainable ") government records either on the target property or within the search radius around the target property for the following databases:

#### STANDARD ENVIRONMENTAL RECORDS

#### Federal NPL site list

NPL	_ National Priority List
	Proposed National Priority List Sites
NPL LIENS	- Federal Superfund Liens

#### Federal Delisted NPL site list

Delisted NPL\_\_\_\_\_ National Priority List Deletions

#### Federal CERCLIS list

FEDERAL FACILITY\_\_\_\_\_\_ Federal Facility Site Information listing SEMS\_\_\_\_\_\_ Superfund Enterprise Management System

#### Federal CERCLIS NFRAP site list

SEMS-ARCHIVE...... Superfund Enterprise Management System Archive

#### Federal RCRA CORRACTS facilities list

CORRACTS..... Corrective Action Report

#### Federal RCRA non-CORRACTS TSD facilities list

RCRA-TSDF..... RCRA - Treatment, Storage and Disposal

#### Federal RCRA generators list

RCRA-LQG	RCRA - Large Quantity Generators
RCRA-SQG	RCRA - Small Quantity Generators
RCRA-VSQG	RCRA - Very Small Quantity Generators (Formerly Conditionally Exempt Small Quantity
	Generators)

#### Federal institutional controls / engineering controls registries

LUCIS...... Land Use Control Information System

US ENG CONTROLS	Engineering Controls Sites List
US INST CONTROL	Sites with Institutional Controls

#### Federal ERNS list

ERNS\_\_\_\_\_ Emergency Response Notification System

#### State- and tribal - equivalent CERCLIS

SHWS\_\_\_\_\_ Florida's State-Funded Action Sites

#### State and tribal landfill and/or solid waste disposal site lists

SWF/LF..... Solid Waste Facility Database

#### State and tribal leaking storage tank lists

LAST	Leaking Aboveground Storage Tank Listing
INDIAN LUST	Leaking Underground Storage Tanks on Indian Land

#### State and tribal registered storage tank lists

FF TANKS	Federal Facilities Listing
FEMA UST	Underground Storage Tank Listing
	. Underground Storage Tanks on Indian Land
TANKS	Storage Tank Facility List

#### State and tribal institutional control / engineering control registries

ENG CONTROLS	Institutional Controls Registry
INST CONTROL	Institutional Controls Registry

#### State and tribal voluntary cleanup sites

VCP...... Voluntary Cleanup Sites INDIAN VCP....... Voluntary Cleanup Priority Listing

#### State and tribal Brownfields sites

BROWNFIELDS\_\_\_\_\_ Brownfields Sites Database

#### ADDITIONAL ENVIRONMENTAL RECORDS

#### Local Brownfield lists

US BROWNFIELDS..... A Listing of Brownfields Sites

#### Local Lists of Landfill / Solid Waste Disposal Sites

SWRCY	Recycling Centers
INDIAN ODI	Report on the Status of Open Dumps on Indian Lands
ODI	Open Dump Inventory
DEBRIS REGION 9	Torres Martinez Reservation Illegal Dump Site Locations
	Open Dumps on Indian Land

#### Local Lists of Hazardous waste / Contaminated Sites

US HIST CDL	Delisted National Clandestine Laboratory Register
PRIORITYCLEANERS	. Priority Ranking List
FI Sites	_ Sites List
US CDL	National Clandestine Laboratory Register
PFAS	PFOS and PFOA stand for perfluorooctane sulfonate and perfluorooctanoic acid

#### Local Land Records

LIENS 2\_\_\_\_\_ CERCLA Lien Information

#### Records of Emergency Release Reports

HMIRS	Hazardous Materials Information Reporting System
SPILLS	Oil and Hazardous Materials Incidents
SPILLS 90	SPILLS 90 data from FirstSearch
SPILLS 80	. SPILLS 80 data from FirstSearch

#### Other Ascertainable Records

RCRA NonGen / NLR	RCRA - Non Generators / No Longer Regulated
FUDS	Formerly Used Defense Sites
	Department of Defense Sites
	State Coalition for Remediation of Drycleaners Listing
	Financial Assurance Information
EPA WATCH LIST	
2020 COR ACTION	2020 Corrective Action Program List
	Toxic Substances Control Act
	Toxic Chemical Release Inventory System
SSIS	Section 7 Tracking Systems
ROD	
RMP	
RAATS	RCRA Administrative Action Tracking System
PRP	Potentially Responsible Parties
	PCB Activity Database System
	Integrated Compliance Information System
	FIFRA/ TSCA Tracking System - FIFRA (Federal Insecticide, Fungicide, & Rodenticide
	Act)/TSCA (Toxic Substances Control Act)
MLTS	Material Licensing Tracking System
	Steam-Electric Plant Operation Data
	Coal Combustion Residues Surface Impoundments List
PCB TRANSFORMER	PCB Transformer Registration Database
RADINFO	Radiation Information Database
HIST FTTS	- FIFRA/TSCA Tracking System Administrative Case Listing
DOT OPS	
	Superfund (CERCLA) Consent Decrees
INDIAN RESERV	
FUSRAP	Formerly Utilized Sites Remedial Action Program
UMTRA	
LEAD SMELTERS	
US AIRS	Aerometric Information Retrieval System Facility Subsystem
US MINES	
ABANDONED MINES	Abandoned Mines

ECHO.ErUXO.UDOCKET HWC.HaFUELS PROGRAM.EIAIRS.PaASBESTOS.A3CLEANUP SITES.DiDEDB.EtDRYCLEANERS.DiDWM CONTAM.DiFinancial Assurance.FiFL Cattle Dip. Vats.CaRESP PARTY.RaSITE INV SITES.SiTIER 2.TiUIC.U	azardous Waste Compliance Docket Listing PA Fuels Program Registered Listing ermitted Facilities Listing SBESTOS EP Cleanup Sites - Contamination Locator Map Listing thylene Dibromide Database Results rycleaning Facilities WM CONTAMINATED SITES inancial Assurance Information Listing attle Dipping Vats esponsible Party Sites Listing ite Investigation Section Sites Listing ier 2 Facility Listing nderground Injection Wells Database Listing
	astewater Facility Regulation Database

#### EDR HIGH RISK HISTORICAL RECORDS

#### EDR Exclusive Records

EDR MGP	EDR Proprietary Manufactured Gas Plants
	EDR Exclusive Historical Auto Stations
EDR Hist Cleaner	. EDR Exclusive Historical Cleaners

#### EDR RECOVERED GOVERNMENT ARCHIVES

#### **Exclusive Recovered Govt. Archives**

RGA HWS	Recovered Government Archive State Hazardous Waste Facilities List
RGA LF	Recovered Government Archive Solid Waste Facilities List
RGA LUST	Recovered Government Archive Leaking Underground Storage Tank

#### SURROUNDING SITES: SEARCH RESULTS

Surrounding sites were identified in the following databases.

Elevations have been determined from the USGS Digital Elevation Model and should be evaluated on a relative (not an absolute) basis. Relative elevation information between sites of close proximity should be field verified. Sites with an elevation equal to or higher than the target property have been differentiated below from sites with an elevation lower than the target property.

Page numbers and map identification numbers refer to the EDR Radius Map report where detailed data on individual sites can be reviewed.

Sites listed in *bold italics* are in multiple databases.

Unmappable (orphan) sites are not considered in the foregoing analysis.

# **EXECUTIVE SUMMARY**

#### STANDARD ENVIRONMENTAL RECORDS

#### State and tribal leaking storage tank lists

LUST: The Leaking Underground Storage Tank Incident Reports contain an inventory of reported leaking underground storage tank incidents. The data come from the Department of Environmental Protection's PCTO1--Petroleum Contamination Detail Report.

A review of the LUST list, as provided by EDR, and dated 10/28/2019 has revealed that there are 2 LUST sites within approximately 0.25 miles of the target property.

Equal/Higher Elevation	Address	Direction / Distance	Map ID	Page
SARASOTA YACHT CLUB Discharge Cleanup Status: SRCR Facility Status: OPEN Facility-Site Id: 8516507	1100 JOHN RINGLING B SRCR COMPLETE	SW 0 - 1/8 (0.004 mi.)	1	8
HARRIS RESIDENCE Discharge Cleanup Status: NFA - N Facility Status: CLOSED Facility-Site Id: 9401473	<b>243 ROBIN DR</b> NFA COMPLETE	E 1/8 - 1/4 (0.221 mi.)	3	30

#### State and tribal registered storage tank lists

UST: The Underground Storage Tank database contains registered USTs. Shortly after the September 11 event, the DEP was instructed to remove the detail about some of the storage tank facilities in the state from their reports. Federal-owned facilities and bulk storage facilities are included in that set.

A review of the UST list, as provided by EDR, has revealed that there are 3 UST sites within approximately 0.25 miles of the target property.

Equal/Higher Elevation	Address	Direction / Distance	Map ID	Page
SARASOTA YACHT CLUB Database: UST, Date of Governme Tank Status: B Tank Status: U Facility-Site Id: 8516507 Facility Status: OPEN	1100 JOHN RINGLING B ent Version: 10/30/2019	SW 0 - 1/8 (0.004 mi.)	1	8
PLYMOUTH HARBOR ON S Database: UST, Date of Governme Tank Status: A Facility-Site Id: 9500095 Facility Status: OPEN	700 JOHN RINGLING BL ent Version: 10/30/2019	SW 0 - 1/8 (0.092 mi.)	2	17
HARRIS RESIDENCE Database: UST, Date of Governme Tank Status: B Facility-Site Id: 9401473 Facility Status: CLOSED	<b>243 ROBIN DR</b> ent Version: 10/30/2019	E 1/8 - 1/4 (0.221 mi.)	3	30

# **EXECUTIVE SUMMARY**


AST: Shortly after the Sept 11 event, the DEP was instructed to remove the detail about some of the storage tank facilities in the state from their reports. Federal-owned facilities and bulk storage facilities are included in that set.

A review of the AST list, as provided by EDR, has revealed that there is 1 AST site within approximately 0.25 miles of the target property.


Equal/Higher Elevation	Address	Direction / Distance	Map ID	Page
PLYMOUTH HARBOR ON S	700 JOHN RINGLING BL	SW 0 - 1/8 (0.092 mi.)	2	17
Database: AST, Date of Governmer	nt Version: 10/30/2019			
Facility-Site Id: 9500095				
Facility Status: OPEN				
Facility Status: OPEN				

# **EXECUTIVE SUMMARY**

There were no unmapped sites in this report.



		CONTACT:	
LAT/LONG:	Sarasota FL 34236	INQUIRY #:	5931196.2s
	27.323764 / 82.567417	DATE:	January 10, 2020 11:46 am



SITE NAME: Little Ringling Bridge	CLIENT: Madrid Engineering Group, Inc.
ADDRESS: SR 789 Bird Key Dr to Sarasota Harbor West	CONTACT: Scott Nyhof
Sarasota FL 34236	INQUIRY #: 5931196.2s
LAT/LONG: 27.323764 / 82.567417	DATE: January 10, 2020 11:46 am
	Copyright © 2020 EDR, Inc. © 2015 TomTom Rel. 2015.

Database	Search Distance (Miles)	Target Property	< 1/8	1/8 - 1/4	1/4 - 1/2	1/2 - 1	> 1	Total Plotted
STANDARD ENVIRONMEN	TAL RECORDS							
Federal NPL site list								
NPL Proposed NPL NPL LIENS	0.250 0.250 0.250		0 0 0	0 0 0	NR NR NR	NR NR NR	NR NR NR	0 0 0
Federal Delisted NPL si	te list							
Delisted NPL	0.250		0	0	NR	NR	NR	0
Federal CERCLIS list								
FEDERAL FACILITY SEMS	0.250 0.250		0 0	0 0	NR NR	NR NR	NR NR	0 0
Federal CERCLIS NFRA	P site list							
SEMS-ARCHIVE	0.250		0	0	NR	NR	NR	0
Federal RCRA CORRAC	TS facilities lis	st						
CORRACTS	0.250		0	0	NR	NR	NR	0
Federal RCRA non-COR	RACTS TSD fa	acilities list						
RCRA-TSDF	0.250		0	0	NR	NR	NR	0
Federal RCRA generato	rs list							
RCRA-LQG RCRA-SQG RCRA-VSQG	0.250 0.250 0.250		0 0 0	0 0 0	NR NR NR	NR NR NR	NR NR NR	0 0 0
Federal institutional cor engineering controls re								
LUCIS US ENG CONTROLS US INST CONTROL	0.250 0.250 0.250		0 0 0	0 0 0	NR NR NR	NR NR NR	NR NR NR	0 0 0
Federal ERNS list								
ERNS	TP		NR	NR	NR	NR	NR	0
State- and tribal - equiva	alent CERCLIS	ì						
SHWS	0.250		0	0	NR	NR	NR	0
State and tribal landfill a solid waste disposal site								
SWF/LF	0.250		0	0	NR	NR	NR	0
State and tribal leaking	storage tank li	sts						
LAST LUST INDIAN LUST	0.250 0.250 0.250		0 1 0	0 1 0	NR NR NR	NR NR NR	NR NR NR	0 2 0
State and tribal register	ed storage tan	k lists						
FF TANKS	0.250		0	0	NR	NR	NR	0

Database	Search Distance (Miles)	Target Property	< 1/8	1/8 - 1/4	1/4 - 1/2	1/2 - 1	> 1	Total Plotted
FEMA UST UST AST INDIAN UST TANKS	0.250 0.250 0.250 0.250 0.250		0 2 1 0 0	0 1 0 0 0	NR NR NR NR	NR NR NR NR NR	NR NR NR NR	0 3 1 0 0
State and tribal instituti control / engineering co		es						
ENG CONTROLS INST CONTROL	0.250 0.250		0 0	0 0	NR NR	NR NR	NR NR	0 0
State and tribal volunta	ry cleanup sit	es						
VCP INDIAN VCP	0.250 0.250		0 0	0 0	NR NR	NR NR	NR NR	0 0
State and tribal Brownfi	elds sites							
BROWNFIELDS	0.250		0	0	NR	NR	NR	0
ADDITIONAL ENVIRONME	NTAL RECORD	<u>s</u>						
Local Brownfield lists								
US BROWNFIELDS	0.250		0	0	NR	NR	NR	0
Local Lists of Landfill / Waste Disposal Sites	Solid							
SWRCY INDIAN ODI ODI DEBRIS REGION 9 IHS OPEN DUMPS	0.250 0.250 0.250 0.250 0.250 0.250		0 0 0 0	0 0 0 0	NR NR NR NR	NR NR NR NR NR	NR NR NR NR NR	0 0 0 0
Local Lists of Hazardou Contaminated Sites	s waste /							
US HIST CDL PRIORITYCLEANERS FI Sites US CDL PFAS	TP 0.250 0.250 TP 0.250		NR 0 0 NR 0	NR 0 0 NR 0	NR NR NR NR	NR NR NR NR	NR NR NR NR	0 0 0 0
Local Land Records								
LIENS 2	TP		NR	NR	NR	NR	NR	0
Records of Emergency	Release Repo	orts						
HMIRS SPILLS SPILLS 90 SPILLS 80	TP TP TP TP		NR NR NR NR	NR NR NR NR	NR NR NR NR	NR NR NR NR	NR NR NR NR	0 0 0 0
Other Ascertainable Re	cords							
RCRA NonGen / NLR	0.250		0	0	NR	NR	NR	0

Database	Search Distance (Miles)	Target Property	< 1/8	1/8 - 1/4	1/4 - 1/2	1/2 - 1	> 1	Total Plotted
	0.050							
FUDS DOD	0.250 0.250		0 0	0 0	NR NR	NR NR	NR NR	0 0
SCRD DRYCLEANERS	0.250		0	Ő	NR	NR	NR	0
US FIN ASSUR	TP		NR	NR	NR	NR	NR	Õ
EPA WATCH LIST	TP		NR	NR	NR	NR	NR	0
2020 COR ACTION	0.250		0	0	NR	NR	NR	0
TSCA	TP		NR	NR	NR	NR	NR	0
TRIS	TP		NR	NR	NR	NR	NR	0
SSTS	TP		NR	NR	NR	NR	NR	0
ROD RMP	0.250 TP		0 NR	0 NR	NR NR	NR NR	NR NR	0 0
RAATS	TP		NR	NR	NR	NR	NR	0
PRP	TP		NR	NR	NR	NR	NR	0
PADS	TP		NR	NR	NR	NR	NR	Õ
ICIS	TP		NR	NR	NR	NR	NR	0
FTTS	TP		NR	NR	NR	NR	NR	0
MLTS	TP		NR	NR	NR	NR	NR	0
COAL ASH DOE	TP		NR	NR	NR	NR	NR	0
COAL ASH EPA PCB TRANSFORMER	0.250				NR	NR	NR	0
RADINFO	TP TP		NR NR	NR NR	NR NR	NR NR	NR NR	0 0
HIST FTTS	TP		NR	NR	NR	NR	NR	0
DOT OPS	TP		NR	NR	NR	NR	NR	0
CONSENT	0.250		0	0	NR	NR	NR	Õ
INDIAN RESERV	0.250		0	0	NR	NR	NR	0
FUSRAP	0.250		0	0	NR	NR	NR	0
UMTRA	0.250		0	0	NR	NR	NR	0
LEAD SMELTERS	TP		NR	NR	NR	NR	NR	0
US AIRS US MINES	TP		NR	NR	NR	NR NR	NR NR	0
ABANDONED MINES	0.250 0.250		0 0	0 0	NR NR	NR	NR	0 0
FINDS	0.230 TP		NR	NR	NR	NR	NR	0
ECHO	TP		NR	NR	NR	NR	NR	Õ
UXO	0.250		0	0	NR	NR	NR	0
DOCKET HWC	TP		NR	NR	NR	NR	NR	0
FUELS PROGRAM	0.250		0	0	NR	NR	NR	0
AIRS	TP		NR	NR	NR	NR	NR	0
ASBESTOS	TP TP		NR NR	NR	NR NR	NR NR	NR NR	0
CLEANUP SITES DEDB	0.250		0	NR 0	NR	NR	NR	0 0
DRYCLEANERS	0.250		0	0	NR	NR	NR	0
DWM CONTAM	0.250		Õ	Õ	NR	NR	NR	Õ
Financial Assurance	TP		NR	NR	NR	NR	NR	0
FL Cattle Dip. Vats	0.250		0	0	NR	NR	NR	0
RESP PARTY	0.250		0	0	NR	NR	NR	0
SITE INV SITES	0.250		0	0	NR	NR	NR	0
TIER 2 UIC	TP			NR				0
NPDES	TP TP		NR NR	NR NR	NR NR	NR NR	NR NR	0 0
MINES MRDS	TP		NR	NR	NR	NR	NR	0
EDR HIGH RISK HISTORICA	L RECORDS							
EDR Exclusive Records								
EDR MGP	0.250		0	0	NR	NR	NR	0

Database	Search Distance (Miles)	Target Property	< 1/8	1/8 - 1/4	1/4 - 1/2	1/2 - 1	> 1	Total Plotted
EDR Hist Auto EDR Hist Cleaner	0.125 0.125		0 0	NR NR	NR NR	NR NR	NR NR	0 0
EDR RECOVERED GOVERNMENT ARCHIVES								
Exclusive Recovered Go	vt. Archives							
RGA HWS RGA LF RGA LUST	TP TP TP		NR NR NR	NR NR NR	NR NR NR	NR NR NR	NR NR NR	0 0 0
- Totals		0	4	2	0	0	0	6

### NOTES:

TP = Target Property

NR = Not Requested at this Search Distance

Sites may be listed in more than one database

Database(s)

EDR ID Number EPA ID Number

1 SW < 1/8 0.004 mi. 20 ft.	SARASOTA YACHT CLUB 1100 JOHN RINGLING BLVD SARASOTA, FL 34236	LUST U001373644 UST N/A Financial Assurance
Relative: Higher Actual: 4 ft.	LUST: Region: Facility Id: Facility Status: Facility Type: Facility Phone: Facility Cleanup Rank: District: Lat/Long (dms): Section: Township: Range: Feature: Method: Datum: Score: Score Effective Date: Score When Ranked: Operator: Name Update:	STATE 8516507 OPEN V - Marine/Coastal Fuel Storage (941)315-4191 12937 South District 27 19 19.567 / 82 34 6.2878 Not reported Not reported Not reported Not reported Not reported ADDM 0 6 2003-02-13 00:00:00 6 AMANDA HOLM, DOCK MASTER Not reported
	Address Update: Petroleum Cleanup PCT Facility Scor Facility Cleanup Status: Contact: Contact Company: Contact Address: Contact City/State/Zip: Phone: Bad Address Ind: State: Zip: Score: Score Effective Date: Related Party ID: Primary RP Role: RP Begin Date: RP Zip: RP Extension:	2007-06-06 00:00 e: CMPL - COMPLETED BERNHARD KLOPPENBURG , GENERAL MGR SARASOTA YACHT CLUB 1100 JOHN RINGLING BLVD SARASOTA, FL 34236 (941)365-4191 N FL 34236 6 2003-02-13 00:00:00 19153 ACCOUNT OWNER 1991-09-16 Not reported Not reported
	Discharge Cleanup Summary: Discharge Date: PCT Discharge Combined: Cleanup Required: Discharge Cleanup Status: Disch Cleanup Status Date: Cleanup Work Status: Information Source: Other Source Description: Eligibility Indicator: Site Manager: Site Mgr End Date: Tank Office:	10/11/2002 Not reported R - CLEANUP REQUIRED SRCR - SRCR COMPLETE 8/1/2008 COMPLETED D - DISCHARGE NOTIFICATION B I - INELIGIBLE SIMPSON_DH 7/21/2008 PCLP58 - SARASOTA CNTY AIR QUALITY/STORAGE TANK MGMT

Database(s)

EDR ID Number EPA ID Number

#### SARASOTA YACHT CLUB (Continued)

U001373644

Contaminated Media: 10/11/2002 Discharge Date: Pct Discharge Combined With: Not reported Cleanup Required: **R - CLEANUP REQUIRED Discharge Cleanup Status:** SRCR - SRCR COMPLETE Disch Cleanup Status Date: 8/1/2008 Cleanup Work Status: COMPLETED Information Source: **D - DISCHARGE NOTIFICATION** Other Source Description: в Elig Indicator: I - INELIGIBLE Site Manager: SIMPSON DH Site Mgr End Date: 7/21/2008 Tank Office: PCLP58 - SARASOTA CNTY AIR QUA Contaminated Drinking Wells: 0 Contaminated Monitoring Well: No Contaminated Soil: Yes Contaminated Surface Water: No Contaminated Ground Water: Yes Pollutant: B - Unleaded Gas Pollutant Other Description: Not reported Gallons Discharged: Not reported **Discharge Date:** 10/11/2002 Pct Discharge Combined With: Not reported Cleanup Required: **R - CLEANUP REQUIRED** Discharge Cleanup Status: SRCR - SRCR COMPLETE **Disch Cleanup Status Date:** 8/1/2008 Cleanup Work Status: COMPLETED Information Source: **D - DISCHARGE NOTIFICATION** Other Source Description: В Elig Indicator: I - INELIGIBLE Site Manager: SIMPSON DH Site Mgr End Date: 7/21/2008 Tank Office: PCLP58 - SARASOTA CNTY AIR QUA Contaminated Drinking Wells: 0 Contaminated Monitoring Well: No Contaminated Soil: Yes Contaminated Surface Water: No Contaminated Ground Water: Yes D - Vehicular Diesel Pollutant: Pollutant Other Description: Not reported Gallons Discharged: Not reported Task Information: District: SD Facility ID: 8516507 Facility Status: OPEN Facility Type: V - Marine/Coastal Fuel Storage -County: SARASOTA County ID: 58 Cleanup Eligibility Status: L Source Effective Date: 07-18-2008 Discharge Date: 10-11-2002 Cleanup Required: **R - CLEANUP REQUIRED Discharge Cleanup Status:** SRCR - SRCR COMPLETE **Disch Cleanup Status Date:** 08-01-2008 SRC Action Type: SRCR - SITE REHABILITATION COMPLETION REPORT SRC Submit Date: 05-20-2008

Database(s)

EDR ID Number EPA ID Number

#### SARASOTA YACHT CLUB (Continued)

SRC Review Date: 07-18-2008 A - APPROVED SRC Completion Status: SRC Issue Date: 08-01-2008 SRC Comment: SRCO SENT TO DEP FOR SIGNATURE Cleanup Work Status: COMPLETED Site Mgr: SIMPSON\_DH Site Mgr End Date: 07-21-2008 Tank Office: PCLP58 - Sarasota County SR Task ID: Not reported SR Cleanup Responsible: SR Funding Eligibility Type: SR Actual Cost: Not reported SR Completion Date: Not reported Not reported SR Payment Date: SR Oral Date: Not reported Not reported SR Written Date: SR Soil Removal: Not reported SR Free Product Removal: Not reported SR Soil Tonnage Removed: Not reported SR Soil Treatment: Not reported SR Other Treatment: Not reported SR Alternate Proc Received Date: Not reported SR Alternate Procedure Status: Not reported SR Alternate Procedure Status Date: Not reported SR Alternate Procedure Comments: Not reported SA Task ID: 69842 SA Cleanup Responsible: SA Funding Eligibility Type: SA Actual Cost: Not reported SA Completion Date: Not reported SA Payment Date: Not reported RAP Task ID: Not reported RAP Cleanup Responsible ID: RAP Funding Eligibility Type: **RAP Actual Cost:** Not reported **RAP** Completion Date: Not reported RAP Payment Date: Not reported RAP Last Order Approved: Not reported RA Task ID: 78328 RA Cleanup Responsible: RA Funding Eligibility Type: RA Years to Complete: 0 **RA Actual Cost:** Not reported

Click here for Florida Oculus:

#### UST:

Facility Id:	8516507
Facility Status:	OPEN
Type Description:	Marine/Coastal Fuel Storage
Facility Phone:	9413154191
Region:	STATE
Positioning Method:	ADDM
Lat/Long (dms):	27 19 19 / 82 34 6
wner:	

Owner: Owner Id:

19153

Database(s)

EDR ID Number EPA ID Number

### SARASOTA YACHT CLUB (Continued)

ARASOTA TACHT CLUB (Cont	inuea)
Owner Name:	SARASOTA YACHT CLUB
Owner Address:	1100 JOHN RINGLING BLVD
Owner Address 2:	Not reported
Owner City,St,Zip:	SARASOTA, FL 34236
Owner Contact:	BERNHARD KLOPPENBURG , GENERAL MGR
Owner Phone:	9413654191
Tank Info:	
Name:	SARASOTA YACHT CLUB
Address:	1100 JOHN RINGLING BLVD
City:	SARASOTA
Zip:	34236
Tank Id:	1
Status:	Removed
Status Date:	Not reported
Install Date:	Not reported
Substance:	Vehicular diesel
Content Description:	Vehicular Diesel
Gallons:	1000
Vessel Indicator:	TANK
Tank Location:	UNDERGROUND
DEP Contractor:	C
Name:	SARASOTA YACHT CLUB
Address:	1100 JOHN RINGLING BLVD
City:	SARASOTA
Zip:	34236
Tank Id:	2
Status:	Removed
Status Date:	Not reported
Install Date:	Not reported
Substance:	Leaded gas
Content Description:	Leaded Gas
Gallons:	1000
Vessel Indicator:	TANK
Tank Location:	UNDERGROUND
DEP Contractor:	С
News	
Name:	SARASOTA YACHT CLUB
Address:	1100 JOHN RINGLING BLVD
City:	SARASOTA
Zip:	34236
Tank Id:	3
Status:	Removed
Status Date:	Not reported
Install Date:	Not reported
Substance:	Vehicular diesel
Content Description:	Vehicular Diesel
Gallons:	1000
Vessel Indicator:	TANK
Tank Location:	UNDERGROUND
DEP Contractor:	C
Name:	SARASOTA YACHT CLUB
Address:	1100 JOHN RINGLING BLVD
City:	SARASOTA
Zip:	34236
<i>د</i>	01200

Database(s)

EDR ID Number EPA ID Number

### SARASOTA YACHT CLUB (Continued)

Tank Id: 4 Status: Removed Status Date: 07/01/2002 Install Date: 3/1/1986 Substance: Vehicular diesel Content Description: Vehicular Diesel Gallons: 4000 TANK Vessel Indicator: Tank Location: UNDERGROUND **DEP Contractor:** С SARASOTA YACHT CLUB Name: 1100 JOHN RINGLING BLVD Address: City: SARASOTA Zip: 34236 Tank Id: 5 Status: Removed 07/01/2002 Status Date: Install Date: 3/1/1986 Unleaded gas Substance: Content Description: Unleaded Gas Gallons: 2000 Vessel Indicator: TANK UNDERGROUND Tank Location: DEP Contractor: С Name: SARASOTA YACHT CLUB Address: 1100 JOHN RINGLING BLVD City: SARASOTA 34236 Zip: Tank Id: 6 Status: In service Status Date: 07/01/2002 Install Date: 7/1/2002 Unleaded gas Substance: Unleaded Gas Content Description: 12000 Gallons: Vessel Indicator: TANK UNDERGROUND Tank Location: **DEP** Contractor: С Construction: Tank Id: 6 Construction Category: **Primary Construction** Construction Description: Fiberglass clad steel Tank Id: 6 Construction Category: Secondary Containment Construction Description: Double wall - tank jacket Tank Id: 6 Construction Category: Overfill/Spill Construction Description: Spill containment bucket Tank Id: 6 Construction Category: Overfill/Spill Construction Description: Flow shut-Off

Database(s)

EDR ID Number EPA ID Number

#### SARASOTA YACHT CLUB (Continued)

Tank Id:6Construction Category:Miscellaneous AttributesConstruction Description:CompartmentedTank Id:6Construction Category:Overfill/Spill

Tight fill

6

6

6

6

6

6

6

6

Double wall

Fiberglass

Construction Category: Construction Description:

Monitoring: Tank ID: Monitoring Description:

> Tank ID: Monitoring Description:

Tank ID: Monitoring Description:

toring Description:

6 Visual inspect pipe sumps

**Primary Construction** 

Approved synthetic material

**Miscellaneous Attributes** 

Secondary Containment

Pressurized piping system

Visual inspect dispenser liners

Monitor dbl wall tank space

Monitor dbl wall pipe space

Mechanical line leak detector

Tank ID: Monitoring Description:

Monitoring Description:

Piping:

Tank ID:

Tank ID: Piping Category: Piping Description:

Facility Type:

Type Description:

6 Miscellaneous Attributes Dispenser liners

**Primary Construction** 

Click here for Florida Oculus:

FL Financial Assurance 3:Region:3Facility ID:8516507Facility Phone:9413154191Facility Status:OPEN

9413154191 OPEN V Marine/Coastal Fuel Storage

Database(s)

EDR ID Number EPA ID Number

### SARASOTA YACHT CLUB (Continued)

	intinueu)
DEP CO:	C
Finaincial Responsibility:	INSURANCE
Insurance Company:	ACE
Effective Date:	05/03/2009
Expire Date:	05/03/2010
Owner ID:	19153
Onwer Name:	SARASOTA YACHT CLUB
Owner Address:	1100 JOHN RINGLING BLVD
Owner Address2:	Not reported
Owner City,St,Zip:	SARASOTA, FL 34236
Contact:	BERNHARD KLOPPENBURG , GENERAL MGR
Resp Party Phone:	9413654191
Region:	3
Facility ID:	8516507
Facility Phone:	9413154191
Facility Status:	OPEN
Facility Type:	V
Type Description:	Marine/Coastal Fuel Storage
DEP CO:	C
Finaincial Responsibility:	INSURANCE
Insurance Company:	ACE
Effective Date:	05/03/2010
Expire Date:	05/03/2010
Owner ID:	05/03/2011
Onwer Name:	19153
Owner Address:	SARASOTA YACHT CLUB
Owner Address:	1100 JOHN RINGLING BLVD
Owner Address2:	Not reported
Owner City,St,Zip:	SARASOTA, FL 34236
Contact:	BERNHARD KLOPPENBURG , GENERAL MGR
Resp Party Phone:	9413654191
Region: Facility ID: Facility Phone: Facility Status: Facility Type: Type Description: DEP CO: Finaincial Responsibility: Insurance Company: Effective Date: Expire Date: Owner ID: Onwer Name: Owner Address: Owner Address: Owner Address2: Owner City,St,Zip: Contact: Resp Party Phone:	3 8516507 9413154191 OPEN V Marine/Coastal Fuel Storage C INSURANCE ACE 05/03/2011 05/03/2012 19153 SARASOTA YACHT CLUB 1100 JOHN RINGLING BLVD Not reported SARASOTA, FL 34236 BERNHARD KLOPPENBURG , GENERAL MGR 9413654191
Region:	3
Facility ID:	8516507
Facility Phone:	9413154191
Facility Status:	OPEN
Facility Type:	V
Type Description:	Marine/Coastal Fuel Storage

Database(s)

EDR ID Number EPA ID Number

### SARASOTA YACHT CLUB (Continued)

DEP CO:	С		
Finaincial Responsibility:	INSURANCE		
Insurance Company:	ACE		
Effective Date:	06/21/2012		
Expire Date:	06/21/2013		
Owner ID:	19153		
Onwer Name:	SARASOTA YACHT CLUB		
Owner Address:	1100 JOHN RINGLING BLVD		
Owner Address2:	Not reported		
	SARASOTA, FL 34236		
Owner City,St,Zip: Contact:	BERNHARD KLOPPENBURG , GENERAL MGR		
Resp Party Phone:	9413654191		
Region:	3		
Facility ID:	-		
Facility Phone:	8516507		
	9413154191		
Facility Status:	OPEN		
Facility Type:	V Marine (On early) Final Otherson		
Type Description:	Marine/Coastal Fuel Storage		
DEP CO:	C		
Finaincial Responsibility:	INSURANCE		
Insurance Company:	ACE		
Effective Date:	06/21/2013		
Expire Date:	06/21/2014		
Owner ID:	19153		
Onwer Name:	SARASOTA YACHT CLUB		
Owner Address:	1100 JOHN RINGLING BLVD		
Owner Address2:	Not reported		
Owner City,St,Zip:	SARASOTA, FL 34236		
Contact:	BERNHARD KLOPPENBURG , GENERAL MGR		
Resp Party Phone:	9413654191		
Region:	3		
Facility ID:	8516507		
Facility ID: Facility Phone:	8516507 9413154191		
Facility ID: Facility Phone: Facility Status:	8516507 9413154191 OPEN		
Facility ID: Facility Phone: Facility Status: Facility Type:	8516507 9413154191 OPEN V		
Facility ID: Facility Phone: Facility Status: Facility Type: Type Description:	8516507 9413154191 OPEN V Marine/Coastal Fuel Storage		
Facility ID: Facility Phone: Facility Status: Facility Type: Type Description: DEP CO:	8516507 9413154191 OPEN V Marine/Coastal Fuel Storage C		
Facility ID: Facility Phone: Facility Status: Facility Type: Type Description: DEP CO: Finaincial Responsibility:	8516507 9413154191 OPEN V Marine/Coastal Fuel Storage C INSURANCE		
Facility ID: Facility Phone: Facility Status: Facility Type: Type Description: DEP CO: Finaincial Responsibility: Insurance Company:	8516507 9413154191 OPEN V Marine/Coastal Fuel Storage C INSURANCE ACE		
Facility ID: Facility Phone: Facility Status: Facility Type: Type Description: DEP CO: Finaincial Responsibility:	8516507 9413154191 OPEN V Marine/Coastal Fuel Storage C INSURANCE		
Facility ID: Facility Phone: Facility Status: Facility Type: Type Description: DEP CO: Finaincial Responsibility: Insurance Company:	8516507 9413154191 OPEN V Marine/Coastal Fuel Storage C INSURANCE ACE		
Facility ID: Facility Phone: Facility Status: Facility Type: Type Description: DEP CO: Finaincial Responsibility: Insurance Company: Effective Date:	8516507 9413154191 OPEN V Marine/Coastal Fuel Storage C INSURANCE ACE 06/21/2014		
Facility ID: Facility Phone: Facility Status: Facility Type: Type Description: DEP CO: Finaincial Responsibility: Insurance Company: Effective Date: Expire Date:	8516507 9413154191 OPEN V Marine/Coastal Fuel Storage C INSURANCE ACE 06/21/2014 06/21/2015		
Facility ID: Facility Phone: Facility Status: Facility Type: Type Description: DEP CO: Finaincial Responsibility: Insurance Company: Effective Date: Expire Date: Owner ID:	8516507 9413154191 OPEN V Marine/Coastal Fuel Storage C INSURANCE ACE 06/21/2014 06/21/2015 19153		
Facility ID: Facility Phone: Facility Status: Facility Type: Type Description: DEP CO: Finaincial Responsibility: Insurance Company: Effective Date: Expire Date: Owner ID: Onwer Name:	8516507 9413154191 OPEN V Marine/Coastal Fuel Storage C INSURANCE ACE 06/21/2014 06/21/2015 19153 SARASOTA YACHT CLUB		
Facility ID: Facility Phone: Facility Status: Facility Type: Type Description: DEP CO: Finaincial Responsibility: Insurance Company: Effective Date: Expire Date: Owner ID: Onwer Name: Owner Address:	8516507 9413154191 OPEN V Marine/Coastal Fuel Storage C INSURANCE ACE 06/21/2014 06/21/2015 19153 SARASOTA YACHT CLUB 1100 JOHN RINGLING BLVD		
Facility ID: Facility Phone: Facility Status: Facility Type: Type Description: DEP CO: Finaincial Responsibility: Insurance Company: Effective Date: Expire Date: Owner ID: Onwer Name: Owner Address: Owner Address2:	8516507 9413154191 OPEN V Marine/Coastal Fuel Storage C INSURANCE ACE 06/21/2014 06/21/2015 19153 SARASOTA YACHT CLUB 1100 JOHN RINGLING BLVD Not reported		
Facility ID: Facility Phone: Facility Status: Facility Type: Type Description: DEP CO: Finaincial Responsibility: Insurance Company: Effective Date: Expire Date: Owner ID: Onwer Name: Owner Address: Owner Address2: Owner City,St,Zip:	8516507 9413154191 OPEN V Marine/Coastal Fuel Storage C INSURANCE ACE 06/21/2014 06/21/2015 19153 SARASOTA YACHT CLUB 1100 JOHN RINGLING BLVD Not reported SARASOTA, FL 34236		
Facility ID: Facility Phone: Facility Status: Facility Status: Facility Type: Type Description: DEP CO: Finaincial Responsibility: Insurance Company: Effective Date: Expire Date: Owner ID: Onwer Name: Owner Address: Owner Address: Owner Address2: Owner City,St,Zip: Contact: Resp Party Phone:	8516507 9413154191 OPEN V Marine/Coastal Fuel Storage C INSURANCE ACE 06/21/2014 06/21/2015 19153 SARASOTA YACHT CLUB 1100 JOHN RINGLING BLVD Not reported SARASOTA, FL 34236 BERNHARD KLOPPENBURG , GENERAL MGR 9413654191		
Facility ID: Facility Phone: Facility Status: Facility Type: Type Description: DEP CO: Finaincial Responsibility: Insurance Company: Effective Date: Expire Date: Owner ID: Onwer Name: Owner Address: Owner Address2: Owner Address2: Owner City,St,Zip: Contact: Resp Party Phone: Region:	8516507 9413154191 OPEN V Marine/Coastal Fuel Storage C INSURANCE ACE 06/21/2014 06/21/2015 19153 SARASOTA YACHT CLUB 1100 JOHN RINGLING BLVD Not reported SARASOTA, FL 34236 BERNHARD KLOPPENBURG , GENERAL MGR 9413654191		
Facility ID: Facility Phone: Facility Status: Facility Type: Type Description: DEP CO: Finaincial Responsibility: Insurance Company: Effective Date: Expire Date: Owner ID: Onwer Name: Owner Address: Owner Address: Owner Address2: Owner City,St,Zip: Contact: Resp Party Phone: Region: Facility ID:	8516507 9413154191 OPEN V Marine/Coastal Fuel Storage C INSURANCE ACE 06/21/2014 06/21/2015 19153 SARASOTA YACHT CLUB 1100 JOHN RINGLING BLVD Not reported SARASOTA, FL 34236 BERNHARD KLOPPENBURG , GENERAL MGR 9413654191		
Facility ID: Facility Phone: Facility Status: Facility Status: Facility Type: Type Description: DEP CO: Finaincial Responsibility: Insurance Company: Effective Date: Expire Date: Owner ID: Onwer Name: Owner Address: Owner Address: Owner Address2: Owner City,St,Zip: Contact: Resp Party Phone: Region: Facility ID: Facility Phone:	8516507 9413154191 OPEN V Marine/Coastal Fuel Storage C INSURANCE ACE 06/21/2014 06/21/2015 19153 SARASOTA YACHT CLUB 1100 JOHN RINGLING BLVD Not reported SARASOTA, FL 34236 BERNHARD KLOPPENBURG , GENERAL MGR 9413654191		
Facility ID: Facility Phone: Facility Status: Facility Status: Facility Type: Type Description: DEP CO: Finaincial Responsibility: Insurance Company: Effective Date: Expire Date: Owner ID: Onwer Name: Owner Address: Owner Address: Owner Address: Owner Address2: Owner City,St,Zip: Contact: Resp Party Phone: Facility ID: Facility Phone: Facility Status:	8516507 9413154191 OPEN V Marine/Coastal Fuel Storage C INSURANCE ACE 06/21/2014 06/21/2015 19153 SARASOTA YACHT CLUB 1100 JOHN RINGLING BLVD Not reported SARASOTA, FL 34236 BERNHARD KLOPPENBURG , GENERAL MGR 9413654191 3 8516507 9413154191 OPEN		
Facility ID: Facility Phone: Facility Status: Facility Status: Facility Type: Type Description: DEP CO: Finaincial Responsibility: Insurance Company: Effective Date: Expire Date: Owner ID: Onwer Name: Owner Address: Owner Address: Owner Address2: Owner City,St,Zip: Contact: Resp Party Phone: Region: Facility ID: Facility Phone:	8516507 9413154191 OPEN V Marine/Coastal Fuel Storage C INSURANCE ACE 06/21/2014 06/21/2015 19153 SARASOTA YACHT CLUB 1100 JOHN RINGLING BLVD Not reported SARASOTA, FL 34236 BERNHARD KLOPPENBURG , GENERAL MGR 9413654191		

Database(s)

EDR ID Number EPA ID Number

### SARASOTA YACHT CLUB (Continued)

	minueu)
DEP CO: Finaincial Responsibility: Insurance Company: Effective Date: Expire Date: Owner ID: Onwer Name: Owner Address: Owner Address2: Owner City,St,Zip: Contact: Resp Party Phone:	C INSURANCE COMMERCE & INDUSTRY 03/03/2016 03/03/2017 19153 SARASOTA YACHT CLUB 1100 JOHN RINGLING BLVD Not reported SARASOTA, FL 34236 BERNHARD KLOPPENBURG , GENERAL MGR 9413654191
Region: Facility ID: Facility Phone: Facility Status: Facility Type: Type Description: DEP CO: Finaincial Responsibility: Insurance Company: Effective Date: Expire Date: Owner ID: Onwer Name: Owner Address: Owner Address: Owner Address2: Owner City,St,Zip: Contact: Resp Party Phone:	3 8516507 9413154191 OPEN V Marine/Coastal Fuel Storage C INSURANCE COMMERCE & INDUSTRY 03/03/2017 03/03/2019 19153 SARASOTA YACHT CLUB 1100 JOHN RINGLING BLVD Not reported SARASOTA, FL 34236 BERNHARD KLOPPENBURG , GENERAL MGR 9413654191
Region: Facility ID: Facility Phone: Facility Status: Facility Status: Facility Type: Type Description: DEP CO: Finaincial Responsibility: Insurance Company: Effective Date: Expire Date: Owner ID: Onwer Name: Owner Address: Owner Address2: Owner City,St,Zip: Contact: Resp Party Phone:	3 8516507 9413154191 OPEN V Marine/Coastal Fuel Storage C INSURANCE COMMERCE & INDUSTRY 06/21/2015 06/21/2016 19153 SARASOTA YACHT CLUB 1100 JOHN RINGLING BLVD Not reported SARASOTA, FL 34236 BERNHARD KLOPPENBURG , GENERAL MGR 9413654191
Region: Facility ID: Facility Phone: Facility Status: Facility Type: Type Description:	3 8516507 9413154191 OPEN V Marine/Coastal Fuel Storage

Database(s)

UST

AST

NPDES

ASBESTOS

**Financial Assurance** 

EDR ID Number **EPA ID Number** 

#### U001373644

U002113565

N/A

#### SARASOTA YACHT CLUB (Continued)

DEP CO:	C
Finaincial Responsibility:	INSURANCE
Insurance Company:	ILLINOIS UNION
Effective Date:	05/03/2008
Expire Date:	05/03/2009
Owner ID:	19153
Onwer Name:	SARASOTA YACHT CLUB
Owner Address:	1100 JOHN RINGLING BLVD
Owner Address2:	Not reported
Owner City,St,Zip:	SARASOTA, FL 34236
Contact:	BERNHARD KLOPPENBURG , GENERAL MGR
Resp. Party Phono:	0413654101
Resp Party Phone:	9413654191

#### 2 PLYMOUTH HARBOR ON SARASOTA BAY SW 700 JOHN RINGLING BLVD

< 1/8 SARASOTA, FL 34236 0.092 mi.

488 ft.

Relative: Higher Actual:

4 ft.

UST: Facility Id: Facility Status: Type Description: Facility Phone: Region: Positioning Method: Lat/Long (dms):	9500095 OPEN Fuel user/Non-retail 9413617520 STATE AGPS 27 19 14 / 82 34 12
Owner: Owner Id: Owner Name: Owner Address: Owner Address 2: Owner City,St,Zip: Owner Contact: Owner Phone:	38303 PLYMOUTH HARBOR INC 700 JOHN RINGLING BLVD ATTN: MARTY MARTEL SARASOTA, FL 34236 MARTY MARTEL 9413617219

Tank Info: Name:

City:

Zip:

Address:

Tank Id:

Status Date:

Install Date:

Substance:

Gallons:

Content Description:

Vessel Indicator:

Tank Location: DEP Contractor:

Status:

PLYMOUTH HARBOR ON SARASOTA BAY 700 JOHN RINGLING BLVD SARASOTA 34236 1 Closed in place 05/12/1997 6/1/1987 Diesel-emergen generator Emerg Generator Diesel 2000 TANK UNDERGROUND С

Click here for Florida Oculus:

#### Map ID Direction Distance Elevation Site

MAP FINDINGS

Database(s)

EDR ID Number EPA ID Number

	PLYMOUTH HARBOR ON SARASOTA BAY	
	700 JOHN RINGLING BLVD	
5	9500095	
,	OPEN Fuel user/Non-retail	
, i		
Facility Phone: DEP Contractor Own:	9413617520	
Region:	STATE	
Positioning Method:	AGPS	
Lat/Long (dms):	27 19 14 / 82 34 12	
Owner:		
Owner Id:	38303	
Owner Name:	PLYMOUTH HARBOR INC	
Owner Address:	700 JOHN RINGLING BLVD	
Owner Address 2:	ATTN: MARTY MARTEL	
Owner City,St,Zip:	SARASOTA, FL 34236	
Owner Contact:	MARTY MARTEL	
Owner Phone:	9413617219	
	3 In service	
	08/28/2018	
• • • • • • • • • • • • • • • • • • • •	8/28/2018	
	Ultra Low Sulfur Diesel	
	8000	
	ABOVEGROUND	
Construction:		
Tank Id:	3	
Construction Category:	Overfill/Spill	
Construction Descriptio		
Tank Id:	3	
Construction Category:	Primary Construction	
Construction Descriptio	n: Steel	
Tank Id:	3	
Construction Category:	Overfill/Spill	
Construction Descriptio	n: Flow shut-Off	
Tank Id:	3	
Construction Category:	Overfill/Spill	
Construction Descriptio	n: Level gauges/alarms	
Tank Id:	3	
Construction Category:	Secondary Containment	
Construction Descriptio	n: Double wall	
Monitoring:		
Tank ID:	3	
Monitoring Description:	Vapor monitoring	
Tank ID: Monitoring Description:	3	
Monitoring Description:	Monitor tank bottom space	

### 3565

Database(s)

EDR ID Number EPA ID Number

Tank ID: Monitoring Description	n:	3 Monitor dbl wall pipe space	
Tank ID: Monitoring Description:		3 None	
Tank ID: Monitoring Description	n:	3 Monitor dbl wall tank space	
Tank ID: Monitoring Description	n:	3 SPCC Plan	
Piping: Tank ID: Piping Category: Piping Description:		3 Secondary Containment Double wall	
Tank ID: Piping Category: Piping Description:		3 Corrosion Protection External protective coating	
Tank ID: Piping Category: Piping Description:		3 Primary Construction Steel/galvanized metal	
Tank ID: Piping Category: Piping Description:		3 Miscellaneous Attributes Abv, no soil contact	
Tank Id: Status: Status Date: Install Date: Substance: Content Description: Gallons: Tank Location:	2 Removed 08/28/2018 5/1/1997 Diesel-emergen generator Emerg Generator Diesel 3000 ABOVEGROUND		
Click here for Florida Oculus:			
ASBESTOS: Name: Address: City,State,Zip: Facility ID: Notification ID:		PLYMOUTH HARBOR 700 JOHN RINGLING BLVD. SARASOTA, FL 34236 AS11502394 87358	

87258

Ν

ORIGINAL

DEMOLITION

REVIEWED COOLING TOWER

Not reported

03/30/2016

PLYMOUTH HARBOR, INC.

WILLIS A SMITH CONSTRUCTION INC

Notification ID:

Project Type:

Site Name:

Owner Name:

Start Date:

Notification Type:

Notification Status:

Ordered Demolition?:

Annual Notification:

Contractor Name:

PLYMOUTH HARBOR ON SARASOTA BAY (Continued)

#### U0

U002113565

### TC5931196.2s Page 19

04/15/2016

Database(s)

EDR ID Number EPA ID Number

#### PLYMOUTH HARBOR ON SARASOTA BAY (Continued)

Finish Date: Cementitious RACM: Cementitious SF: Floor RACM: Floor SF: Pipe RACM: Pipe SF: CF RACM: Roof RACM: Roof SF: Surface Mat RACM: Surface Mat SF: Waste Disposal Site: Waste Disposal Address: Waste Disposal City: Waste Disposal State: Waste Disposal Zip: Transporter Name: Contractor is Transporter: Waste Disp ID: Waste Disp Source: Transporter Address: Transporter City: Transporter State: Transporter Zip: Date Receive: Name: Address: City,State,Zip: Facility ID: Notification ID: Notification Type: Project Type: Notification Status: Site Name: Ordered Demolition?: Annual Notification: **Owner Name:** Contractor Name: Start Date: Finish Date: Cementitious RACM: Cementitious SF: Floor RACM: Floor SF: Pipe RACM: Pipe SF: CF RACM: Roof RACM: Roof SF: Surface Mat RACM: Surface Mat SF: Waste Disposal Site: Waste Disposal Address: Waste Disposal City: Waste Disposal State:

Not reported FL Not reported Not reported PLYMOUTH HARBOR 700 JOHN RINGLING BLVD. SARASOTA, FL 34236 AS11502394 69814 ORIGINAL RENOVATION REVIEWED **UNIT T403** Ν Not reported PLYMOUTH HARBOR, INC. ENVIRONMENTAL CONSTRUCTION, INC. 09/18/2012 09/21/2012 Ν Not reported N Not reported Y Not reported Not reported N Not reported 1000 ADVANCED DISPOSAL 4000 KNIGHTS TRAIL SARASOTA FL

Database(s)

EDR ID Number EPA ID Number

#### PLYMOUTH HARBOR ON SARASOTA BAY (Continued)

Waste Disposal Zip: Transporter Name: Contractor is Transporter: Waste Disp ID: Waste Disp Source: Transporter Address: Transporter City: Transporter State: Transporter Zip: Date Receive: Name: Address: City,State,Zip: Facility ID: Notification ID: Notification Type: Project Type: Notification Status: Site Name: Ordered Demolition?: Annual Notification: **Owner Name:** Contractor Name: Start Date: Finish Date: Cementitious RACM: Cementitious SF: Floor RACM: Floor SF: Pipe RACM: Pipe SF:

CF RACM: Roof RACM: Roof SF: Surface Mat RACM: Surface Mat SF: Waste Disposal Site: Waste Disposal Address: Waste Disposal City: Waste Disposal State: Waste Disposal Zip: Transporter Name: Contractor is Transporter: Waste Disp ID: Waste Disp Source: Transporter Address: Transporter City: Transporter State: Transporter Zip: Date Receive:

Name: Address: City,State,Zip: Facility ID: Notification ID:

34275 Not reported Υ 847 А Not reported Not reported Not reported Not reported Not reported PLYMOUTH HARBOR 700 JOHN RINGLING BLVD. SARASOTA, FL 34236 AS11502394 75550 ORIGINAL RENOVATION COMPLETE T1103 N Not reported PLYMOUTH HARBOR, INC. ENVIRONMENTAL CONSTRUCTION, INC. 01/23/2014 01/24/2014 Not reported Not reported Not reported 100 Not reported Not reported Not reported Not reported Not reported Not reported 500 ADVANCED DISPOSAL 4000 KNIGHTS TRAIL SARASOTA FL 34275 Not reported Υ 847 А Not reported Not reported FL Not reported Not reported

PLYMOUTH HARBOR 700 JOHN RINGLING BLVD. SARASOTA, FL 34236 AS11502394 70720

Database(s) EP

EDR ID Number EPA ID Number

#### PLYMOUTH HARBOR ON SARASOTA BAY (Continued)

Notification Type: Project Type: Notification Status: Site Name: Ordered Demolition?: Annual Notification: **Owner Name:** Contractor Name: Start Date: Finish Date: Cementitious RACM: Cementitious SF: Floor RACM: Floor SF: Pipe RACM: Pipe SF: CF RACM: Roof RACM: Roof SF: Surface Mat RACM: Surface Mat SF: Waste Disposal Site: Waste Disposal Address: Waste Disposal City: Waste Disposal State: Waste Disposal Zip: Transporter Name: Contractor is Transporter: Waste Disp ID: Waste Disp Source: Transporter Address: Transporter City: Transporter State: Transporter Zip: Date Receive: Name: Address: City,State,Zip: Facility ID: Notification ID: Notification Type: Project Type: Notification Status: Site Name: Ordered Demolition?: Annual Notification: **Owner Name:** Contractor Name:

Start Date:

Finish Date: Cementitious RACM:

Floor SF:

Pipe SF:

Pipe RACM:

Cementitious SF: Floor RACM:

ORIGINAL RENOVATION REVIEWED 700 JOHN RINGLING BLVD # 2105 Ν Not reported PLYMOUTH HARBOR, INC. ENVIRONMENTAL CONSTRUCTION, INC. 12/31/2012 01/04/2013 Ν Not reported Ν Not reported 100 Not reported Ν Not reported Y 900 ADVANCED DISPOSAL 4000 KNIGHTS TRAIL SARASOTA FL 34275 Not reported Y 847 А Not reported Not reported Not reported Not reported Not reported PLYMOUTH HARBOR 700 JOHN RINGLING BLVD. SARASOTA, FL 34236 AS11502394 74257 REVISED RENOVATION REVIEWED **UNIT T1114** Ν Not reported PLYMOUTH HARBOR, INC. ENVIRONMENTAL CONSTRUCTION, INC. 10/14/2013 10/18/2013 Not reported Not reported Not reported Not reported Not reported Not reported

Database(s)

EDR ID Number EPA ID Number

#### PLYMOUTH HARBOR ON SARASOTA BAY (Continued)

CF RACM: Roof RACM: Roof SF: Surface Mat RACM: Surface Mat SF: Waste Disposal Site: Waste Disposal Address: Waste Disposal City: Waste Disposal State: Waste Disposal Zip: Transporter Name: Contractor is Transporter: Waste Disp ID: Waste Disp Source: Transporter Address: Transporter City: Transporter State: Transporter Zip: Date Receive: Name: Address: City,State,Zip: Facility ID: Notification ID: Notification Type: Project Type: Notification Status: Site Name: Ordered Demolition?: Annual Notification: Owner Name: Contractor Name: Start Date: Finish Date: Cementitious RACM: Cementitious SF: Floor RACM: Floor SF: Pipe RACM: Pipe SF: CF RACM: Roof RACM: Roof SF: Surface Mat RACM: Surface Mat SF: Waste Disposal Site: Waste Disposal Address: Waste Disposal City: Waste Disposal State: Waste Disposal Zip: Transporter Name: Contractor is Transporter: Waste Disp ID: Waste Disp Source: Transporter Address: Transporter City:

Not reported Not reported Not reported Not reported 900 ADVANCED DISPOSAL 4000 KNIGHTS TRAIL SARASOTA FL 34275 Not reported Y 847 А Not reported Not reported FL Not reported Not reported PLYMOUTH HARBOR 700 JOHN RINGLING BLVD. SARASOTA, FL 34236 AS11502394 75245 ORIGINAL RENOVATION REVIEWED **UNIT T2107** Ν Not reported PLYMOUTH HARBOR, INC. ENVIRONMENTAL CONSTRUCTION, INC. 12/19/2013 12/24/2013 Not reported 500 ADVANCED DISPOSAL 4000 KNIGHTS TRAIL SARASOTA FL 34275 Not reported Υ 847 Α Not reported Not reported

Database(s)

EDR ID Number EPA ID Number

#### PLYMOUTH HARBOR ON SARASOTA BAY (Continued)

Transporter State: Transporter Zip: Date Receive:

Name: Address: City,State,Zip: Facility ID: Notification ID: Notification Type: Project Type: Notification Status: Site Name: Ordered Demolition?: Annual Notification: **Owner Name:** Contractor Name: Start Date: Finish Date: Cementitious RACM: Cementitious SF: Floor RACM: Floor SF: Pipe RACM: Pipe SF: CF RACM: Roof RACM: Roof SF: Surface Mat RACM: Surface Mat SF: Waste Disposal Site: Waste Disposal Address: Waste Disposal City: Waste Disposal State: Waste Disposal Zip: Transporter Name: Contractor is Transporter: Waste Disp ID: Waste Disp Source: Transporter Address: Transporter City: Transporter State: Transporter Zip: Date Receive:

Name: Address: City,State,Zip: Facility ID: Notification ID: Notification Type: Project Type: Notification Status: Site Name: Ordered Demolition?: Annual Notification: Owner Name: FL Not reported Not reported PLYMOUTH 700. JOHN R

PLYMOUTH HARBOR 700 JOHN RINGLING BLVD. SARASOTA, FL 34236 AS11502394 73436 ORIGINAL RENOVATION REVIEWED **UNIT T1910** Ν Not reported PLYMOUTH HARBOR, INC. ENVIRONMENTAL CONSTRUCTION, INC. 07/29/2013 08/02/2013 Not reported 900 ADVANCED DISPOSAL 4000 KNIGHTS TRAIL SARASOTA FL 34275 Not reported Y 847 Α Not reported Not reported FL Not reported Not reported PLYMOUTH HARBOR 700 JOHN RINGLING BLVD. SARASOTA, FL 34236 AS11502394 74256 ORIGINAL RENOVATION REVIEWED UNIT E309 Ν Not reported PLYMOUTH HARBOR, INC.

**ENVIROREM** 

Database(s)

EDR ID Number EPA ID Number

#### PLYMOUTH HARBOR ON SARASOTA BAY (Continued)

Contractor Name: Start Date: Finish Date: Cementitious RACM: Cementitious SF: Floor RACM: Floor SF: Pipe RACM: Pipe SF: CF RACM: Roof RACM: Roof SF: Surface Mat RACM: Surface Mat SF: Waste Disposal Site: Waste Disposal Address: Waste Disposal City: Waste Disposal State: Waste Disposal Zip: Transporter Name: Contractor is Transporter: Waste Disp ID: Waste Disp Source: Transporter Address: Transporter City: Transporter State: Transporter Zip: Date Receive: Name: Address: City,State,Zip: Facility ID: Notification ID: Notification Type: Project Type: Notification Status: Site Name: Ordered Demolition?: Annual Notification: Owner Name: Contractor Name: Start Date: Finish Date: Cementitious RACM: Cementitious SF: Floor RACM: Floor SF: Pipe RACM: Pipe SF: CF RACM: Roof RACM: Roof SF: Surface Mat RACM: Surface Mat SF: Waste Disposal Site: Waste Disposal Address:

09/26/2013 09/27/2013 Not reported 500 Not reported FL Not reported Not reported PLYMOUTH HARBOR 700 JOHN RINGLING BLVD. SARASOTA, FL 34236 AS11502394 65368 REVISED RENOVATION REVIEWED **UNIT T1405** Ν Not reported PLYMOUTH HARBOR, INC. ENVIRONMENTAL CONSTRUCTION, INC. 01/16/2012 01/20/2012 N Not reported Ν Not reported Υ Not reported Not reported Ν Not reported Υ 1600 ADVANCED DISPOSAL 4000 KNIGHTS TRAIL

#### Map ID Direction Distance Elevation Site

### MAP FINDINGS

Database(s)

EDR ID Number EPA ID Number

PLYMOUTH HARBOR ON SARASOTA BAY (Continued)			
Waste Disposal City:	SARASOTA		
Waste Disposal State:	FL		
Waste Disposal Zip:	34275		
Transporter Name:	Not reported		
Contractor is Transporter:	Y		
Waste Disp ID:	847		
Waste Disp Source:	A		
Transporter Address:	Not reported		
Transporter City:	Not reported		
Transporter State:	Not reported		
Transporter Zip:	Not reported		
Date Receive:	Not reported		
200000000			
FL Financial Assurance 3:			
Region:	3		
Facility ID:	9500095		
Facility Phone:	9413617520		
Facility Status:	OPEN		
Facility Type:	C		
Type Description:	Fuel user/Non-retail		
DEP CO:	C		
Finaincial Responsibility:	INSURANCE		
Insurance Company:	COMMERCE & INDUSTRY		
Effective Date:	11/21/2008		
Expire Date:	11/21/2009		
Owner ID:	38303		
Onwer Name:	PLYMOUTH HARBOR INC		
Owner Address:	700 JOHN RINGLING BLVD		
Owner Address2:	ATTN: MARTY MARTEL		
Owner City,St,Zip:	SARASOTA, FL 34236		
Contact:	MARTY MARTEL		
Resp Party Phone:	9413617219		
Region:	3		
Facility ID:	9500095		
Facility Phone:	9413617520		
Facility Status:	OPEN		
Facility Type:	C		
Type Description:	Fuel user/Non-retail		
DEP CO:			
Finaincial Responsibility:			
Insurance Company:	COMMERCE & INDUSTRY		
Effective Date: Expire Date:	11/21/2009 11/21/2010		
Owner ID:	38303		
Onwer Name:	PLYMOUTH HARBOR INC		
Owner Address:	700 JOHN RINGLING BLVD		
Owner Address2:	ATTN: MARTY MARTEL		
Owner City,St,Zip:	SARASOTA, FL 34236		
Contact:	MARTY MARTEL		
Resp Party Phone:	9413617219		
Region:	3		
Facility ID:	9500095		
Facility Phone:	9413617520 ODEN		
Facility Status: Facility Type:	OPEN C		
Facility Type.	0		

Database(s)

EDR ID Number EPA ID Number

#### PLYMOUTH HARBOR ON SARASOTA BAY (Continued)

Type Description: Fuel user/Non-retail DEP CO: С Finaincial Responsibility: INSURANCE Insurance Company: **COMMERCE & INDUSTRY** Effective Date: 11/21/2010 Expire Date: 11/21/2011 Owner ID: 38303 Onwer Name: PLYMOUTH HARBOR INC Owner Address: 700 JOHN RINGLING BLVD Owner Address2: ATTN: MARTY MARTEL Owner City, St, Zip: SARASOTA, FL 34236 Contact: MARTY MARTEL Resp Party Phone: 9413617219 Region: 3 Facility ID: 9500095 Facility Phone: 9413617520 Facility Status: OPEN Facility Type: С Type Description: Fuel user/Non-retail DEP CO: С Finaincial Responsibility: INSURANCE Insurance Company: **COMMERCE & INDUSTRY** Effective Date: 11/21/2011 Expire Date: 11/21/2012 Owner ID: 38303 Onwer Name: PLYMOUTH HARBOR INC Owner Address: 700 JOHN RINGLING BLVD Owner Address2: ATTN: MARTY MARTEL Owner City,St,Zip: SARASOTA, FL 34236 MARTY MARTEL Contact: **Resp Party Phone:** 9413617219 Region: 3 Facility ID: 9500095 Facility Phone: 9413617520 Facility Status: OPEN Facility Type: С Type Description: Fuel user/Non-retail DEP CO: С Finaincial Responsibility: INSURANCE Insurance Company: COMMERCE & INDUSTRY Effective Date: 11/21/2012 Expire Date: 11/21/2013 Owner ID: 38303 PLYMOUTH HARBOR INC Onwer Name: Owner Address: 700 JOHN RINGLING BLVD Owner Address2: ATTN: MARTY MARTEL Owner City, St, Zip: SARASOTA, FL 34236 Contact: MARTY MARTEL **Resp Party Phone:** 9413617219 3 Region: Facility ID: 9500095 Facility Phone: 9413617520 Facility Status: OPEN Facility Type: С

Database(s)

EDR ID Number EPA ID Number

#### PLYMOUTH HARBOR ON SARASOTA BAY (Continued)

Type Description: Fuel user/Non-retail DEP CO: С Finaincial Responsibility: INSURANCE Insurance Company: **COMMERCE & INDUSTRY** Effective Date: 11/21/2013 Expire Date: 11/21/2015 Owner ID: 38303 Onwer Name: PLYMOUTH HARBOR INC Owner Address: 700 JOHN RINGLING BLVD Owner Address2: ATTN: MARTY MARTEL Owner City, St, Zip: SARASOTA, FL 34236 Contact: MARTY MARTEL Resp Party Phone: 9413617219 Region: 3 Facility ID: 9500095 Facility Phone: 9413617520 Facility Status: OPEN Facility Type: С Type Description: Fuel user/Non-retail DEP CO: С Finaincial Responsibility: INSURANCE Insurance Company: **COMMERCE & INDUSTRY** Effective Date: 11/21/2018 Expire Date: 11/21/2019 Owner ID: 38303 Onwer Name: PLYMOUTH HARBOR INC Owner Address: 700 JOHN RINGLING BLVD Owner Address2: ATTN: MARTY MARTEL Owner City,St,Zip: SARASOTA, FL 34236 MARTY MARTEL Contact: Resp Party Phone: 9413617219 Region: 3 Facility ID: 9500095 Facility Phone: 9413617520 Facility Status: OPEN Facility Type: С Type Description: Fuel user/Non-retail DEP CO: С Finaincial Responsibility: INSURANCE Insurance Company: COMMERCE & INDUSTRY INSURANCE CO Effective Date: 11/21/2015 Expire Date: 11/21/2018 Owner ID: 38303 PLYMOUTH HARBOR INC Onwer Name: Owner Address: 700 JOHN RINGLING BLVD Owner Address2: ATTN: MARTY MARTEL Owner City, St, Zip: SARASOTA, FL 34236 MARTY MARTEL Contact: Resp Party Phone: 9413617219 WASTEWATER: COON KEY Name: 700 JOHN RINGLING BLVD Address: City,State,Zip: SARASOTA, FL

FLR20CR49

Facility ID:

EDR ID Number Database(s) EPA ID Number

### PLYMOUTH HARBOR ON SARASOTA BAY (Continued)

MOUTH HARBOR ON SARA	ASOTA BAT (Conunded)	00
Facility Type:	Construction Generic Dewatering	
Status:	Active - Existing, permitted facility/site for which effluent,	
	reclaimed water or wastewater residual discharge into the environment	
	and/or monitoring is taking place.	
District Office:	TLST	
NPDES Permitted Site:	Not reported	
Environmental Interest:	Not reported	
Owner Type:	Private	
Permit Capacity:	Not reported	
Party Name:	Kevin Lane, PMTE	
Company Name:	Spectrum Underground, Inc.	
RP Address:	5802 Bee Ridge Rd	
RP Address 2:	Ste 101	
RP City,Stat,Zip:	Sarasota FL 34233-5069	
Telephone:	9413426708	
Email:	kevinlane@masterrockllc.com	
Issue Date:	03/03/2019	
Effective Date:	03/03/2019	
Expiration Date:	03/02/2024	
DOC Description:	Generic Permit	
Latitude Degrees:	27	
Latitude Minutes:	19	
Latitude Seconds:	18.88	
Longitude Degrees:	82	
Longitude Minutes:	34	
Longitude Seconds:	14.16	
Treatment:	Not reported	
Decode For Fstatus:	Active	
Name:	PLYMOUTH HARBOR COOLING TOWER AND ALF EXPANSION	
Address:	700 JOHN RINGLING BLVD	
City,State,Zip:	SARASOTA, FL	
Facility ID:	FLR20AF18	
Facility Type:	Construction Generic Dewatering	
Status:	Active - Existing, permitted facility/site for which effluent,	
Oldido.	reclaimed water or wastewater residual discharge into the environment	
	and/or monitoring is taking place.	
District Office:	TLST	
NPDES Permitted Site:	Not reported	
Environmental Interest:	Not reported	
Owner Type:	Private	
Permit Capacity:	Not reported	
Party Name:	Bradley Ellender, Project Manager	
Company Name:	Willis A Smith Construction, Inc.	
RP Address:	5001 Lakewood Ranch Blvd N	
RP Address 2:	Not reported	
RP City,Stat,Zip:	Lakewood Ranch FL 34240-8621	
Telephone:	9413663116	
Email:	bellender@willissmith.com	
Issue Date:	07/03/2015	
Effective Date:	07/03/2015	
Expiration Date:	07/02/2020	
DOC Description:	Generic Permit	
Latitude Degrees:	27	
Latitude Minutes:	19	
Latitude Seconds:	16.87	
Longitude Degrees:	82	
-		

Database(s)

EDR ID Number EPA ID Number

	Longitude Minutes: Longitude Seconds: Treatment: Decode For Fstatus:	34 7.751 Not reported Active		
3 East 1/8-1/4 0.221 mi. 1166 ft.	HARRIS RESIDENCE 243 ROBIN DR SARASOTA, FL 34236		LUST UST	U002038389 N/A
Relative:	LUST:			
Higher		STATE 0404472		
Actual: 4 ft.	Facility Id: Facility Status:	9401473 CLOSED		
4 11.	Facility Type:	B - Residential		
	Facility Phone:	(708)615-0200		
	Facility Cleanup Rank:	11086		
	District:	South District		
	Lat/Long (dms):	27 19 25.3519 / 82 33 35.2037		
	Section: Township:	Not reported Not reported		
	Range:	Not reported		
	Feature:	Not reported		
	Method:	ADDM		
	Datum:	Not reported		
	Score:	9		
	Score Effective Date:	2001-04-24 00:00:00		
	Score When Ranked: Operator:	9 Not reported		
	Name Update:	Not reported		
	Address Update:	Not reported		
	Petroleum Cleanup PCT Facil	ity Score		
	Facility Cleanup Status:	CMPL - COMPLETED		
	Contact:	DAVID HARRIS		
	Contact Company:	HARRIS, DAVID		
	Contact Address:	190 AHWAHNEE RD		
	Contact City/State/Zip:	LAKE FOREST, IL 60045		
	Phone:	(708)615-0200		
	Bad Address Ind: State:	N FL		
	Zip:	34236		
	Score:	9		
	Score Effective Date:	2001-04-24 00:00:00		
	Related Party ID:	37611		
	Primary RP Role:	ACCOUNT OWNER		
	RP Begin Date:	1994-08-18		
	RP Zip: RP Extension:	Not reported Not reported		
	RF EXTENSION.	Not reported		
	Discharge Cleanup Summary:			
	Discharge Date:	5/19/1994		
	PCT Discharge Combined:			
	Cleanup Required:	R - CLEANUP REQUIRED		
	Discharge Cleanup Status:			
	Disch Cleanup Status Date			
	Cleanup Work Status:	COMPLETED		

Database(s)

EDR ID Number EPA ID Number

## HARRIS RESIDENCE (Continued)

UO
D - DISCHARGE NOTIFICATION Not reported I - INELIGIBLE MURRAY_S 10/3/2006 PCLP58 - SARASOTA CNTY AIR QUALITY/STORAGE TANK MGMT
5/19/1994 Not reported R - CLEANUP REQUIRED NFA - NFA COMPLETE 10/23/2006 COMPLETED D - DISCHARGE NOTIFICATION Not reported I - INELIGIBLE MURRAY_S 10/3/2006 PCLP58 - SARASOTA CNTY AIR QUA 0 Yes Yes No No No M - Fuel Oil - Onsite Heat Not reported Not reported
SD 9401473 CLOSED B - Residential - SARASOTA 58 I 09-29-2006 05-19-1994 R - CLEANUP REQUIRED NFA - NFA COMPLETE 10-23-2006 NFA - NO FURTHER ACTION 08-30-2006 09-29-2006 A - APPROVED 10-23-2006 SUBMITTED TO DEP FOR SIGNATURE COMPLETED MURRAY_S 10-03-2006 PCLP58 - Sarasota County Not reported - Not reported Not reported Not reported

Database(s)

EDR ID Number EPA ID Number

### HARRIS RESIDENCE (Continued)

SR Oral Date: SR Written Date: SR Soil Removal: SR Free Product Removal: SR Soil Tonnage Removed: SR Soil Treatment: SR Other Treatment: SR Alternate Proc Received Date: SR Alternate Procedure Status: SR Alternate Procedure Status Date: SR Alternate Procedure Comments: SA Actual Cost: SA Cleanup Responsible: SA Payment Date: RAP Cleanup Responsible ID: RAP Completion Date: RAP Completion Date: RAP Payment Date: RAP Last Order Approved: RA Task ID: RA Cleanup Responsible: RA Funding Eligibility Type: PA Yacara to Commentate	Not reported 57976 - - Not reported Not reported - - - -
	- 0 Not reported

Click here for Florida Oculus:

#### UST:

Zip: Tank Id:

Status:

Facility Id: Facility Status: Type Description: Facility Phone: Region: Positioning Method: Lat/Long (dms):	9401473 CLOSED Residential 7086150200 STATE ADDM 27 19 25.6692 / 82 33 35.8812
Owner: Owner Id: Owner Name: Owner Address: Owner Address 2: Owner City,St,Zip: Owner Contact: Owner Phone:	37611 HARRIS, DAVID 190 AHWAHNEE RD Not reported LAKE FOREST, IL 60045 DAVID HARRIS 7086150200
Tank Info: Name: Address: City:	HARRIS RESIDENCE 243 ROBIN DR SARASOTA

34236 1 Removed

Database(s)

EDR ID Number EPA ID Number

#### U002038389

### HARRIS RESIDENCE (Continued)

Status Date:	05/01/1994
Install Date:	Not reported
Substance:	Fuel oil-on site heat
Content Description:	Fuel Oil - Onsite Heat
Gallons:	300
Vessel Indicator:	TANK
Tank Location:	UNDERGROUND
DEP Contractor:	P
DEP Contractor:	Р

Click here for Florida Oculus:

Count: 0 records.

ORPHAN SUMMARY

City	EDR ID	Site Name	Site Address	Zip	Database(s)
	_				

NO SITES FOUND

To maintain currency of the following federal and state databases, EDR contacts the appropriate governmental agency on a monthly or quarterly basis, as required.

**Number of Days to Update:** Provides confirmation that EDR is reporting records that have been updated within 90 days from the date the government agency made the information available to the public.

### STANDARD ENVIRONMENTAL RECORDS

#### Federal NPL site list

#### NPL: National Priority List

National Priorities List (Superfund). The NPL is a subset of CERCLIS and identifies over 1,200 sites for priority cleanup under the Superfund Program. NPL sites may encompass relatively large areas. As such, EDR provides polygon coverage for over 1,000 NPL site boundaries produced by EPA's Environmental Photographic Interpretation Center (EPIC) and regional EPA offices.

Date of Government Version: 10/25/2019 Date Data Arrived at EDR: 11/07/2019 Date Made Active in Reports: 11/20/2019 Number of Days to Update: 13 Source: EPA Telephone: N/A Last EDR Contact: 01/03/2020 Next Scheduled EDR Contact: 04/13/2020 Data Release Frequency: Quarterly

NPL Site Boundaries

Sources:

EPA's Environmental Photographic Interpretation Center (EPIC) Telephone: 202-564-7333

EPA Region 1 Telephone 617-918-1143

EPA Region 3 Telephone 215-814-5418

EPA Region 4 Telephone 404-562-8033

EPA Region 5 Telephone 312-886-6686

EPA Region 10 Telephone 206-553-8665 EPA Region 6 Telephone: 214-655-6659

EPA Region 7 Telephone: 913-551-7247

EPA Region 8 Telephone: 303-312-6774

EPA Region 9 Telephone: 415-947-4246

#### Proposed NPL: Proposed National Priority List Sites

A site that has been proposed for listing on the National Priorities List through the issuance of a proposed rule in the Federal Register. EPA then accepts public comments on the site, responds to the comments, and places on the NPL those sites that continue to meet the requirements for listing.

Date of Government Version: 10/25/2019 Date Data Arrived at EDR: 11/07/2019 Date Made Active in Reports: 11/20/2019 Number of Days to Update: 13 Source: EPA Telephone: N/A Last EDR Contact: 01/03/2020 Next Scheduled EDR Contact: 04/13/2020 Data Release Frequency: Quarterly

NPL LIENS: Federal Superfund Liens

Federal Superfund Liens. Under the authority granted the USEPA by CERCLA of 1980, the USEPA has the authority to file liens against real property in order to recover remedial action expenditures or when the property owner received notification of potential liability. USEPA compiles a listing of filed notices of Superfund Liens.

Date of Government Version: 10/15/1991 Date Data Arrived at EDR: 02/02/1994 Date Made Active in Reports: 03/30/1994 Number of Days to Update: 56 Source: EPA Telephone: 202-564-4267 Last EDR Contact: 08/15/2011 Next Scheduled EDR Contact: 11/28/2011 Data Release Frequency: No Update Planned

### Federal Delisted NPL site list

Delisted NPL: National Priority List Deletions

The National Oil and Hazardous Substances Pollution Contingency Plan (NCP) establishes the criteria that the EPA uses to delete sites from the NPL. In accordance with 40 CFR 300.425.(e), sites may be deleted from the NPL where no further response is appropriate.

Date of Government Version: 10/25/2019 Date Data Arrived at EDR: 11/07/2019 Date Made Active in Reports: 11/20/2019 Number of Days to Update: 13 Source: EPA Telephone: N/A Last EDR Contact: 01/03/2020 Next Scheduled EDR Contact: 04/13/2020 Data Release Frequency: Quarterly

## Federal CERCLIS list

FEDERAL FACILITY: Federal Facility Site Information listing

A listing of National Priority List (NPL) and Base Realignment and Closure (BRAC) sites found in the Comprehensive Environmental Response, Compensation and Liability Information System (CERCLIS) Database where EPA Federal Facilities Restoration and Reuse Office is involved in cleanup activities.

Date of Government Version: 04/03/2019 Date Data Arrived at EDR: 04/05/2019 Date Made Active in Reports: 05/14/2019 Number of Days to Update: 39 Source: Environmental Protection Agency Telephone: 703-603-8704 Last EDR Contact: 04/05/2019 Next Scheduled EDR Contact: 04/13/2020 Data Release Frequency: Varies

#### SEMS: Superfund Enterprise Management System

SEMS (Superfund Enterprise Management System) tracks hazardous waste sites, potentially hazardous waste sites, and remedial activities performed in support of EPA's Superfund Program across the United States. The list was formerly know as CERCLIS, renamed to SEMS by the EPA in 2015. The list contains data on potentially hazardous waste sites that have been reported to the USEPA by states, municipalities, private companies and private persons, pursuant to Section 103 of the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA). This dataset also contains sites which are either proposed to or on the National Priorities List (NPL) and the sites which are in the screening and assessment phase for possible inclusion on the NPL.

Date of Government Version: 10/25/2019 Date Data Arrived at EDR: 11/07/2019 Date Made Active in Reports: 11/21/2019 Number of Days to Update: 14 Source: EPA Telephone: 800-424-9346 Last EDR Contact: 01/03/2020 Next Scheduled EDR Contact: 01/27/2020 Data Release Frequency: Quarterly

#### Federal CERCLIS NFRAP site list

SEMS-ARCHIVE: Superfund Enterprise Management System Archive

SEMS-ARCHIVE (Superfund Enterprise Management System Archive) tracks sites that have no further interest under the Federal Superfund Program based on available information. The list was formerly known as the CERCLIS-NFRAP, renamed to SEMS ARCHIVE by the EPA in 2015. EPA may perform a minimal level of assessment work at a site while it is archived if site conditions change and/or new information becomes available. Archived sites have been removed and archived from the inventory of SEMS sites. Archived status indicates that, to the best of EPA's knowledge, assessment at a site has been completed and that EPA has determined no further steps will be taken to list the site on the National Priorities List (NPL), unless information indicates this decision was not appropriate or other considerations require a recommendation for listing at a later time. The decision does not necessarily mean that there is no hazard associated with a given site; it only means that. based upon available information, the location is not judged to be potential NPL site.

Date of Government Version: 10/25/2019 Date Data Arrived at EDR: 11/07/2019 Date Made Active in Reports: 11/21/2019 Number of Days to Update: 14 Source: EPA Telephone: 800-424-9346 Last EDR Contact: 01/03/2020 Next Scheduled EDR Contact: 01/27/2020 Data Release Frequency: Quarterly

### Federal RCRA CORRACTS facilities list

CORRACTS: Corrective Action Report

CORRACTS identifies hazardous waste handlers with RCRA corrective action activity.

Date of Government Version: 12/16/2019	Source: EPA
Date Data Arrived at EDR: 12/16/2019	Telephone: 800-424-9346
Date Made Active in Reports: 12/20/2019	Last EDR Contact: 12/16/2019
Number of Days to Update: 4	Next Scheduled EDR Contact: 04/06/2020
	Data Release Frequency: Quarterly

## Federal RCRA non-CORRACTS TSD facilities list

RCRA-TSDF: RCRA - Treatment, Storage and Disposal

RCRAInfo is EPA's comprehensive information system, providing access to data supporting the Resource Conservation and Recovery Act (RCRA) of 1976 and the Hazardous and Solid Waste Amendments (HSWA) of 1984. The database includes selective information on sites which generate, transport, store, treat and/or dispose of hazardous waste as defined by the Resource Conservation and Recovery Act (RCRA). Transporters are individuals or entities that move hazardous waste from the generator offsite to a facility that can recycle, treat, store, or dispose of the waste. TSDFs treat, store, or dispose of the waste.

Date of Government Version: 12/16/2019 Date Data Arrived at EDR: 12/16/2019 Date Made Active in Reports: 12/20/2019 Number of Days to Update: 4 Source: Environmental Protection Agency Telephone: (404) 562-8651 Last EDR Contact: 12/16/2019 Next Scheduled EDR Contact: 04/06/2020 Data Release Frequency: Quarterly

#### Federal RCRA generators list

## RCRA-LQG: RCRA - Large Quantity Generators

RCRAInfo is EPA's comprehensive information system, providing access to data supporting the Resource Conservation and Recovery Act (RCRA) of 1976 and the Hazardous and Solid Waste Amendments (HSWA) of 1984. The database includes selective information on sites which generate, transport, store, treat and/or dispose of hazardous waste as defined by the Resource Conservation and Recovery Act (RCRA). Large quantity generators (LQGs) generate over 1,000 kilograms (kg) of hazardous waste, or over 1 kg of acutely hazardous waste per month.

Date of Government Version: 12/16/2019 Date Data Arrived at EDR: 12/16/2019 Date Made Active in Reports: 12/20/2019 Number of Days to Update: 4 Source: Environmental Protection Agency Telephone: (404) 562-8651 Last EDR Contact: 12/16/2019 Next Scheduled EDR Contact: 04/06/2020 Data Release Frequency: Quarterly

#### RCRA-SQG: RCRA - Small Quantity Generators

RCRAInfo is EPA's comprehensive information system, providing access to data supporting the Resource Conservation and Recovery Act (RCRA) of 1976 and the Hazardous and Solid Waste Amendments (HSWA) of 1984. The database includes selective information on sites which generate, transport, store, treat and/or dispose of hazardous waste as defined by the Resource Conservation and Recovery Act (RCRA). Small quantity generators (SQGs) generate between 100 kg and 1,000 kg of hazardous waste per month.

Date of Government Version: 12/16/2019 Date Data Arrived at EDR: 12/16/2019 Date Made Active in Reports: 12/20/2019 Number of Days to Update: 4 Source: Environmental Protection Agency Telephone: (404) 562-8651 Last EDR Contact: 12/16/2019 Next Scheduled EDR Contact: 04/06/2020 Data Release Frequency: Quarterly

RCRA-VSQG: RCRA - Very Small Quantity Generators (Formerly Conditionally Exempt Small Quantity Generators) RCRAInfo is EPA's comprehensive information system, providing access to data supporting the Resource Conservation and Recovery Act (RCRA) of 1976 and the Hazardous and Solid Waste Amendments (HSWA) of 1984. The database includes selective information on sites which generate, transport, store, treat and/or dispose of hazardous waste as defined by the Resource Conservation and Recovery Act (RCRA). Very small quantity generators (VSQGs) generate less than 100 kg of hazardous waste, or less than 1 kg of acutely hazardous waste per month.

Date of Government Version: 12/16/2019 Date Data Arrived at EDR: 12/16/2019 Date Made Active in Reports: 12/20/2019 Number of Days to Update: 4 Source: Environmental Protection Agency Telephone: (404) 562-8651 Last EDR Contact: 12/16/2019 Next Scheduled EDR Contact: 04/06/2020 Data Release Frequency: Quarterly

#### Federal institutional controls / engineering controls registries

#### LUCIS: Land Use Control Information System

LUCIS contains records of land use control information pertaining to the former Navy Base Realignment and Closure properties.

Date of Government Version: 08/13/2019Source: Department of the NavyDate Data Arrived at EDR: 08/20/2019Telephone: 843-820-7326Date Made Active in Reports: 08/26/2019Last EDR Contact: 11/07/2019Number of Days to Update: 6Next Scheduled EDR Contact: 02/24/2020Data Release Frequency: Varies

## US ENG CONTROLS: Engineering Controls Sites List

A listing of sites with engineering controls in place. Engineering controls include various forms of caps, building foundations, liners, and treatment methods to create pathway elimination for regulated substances to enter environmental media or effect human health.

Date of Government Version: 08/19/2019	Source: Environmental Protection Agency
Date Data Arrived at EDR: 08/20/2019	Telephone: 703-603-0695
Date Made Active in Reports: 08/26/2019	Last EDR Contact: 11/22/2019
Number of Days to Update: 6	Next Scheduled EDR Contact: 03/09/2020
	Data Release Frequency: Varies

## US INST CONTROL: Sites with Institutional Controls

A listing of sites with institutional controls in place. Institutional controls include administrative measures, such as groundwater use restrictions, construction restrictions, property use restrictions, and post remediation care requirements intended to prevent exposure to contaminants remaining on site. Deed restrictions are generally required as part of the institutional controls.

Date of Government Version: 08/19/2019SDate Data Arrived at EDR: 08/20/2019TDate Made Active in Reports: 08/26/2019LNumber of Days to Update: 6M

Source: Environmental Protection Agency Telephone: 703-603-0695 Last EDR Contact: 11/22/2019 Next Scheduled EDR Contact: 03/09/2020 Data Release Frequency: Varies

### Federal ERNS list

ERNS: Emergency Response Notification System

Emergency Response Notification System. ERNS records and stores information on reported releases of oil and hazardous substances.

Date of Government Version: 09/09/2019 Date Data Arrived at EDR: 09/09/2019 Date Made Active in Reports: 09/23/2019 Number of Days to Update: 14 Source: National Response Center, United States Coast Guard Telephone: 202-267-2180 Last EDR Contact: 12/19/2019 Next Scheduled EDR Contact: 04/06/2020 Data Release Frequency: Quarterly

## State- and tribal - equivalent CERCLIS

SHWS: Florida's State-Funded Action Sites

State Hazardous Waste Sites. State hazardous waste site records are the states' equivalent to CERCLIS. These sites may or may not already be listed on the federal CERCLIS list. Priority sites planned for cleanup using state funds (state equivalent of Superfund) are identified along with sites where cleanup will be paid for by potentially responsible parties. Available information varies by state.

Date of Government Version: 12/06/2018	Source: Department of Environmental Protection
Date Data Arrived at EDR: 02/20/2019	Telephone: 850-488-0190
Date Made Active in Reports: 03/12/2019	Last EDR Contact: 11/22/2019
Number of Days to Update: 20	Next Scheduled EDR Contact: 03/02/2020
	Data Release Frequency: Semi-Annually

#### State and tribal landfill and/or solid waste disposal site lists

#### SWF/LF: Solid Waste Facility Database

Solid Waste Facilities/Landfill Sites. SWF/LF type records typically contain an inventory of solid waste disposal facilities or landfills in a particular state. Depending on the state, these may be active or inactive facilities or open dumps that failed to meet RCRA Subtitle D Section 4004 criteria for solid waste landfills or disposal sites.

Date of Government Version: 10/15/2019 Date Data Arrived at EDR: 10/16/2019 Date Made Active in Reports: 12/19/2019 Number of Days to Update: 64 Source: Department of Environmental Protection Telephone: 850-922-7121 Last EDR Contact: 10/16/2019 Next Scheduled EDR Contact: 01/27/2020 Data Release Frequency: Quarterly

#### State and tribal leaking storage tank lists

LUST: Petroleum Contamination Detail Report Leaking Underground Storage Tank Incident Reports. LUST records contain an inventory of reported leaking underground storage tank incidents. Not all states maintain these records, and the information stored varies by state.

Date of Government Version: 10/28/2019 Date Data Arrived at EDR: 10/29/2019	Source: Department of Environmental Protection Telephone: 850-245-8839
Date Made Active in Reports: 01/06/2020	Last EDR Contact: 10/29/2019
Number of Days to Update: 69	Next Scheduled EDR Contact: 02/10/2020 Data Release Frequency: Quarterly

## LAST: Leaking Aboveground Storage Tank Listing

The file for Leaking Aboveground Storage Tanks. Please remember STCM does not track the source of the discharge so the agency provides a list of facilities with an aboveground tank and an open discharge split by facilities with aboveground tanks only and facilities with aboveground and underground tanks.

Date of Government Version: 08/01/2019	Source: Department of Environmental Protection
Date Data Arrived at EDR: 08/02/2019	Telephone: 850-245-8799
Date Made Active in Reports: 08/06/2019	Last EDR Contact: 10/25/2019
Number of Days to Update: 4	Next Scheduled EDR Contact: 02/10/2020
	Data Release Frequency: Varies

INDIAN LUST R10: Leaking Underground Storage Tanks on Indian Land LUSTs on Indian land in Alaska, Idaho, Oregon and Washington.		
Date of Government Version: 04/16/2019 Date Data Arrived at EDR: 07/29/2019 Date Made Active in Reports: 10/17/2019 Number of Days to Update: 80	Source: EPA Region 10 Telephone: 206-553-2857 Last EDR Contact: 12/04/2019 Next Scheduled EDR Contact: 02/03/2020 Data Release Frequency: Varies	
INDIAN LUST R1: Leaking Underground Storage Tanks on Indian Land A listing of leaking underground storage tank locations on Indian Land.		
Date of Government Version: 04/11/2019 Date Data Arrived at EDR: 07/29/2019 Date Made Active in Reports: 10/17/2019 Number of Days to Update: 80	Source: EPA Region 1 Telephone: 617-918-1313 Last EDR Contact: 12/04/2019 Next Scheduled EDR Contact: 02/03/2020 Data Release Frequency: Varies	
INDIAN LUST R5: Leaking Underground Storage Tanks on Indian Land Leaking underground storage tanks located on Indian Land in Michigan, Minnesota and Wisconsin.		
Date of Government Version: 04/08/2019 Date Data Arrived at EDR: 07/30/2019 Date Made Active in Reports: 10/17/2019 Number of Days to Update: 79	Source: EPA, Region 5 Telephone: 312-886-7439 Last EDR Contact: 12/04/2019 Next Scheduled EDR Contact: 02/03/2020 Data Release Frequency: Varies	
INDIAN LUST R6: Leaking Underground Storage Tanks on Indian Land LUSTs on Indian land in New Mexico and Oklahoma.		
Date of Government Version: 05/01/2019 Date Data Arrived at EDR: 07/29/2019 Date Made Active in Reports: 10/17/2019 Number of Days to Update: 80	Source: EPA Region 6 Telephone: 214-665-6597 Last EDR Contact: 10/25/2019 Next Scheduled EDR Contact: 02/03/2020 Data Release Frequency: Varies	
INDIAN LUST R9: Leaking Underground Storage Ta LUSTs on Indian land in Arizona, California, Ne		
Date of Government Version: 04/08/2019 Date Data Arrived at EDR: 07/29/2019 Date Made Active in Reports: 10/17/2019 Number of Days to Update: 80	Source: Environmental Protection Agency Telephone: 415-972-3372 Last EDR Contact: 12/04/2019 Next Scheduled EDR Contact: 02/03/2020 Data Release Frequency: Varies	
INDIAN LUST R7: Leaking Underground Storage Tanks on Indian Land LUSTs on Indian land in Iowa, Kansas, and Nebraska		
Date of Government Version: 07/02/2019 Date Data Arrived at EDR: 10/16/2019 Date Made Active in Reports: 10/24/2019 Number of Days to Update: 8	Source: EPA Region 7 Telephone: 913-551-7003 Last EDR Contact: 12/16/2020 Next Scheduled EDR Contact: 02/03/2020 Data Release Frequency: Varies	
INDIAN LUST R4: Leaking Underground Storage Ta LUSTs on Indian land in Florida, Mississippi an		
Date of Government Version: 04/12/2019 Date Data Arrived at EDR: 07/29/2019 Date Made Active in Reports: 10/17/2019 Number of Days to Update: 80	Source: EPA Region 4 Telephone: 404-562-8677 Last EDR Contact: 12/03/2019 Next Scheduled EDR Contact: 02/03/2020 Data Release Frequency: Varies	

INDIAN LUST R8: Leaking Underground Storage Tanks on Indian Land LUSTs on Indian land in Colorado, Montana, North Dakota, South Dakota, Utah and Wyoming.		
Date of Government Version: 05/02/2019 Date Data Arrived at EDR: 10/22/2019 Date Made Active in Reports: 11/11/2019 Number of Days to Update: 20	Source: EPA Region 8 Telephone: 303-312-6271 Last EDR Contact: 12/04/2019 Next Scheduled EDR Contact: 02/03/2020 Data Release Frequency: Varies	
State and tribal registered storage tank lists		
FEMA UST: Underground Storage Tank Listing A listing of all FEMA owned underground stor	age tanks.	
Date of Government Version: 08/27/2019 Date Data Arrived at EDR: 08/28/2019 Date Made Active in Reports: 11/11/2019 Number of Days to Update: 75	Source: FEMA Telephone: 202-646-5797 Last EDR Contact: 01/07/2020 Next Scheduled EDR Contact: 04/20/2020 Data Release Frequency: Varies	
FF TANKS: Federal Facilities Listing A listing of federal facilities with storage tanks		
Date of Government Version: 09/23/2019 Date Data Arrived at EDR: 09/24/2019 Date Made Active in Reports: 11/22/2019 Number of Days to Update: 59	Source: Department of Environmental Protection Telephone: 850-245-8250 Last EDR Contact: 12/17/2019 Next Scheduled EDR Contact: 04/06/2020 Data Release Frequency: Quarterly	
	□'s are regulated under Subtitle I of the Resource Conservation and Recovery state department responsible for administering the UST program. Available	
Date of Government Version: 10/30/2019 Date Data Arrived at EDR: 10/31/2019 Date Made Active in Reports: 01/09/2020 Number of Days to Update: 70	Source: Department of Environmental Protection Telephone: 850-245-8839 Last EDR Contact: 10/25/2019 Next Scheduled EDR Contact: 02/10/2020 Data Release Frequency: Quarterly	
AST: Storage Tank Facility Information Registered Aboveground Storage Tanks.		
Date of Government Version: 10/30/2019 Date Data Arrived at EDR: 10/31/2019 Date Made Active in Reports: 01/09/2020 Number of Days to Update: 70	Source: Department of Environmental Protection Telephone: 850-245-8839 Last EDR Contact: 10/25/2019 Next Scheduled EDR Contact: 02/10/2020 Data Release Frequency: Quarterly	
INDIAN UST R10: Underground Storage Tanks on Indian Land The Indian Underground Storage Tank (UST) database provides information about underground storage tanks on Indian land in EPA Region 10 (Alaska, Idaho, Oregon, Washington, and Tribal Nations).		
Date of Government Version: 04/16/2019 Date Data Arrived at EDR: 07/30/2019	Source: EPA Region 10 Telephone: 206-553-2857	

Source: EPA Region 10 Telephone: 206-553-2857 Last EDR Contact: 12/04/2019 Next Scheduled EDR Contact: 02/03/2020 Data Release Frequency: Varies

Date Made Active in Reports: 10/17/2019

Number of Days to Update: 79

## INDIAN UST R7: Underground Storage Tanks on Indian Land

The Indian Underground Storage Tank (UST) database provides information about underground storage tanks on Indian land in EPA Region 7 (Iowa, Kansas, Missouri, Nebraska, and 9 Tribal Nations).

Date of Government Version: 05/02/2019
Date Data Arrived at EDR: 07/29/2019
Date Made Active in Reports: 10/17/2019
Number of Days to Update: 80

Source: EPA Region 7 Telephone: 913-551-7003 Last EDR Contact: 12/04/2019 Next Scheduled EDR Contact: 02/03/2020 Data Release Frequency: Varies

INDIAN UST R8: Underground Storage Tanks on Indian Land

The Indian Underground Storage Tank (UST) database provides information about underground storage tanks on Indian land in EPA Region 8 (Colorado, Montana, North Dakota, South Dakota, Utah, Wyoming and 27 Tribal Nations).

Date of Government Version: 05/02/2019	Source: EPA Region 8
Date Data Arrived at EDR: 10/22/2019	Telephone: 303-312-6137
Date Made Active in Reports: 11/11/2019	Last EDR Contact: 12/04/2019
Number of Days to Update: 20	Next Scheduled EDR Contact: 02/03/2020
	Data Release Frequency: Varies

INDIAN UST R9: Underground Storage Tanks on Indian Land

The Indian Underground Storage Tank (UST) database provides information about underground storage tanks on Indian land in EPA Region 9 (Arizona, California, Hawaii, Nevada, the Pacific Islands, and Tribal Nations).

Date of Government Version: 04/08/2019 Date Data Arrived at EDR: 07/29/2019 Date Made Active in Reports: 10/17/2019 Number of Days to Update: 80 Source: EPA Region 9 Telephone: 415-972-3368 Last EDR Contact: 12/04/2019 Next Scheduled EDR Contact: 02/03/2020 Data Release Frequency: Varies

## INDIAN UST R6: Underground Storage Tanks on Indian Land

The Indian Underground Storage Tank (UST) database provides information about underground storage tanks on Indian land in EPA Region 6 (Louisiana, Arkansas, Oklahoma, New Mexico, Texas and 65 Tribes).

Date of Government Version: 05/01/2019 Date Data Arrived at EDR: 07/29/2019 Date Made Active in Reports: 10/17/2019 Number of Days to Update: 80 Source: EPA Region 6 Telephone: 214-665-7591 Last EDR Contact: 12/04/2019 Next Scheduled EDR Contact: 02/03/2020 Data Release Frequency: Varies

#### INDIAN UST R1: Underground Storage Tanks on Indian Land

The Indian Underground Storage Tank (UST) database provides information about underground storage tanks on Indian land in EPA Region 1 (Connecticut, Maine, Massachusetts, New Hampshire, Rhode Island, Vermont and ten Tribal Nations).

Date of Government Version: 04/11/2019	Source: EPA, Region 1
Date Data Arrived at EDR: 07/30/2019	Telephone: 617-918-1313
Date Made Active in Reports: 10/17/2019	Last EDR Contact: 12/04/2019
Number of Days to Update: 79	Next Scheduled EDR Contact: 02/03/2020
	Data Release Frequency: Varies

## INDIAN UST R4: Underground Storage Tanks on Indian Land

The Indian Underground Storage Tank (UST) database provides information about underground storage tanks on Indian land in EPA Region 4 (Alabama, Florida, Georgia, Kentucky, Mississippi, North Carolina, South Carolina, Tennessee and Tribal Nations)

Date of Government Version: 04/12/2019	Source: EPA Region 4
Date Data Arrived at EDR: 07/29/2019	Telephone: 404-562-9424
Date Made Active in Reports: 10/17/2019	Last EDR Contact: 12/03/2019
Number of Days to Update: 80	Next Scheduled EDR Contact: 02/03/2020
	Data Release Frequency: Varies

## INDIAN UST R5: Underground Storage Tanks on Indian Land

The Indian Underground Storage Tank (UST) database provides information about underground storage tanks on Indian land in EPA Region 5 (Michigan, Minnesota and Wisconsin and Tribal Nations).

Date of Government Version: 04/08/2019 Date Data Arrived at EDR: 07/29/2019 Date Made Active in Reports: 10/17/2019 Number of Days to Update: 80 Source: EPA Region 5 Telephone: 312-886-6136 Last EDR Contact: 12/04/2019 Next Scheduled EDR Contact: 02/03/2020 Data Release Frequency: Varies

TANKS: Storage Tank Facility List

This listing includes storage tank facilities that do not have tank information. The tanks have either be closed or removed from the site, but the facilities were still registered at some point in history.

Date of Government Version: 10/30/2019	Source: Department of Environmental Protection
Date Data Arrived at EDR: 10/31/2019	Telephone: 850-245-8841
Date Made Active in Reports: 01/09/2020	Last EDR Contact: 10/25/2019
Number of Days to Update: 70	Next Scheduled EDR Contact: 02/10/2020
	Data Release Frequency: Quarterly

### State and tribal institutional control / engineering control registries

ENG CONTROLS: Institutional Controls Registry

The registry is a database of all contaminated sites in the state of Florida which are subject to engineering controls. Engineering Controls encompass a variety of engineered remedies to contain and/or reduce contamination, and/or physical barriers intended to limit access to property. ECs include fences, signs, guards, landfill caps, provision of potable water, slurry walls, sheet pile (vertical caps), pumping and treatment of groundwater, monitoring wells, and vapor extraction systems.

Date of Government Version: 09/28/2019	Source: Department of Environmental Protection
Date Data Arrived at EDR: 10/01/2019	Telephone: 850-245-8927
Date Made Active in Reports: 12/04/2019	Last EDR Contact: 01/08/2020
Number of Days to Update: 64	Next Scheduled EDR Contact: 04/13/2020
	Data Release Frequency: Semi-Annually

Inst Control: Institutional Controls Registry

The registry is a database of all contaminated sites in the state of Florida which are subject to institutional and engineering controls.

Date of Government Version: 09/28/2019 Date Data Arrived at EDR: 10/01/2019 Date Made Active in Reports: 12/04/2019 Number of Days to Update: 64 Source: Department of Environmental Protection Telephone: 850-245-8927 Last EDR Contact: 10/01/2019 Next Scheduled EDR Contact: 04/13/2020 Data Release Frequency: Semi-Annually

#### State and tribal voluntary cleanup sites

INDIAN VCP R7: Voluntary Cleanup Priority Lisitng

A listing of voluntary cleanup priority sites located on Indian Land located in Region 7.

Date of Government Version: 03/20/2008 Date Data Arrived at EDR: 04/22/2008 Date Made Active in Reports: 05/19/2008 Number of Days to Update: 27 Source: EPA, Region 7 Telephone: 913-551-7365 Last EDR Contact: 04/20/2009 Next Scheduled EDR Contact: 07/20/2009 Data Release Frequency: Varies

INDIAN VCP R1: Voluntary Cleanup Priority Listing

A listing of voluntary cleanup priority sites located on Indian Land located in Region 1.

Date of Government Version: 07/27/2015 Date Data Arrived at EDR: 09/29/2015 Date Made Active in Reports: 02/18/2016 Number of Days to Update: 142 Source: EPA, Region 1 Telephone: 617-918-1102 Last EDR Contact: 12/17/2019 Next Scheduled EDR Contact: 04/06/2020 Data Release Frequency: Varies

VCP: Voluntary Cleanup Sites

Listing of closed and active voluntary cleanup sites.

Date of Government Version: 06/28/2019	Source: Department of Environmental Protection
Date Data Arrived at EDR: 08/23/2019	Telephone: 850-245-8705
Date Made Active in Reports: 11/01/2019	Last EDR Contact: 11/14/2019
Number of Days to Update: 70	Next Scheduled EDR Contact: 03/02/2020
	Data Release Frequency: Varies

### State and tribal Brownfields sites

BROWNFIELDS: Brownfields Sites Database

Brownfields are defined by the Florida Department of Environmental Protection (FDEP) as abandoned, idled, or underused industrial and commercial facilities where expansion or redevelopment is complicated by real or perceived environmental contamination.

Date of Government Version: 08/01/2019	Source: Department of Environmental Protection
Date Data Arrived at EDR: 10/01/2019	Telephone: 850-245-8927
Date Made Active in Reports: 12/04/2019	Last EDR Contact: 12/30/2019
Number of Days to Update: 64	Next Scheduled EDR Contact: 04/13/2020
	Data Release Frequency: Semi-Annually

## BSRA: Brownfield Site Rehabilitation Agreements Listing

The BSRA provides DEP and the public assurance that site rehabilitation will be conducted in accordance with Florida Statutes and DEP's Contaminated Site Cleanup Criteria rule. In addition, the BSRA provides limited liability protection for the voluntary responsible party. The BSRA contains various commitments by the voluntary responsible party, including milestones for completion of site rehabilitation tasks and submittal of technical reports and plans. It also contains a commitment by DEP to review technical reports according to an agreed upon schedule. Only those brownfield sites with an executed BSRA are eligible to apply for a voluntary cleanup tax credit incentive pursuant to Section 376.30781, Florida Statutes.

Date of Government Version: 10/03/2019 Date Data Arrived at EDR: 10/04/2019 Date Made Active in Reports: 12/09/2019 Number of Days to Update: 66 Source: Department of Environmental Protection Telephone: 850-245-8934 Last EDR Contact: 12/29/2019 Next Scheduled EDR Contact: 04/12/2020 Data Release Frequency: Varies

## BROWNFIELDS AREAS: Brownfields Areas Database

A "brownfield area" means a contiguous area of one or more brownfield sites, some of which may not be contaminated, that has been designated as such by a local government resolution. Such areas may include all or portions of community redevelopment areas, enterprise zones, empowerment zones, other such designated economically deprived communities and areas, and Environmental Protection Agency (EPA) designated brownfield pilot projects. This layer provides a polygon representation of the boundaries of these designated Brownfield Areas in Florida.

Date of Government Version: 08/29/2019 Date Data Arrived at EDR: 10/01/2019 Date Made Active in Reports: 12/04/2019 Number of Days to Update: 64 Source: Department of Environmental Protection Telephone: 850-245-8934 Last EDR Contact: 12/30/2019 Next Scheduled EDR Contact: 04/13/2020 Data Release Frequency: Quarterly

## ADDITIONAL ENVIRONMENTAL RECORDS

Local Brownfield lists

#### US BROWNFIELDS: A Listing of Brownfields Sites

Brownfields are real property, the expansion, redevelopment, or reuse of which may be complicated by the presence or potential presence of a hazardous substance, pollutant, or contaminant. Cleaning up and reinvesting in these properties takes development pressures off of undeveloped, open land, and both improves and protects the environment. Assessment, Cleanup and Redevelopment Exchange System (ACRES) stores information reported by EPA Brownfields grant recipients on brownfields properties assessed or cleaned up with grant funding as well as information on Targeted Brownfields Assessments performed by EPA Regions. A listing of ACRES Brownfield sites is obtained from Cleanups in My Community. Cleanups in My Community provides information on Brownfields properties for which information is reported back to EPA, as well as areas served by Brownfields grant programs.

Date of Government Version: 06/03/2019 Date Data Arrived at EDR: 06/04/2019 Date Made Active in Reports: 08/26/2019 Number of Days to Update: 83 Source: Environmental Protection Agency Telephone: 202-566-2777 Last EDR Contact: 12/16/2019 Next Scheduled EDR Contact: 03/30/2020 Data Release Frequency: Semi-Annually

#### Local Lists of Landfill / Solid Waste Disposal Sites

SWRCY: Recycling Centers

A listing of recycling centers located in the state of Florida.

Date of Government Version: 12/03/2018	Source: Department of Environmental Protection
Date Data Arrived at EDR: 01/15/2019	Telephone: 850-245-8718
Date Made Active in Reports: 03/14/2019	Last EDR Contact: 10/18/2019
Number of Days to Update: 58	Next Scheduled EDR Contact: 01/27/2020
	Data Release Frequency: Varies

INDIAN ODI: Report on the Status of Open Dumps on Indian Lands Location of open dumps on Indian land.

Date of Government Version: 12/31/1998 Date Data Arrived at EDR: 12/03/2007 Date Made Active in Reports: 01/24/2008 Number of Days to Update: 52 Source: Environmental Protection Agency Telephone: 703-308-8245 Last EDR Contact: 10/28/2019 Next Scheduled EDR Contact: 02/10/2020 Data Release Frequency: Varies

DEBRIS REGION 9: Torres Martinez Reservation Illegal Dump Site Locations

A listing of illegal dump sites location on the Torres Martinez Indian Reservation located in eastern Riverside County and northern Imperial County, California.

Date of Government Version: 01/12/2009 Date Data Arrived at EDR: 05/07/2009 Date Made Active in Reports: 09/21/2009 Number of Days to Update: 137 Source: EPA, Region 9 Telephone: 415-947-4219 Last EDR Contact: 10/17/2019 Next Scheduled EDR Contact: 02/03/2020 Data Release Frequency: No Update Planned

ODI: Open Dump Inventory

An open dump is defined as a disposal facility that does not comply with one or more of the Part 257 or Part 258 Subtitle D Criteria.

Date of Government Version: 06/30/1985	Source: Environmental Protection Agency
Date Data Arrived at EDR: 08/09/2004	Telephone: 800-424-9346
Date Made Active in Reports: 09/17/2004	Last EDR Contact: 06/09/2004
Number of Days to Update: 39	Next Scheduled EDR Contact: N/A
	Data Release Frequency: No Update Planned

#### IHS OPEN DUMPS: Open Dumps on Indian Land

A listing of all open dumps located on Indian Land in the United States.

Date of Government Version: 04/01/2014 Date Data Arrived at EDR: 08/06/2014 Date Made Active in Reports: 01/29/2015 Number of Days to Update: 176 Source: Department of Health & Human Serivces, Indian Health Service Telephone: 301-443-1452 Last EDR Contact: 11/01/2019 Next Scheduled EDR Contact: 02/10/2020 Data Release Frequency: Varies

### Local Lists of Hazardous waste / Contaminated Sites

US HIST CDL: National Clandestine Laboratory Register

A listing of clandestine drug lab locations that have been removed from the DEAs National Clandestine Laboratory Register.

Date of Government Version: 06/11/2019	Source: Drug Enforcement Administration
Date Data Arrived at EDR: 06/13/2019	Telephone: 202-307-1000
Date Made Active in Reports: 09/03/2019	Last EDR Contact: 11/20/2019
Number of Days to Update: 82	Next Scheduled EDR Contact: 03/09/2020
	Data Release Frequency: No Update Planned

## PRIORITYCLEANERS: Priority Ranking List

The Florida Legislature has established a state-funded program to cleanup properties that are contaminated as a result of the operations of a drycleaning facility.

Date of Government Version: 07/15/2019	Source: Department of Environmental Protection
Date Data Arrived at EDR: 08/13/2019	Telephone: 850-245-8927
Date Made Active in Reports: 10/24/2019	Last EDR Contact: 11/12/2019
Number of Days to Update: 72	Next Scheduled EDR Contact: 02/24/2020
	Data Release Frequency: Varies

## FL SITES: Sites List

This summary status report was developed from a number of lists including the Eckhardt list, the Moffit list, the EPA Hazardous Waste Sites list, EPA's Emergency & Remedial Response information System list (RCRA Section 3012) & existing department lists such as the obsolete uncontrolled Hazardous Waste Sites list. This list is no longer updated.

Date of Government Version: 12/31/1989 Date Data Arrived at EDR: 05/09/1994 Date Made Active in Reports: 08/04/1994 Number of Days to Update: 87 Source: Department of Environmental Protection Telephone: 850-245-8705 Last EDR Contact: 03/24/1994 Next Scheduled EDR Contact: N/A Data Release Frequency: No Update Planned

## US CDL: Clandestine Drug Labs

A listing of clandestine drug lab locations. The U.S. Department of Justice ("the Department") provides this web site as a public service. It contains addresses of some locations where law enforcement agencies reported they found chemicals or other items that indicated the presence of either clandestine drug laboratories or dumpsites. In most cases, the source of the entries is not the Department, and the Department has not verified the entry and does not guarantee its accuracy. Members of the public must verify the accuracy of all entries by, for example, contacting local law enforcement and local health departments.

Date of Government Version: 06/11/2019 Date Data Arrived at EDR: 06/13/2019 Date Made Active in Reports: 09/03/2019 Number of Days to Update: 82 Source: Drug Enforcement Administration Telephone: 202-307-1000 Last EDR Contact: 11/20/2019 Next Scheduled EDR Contact: 03/09/2020 Data Release Frequency: Quarterly

PFAS: PFOS and PFOA stand for perfluorooctane sulfonate and perfluorooctanoic acid PFOS and PFOA stand for perfluorooctane sulfonate and perfluorooctanoic acid, respectively. Both are fluorinated organic chemicals, part of a larger family of compounds referred to as perfluoroalkyl substances (PFASs).

Date of Government Version: 10/28/2019 Date Data Arrived at EDR: 10/30/2019 Date Made Active in Reports: 01/07/2020 Number of Days to Update: 69 Source: Department of Environmental Protection Telephone: 850-245-8690 Last EDR Contact: 10/25/2019 Next Scheduled EDR Contact: 02/10/2020 Data Release Frequency: Varies

### Local Land Records

LIENS 2: CERCLA Lien Information

A Federal CERCLA ('Superfund') lien can exist by operation of law at any site or property at which EPA has spent Superfund monies. These monies are spent to investigate and address releases and threatened releases of contamination. CERCLIS provides information as to the identity of these sites and properties.

Date of Government Version: 10/25/2019	Source: Environmental Protection Agency
Date Data Arrived at EDR: 11/07/2019	Telephone: 202-564-6023
Date Made Active in Reports: 11/20/2019	Last EDR Contact: 01/03/2020
Number of Days to Update: 13	Next Scheduled EDR Contact: 04/13/2020
	Data Release Frequency: Semi-Annually

### **Records of Emergency Release Reports**

HMIRS: Hazardous Materials Information Reporting System Hazardous Materials Incident Report System. HMIRS contains hazardous material spill incidents reported to DOT.

Date of Government Version: 06/24/2019	Source: U.S. Department of Transportation
Date Data Arrived at EDR: 06/26/2019	Telephone: 202-366-4555
Date Made Active in Reports: 09/23/2019	Last EDR Contact: 12/06/2019
Number of Days to Update: 89	Next Scheduled EDR Contact: 04/06/2020
	Data Release Frequency: Quarterly

SPILLS: Oil and Hazardous Materials Incidents

Statewide oil and hazardous materials inland incidents.

Date of Government Version: 10/03/2019	Source: Department of Environmental Protection
Date Data Arrived at EDR: 10/03/2019	Telephone: 850-245-2010
Date Made Active in Reports: 12/06/2019	Last EDR Contact: 01/06/2020
Number of Days to Update: 64	Next Scheduled EDR Contact: 04/20/2020
	Data Release Frequency: Semi-Annually

#### SPILLS 90: SPILLS90 data from FirstSearch

Spills 90 includes those spill and release records available exclusively from FirstSearch databases. Typically, they may include chemical, oil and/or hazardous substance spills recorded after 1990. Duplicate records that are already included in EDR incident and release records are not included in Spills 90.

Date of Government Version: 12/10/2012	
Date Data Arrived at EDR: 01/03/2013	
Date Made Active in Reports: 03/04/2013	
Number of Days to Update: 60	

Source: FirstSearch Telephone: N/A Last EDR Contact: 01/03/2013 Next Scheduled EDR Contact: N/A Data Release Frequency: No Update Planned

#### SPILLS 80: SPILLS80 data from FirstSearch

Spills 80 includes those spill and release records available from FirstSearch databases prior to 1990. Typically, they may include chemical, oil and/or hazardous substance spills recorded before 1990. Duplicate records that are already included in EDR incident and release records are not included in Spills 80.

Source: FirstSearch
Telephone: N/A
Last EDR Contact: 01/03/2013
Next Scheduled EDR Contact: N/A
Data Release Frequency: No Update Planned

#### Other Ascertainable Records

RCRA NonGen / NLR: RCRA - Non Generators / No Longer Regulated

RCRAInfo is EPA's comprehensive information system, providing access to data supporting the Resource Conservation and Recovery Act (RCRA) of 1976 and the Hazardous and Solid Waste Amendments (HSWA) of 1984. The database includes selective information on sites which generate, transport, store, treat and/or dispose of hazardous waste as defined by the Resource Conservation and Recovery Act (RCRA). Non-Generators do not presently generate hazardous waste.

Date of Government Version: 12/16/2019 Date Data Arrived at EDR: 12/16/2019 Date Made Active in Reports: 12/20/2019 Number of Days to Update: 4

Source: Environmental Protection Agency Telephone: (404) 562-8651 Last EDR Contact: 12/16/2019 Next Scheduled EDR Contact: 04/06/2020 Data Release Frequency: Quarterly

FUDS: Formerly Used Defense Sites

The listing includes locations of Formerly Used Defense Sites properties where the US Army Corps of Engineers is actively working or will take necessary cleanup actions.

Date of Government Version: 05/15/2019	Source: U.S. Army Corps of Engineers
Date Data Arrived at EDR: 05/21/2019	Telephone: 202-528-4285
Date Made Active in Reports: 08/08/2019	Last EDR Contact: 11/19/2019
Number of Days to Update: 79	Next Scheduled EDR Contact: 03/02/2020
	Data Release Frequency: Varies

### DOD: Department of Defense Sites

This data set consists of federally owned or administered lands, administered by the Department of Defense, that have any area equal to or greater than 640 acres of the United States, Puerto Rico, and the U.S. Virgin Islands.

Date of Government Version: 12/31/2005 Date Data Arrived at EDR: 11/10/2006 Date Made Active in Reports: 01/11/2007 Number of Days to Update: 62

Source: USGS Telephone: 888-275-8747 Last EDR Contact: 10/11/2019 Next Scheduled EDR Contact: 01/20/2020 Data Release Frequency: Semi-Annually

### FEDLAND: Federal and Indian Lands

Federally and Indian administrated lands of the United States. Lands included are administrated by: Army Corps of Engineers, Bureau of Reclamation, National Wild and Scenic River, National Wildlife Refuge, Public Domain Land, Wilderness, Wilderness Study Area, Wildlife Management Area, Bureau of Indian Affairs, Bureau of Land Management, Department of Justice, Forest Service, Fish and Wildlife Service, National Park Service.

Date of Government Version: 04/02/2018 Date Data Arrived at EDR: 04/11/2018 Date Made Active in Reports: 11/06/2019 Number of Days to Update: 574

Source: U.S. Geological Survey Telephone: 888-275-8747 Last EDR Contact: 01/09/2020 Next Scheduled EDR Contact: 04/20/2020 Data Release Frequency: N/A

## SCRD DRYCLEANERS: State Coalition for Remediation of Drycleaners Listing

The State Coalition for Remediation of Drycleaners was established in 1998, with support from the U.S. EPA Office of Superfund Remediation and Technology Innovation. It is comprised of representatives of states with established drycleaner remediation programs. Currently the member states are Alabama, Connecticut, Florida, Illinois, Kansas, Minnesota, Missouri, North Carolina, Oregon, South Carolina, Tennessee, Texas, and Wisconsin.

Date of Government Version: 01/01/2017 Date Data Arrived at EDR: 02/03/2017 Date Made Active in Reports: 04/07/2017 Number of Days to Update: 63

Source: Environmental Protection Agency Telephone: 615-532-8599 Last EDR Contact: 12/02/2019 Next Scheduled EDR Contact: 02/24/2020 Data Release Frequency: Varies

## US FIN ASSUR: Financial Assurance Information

All owners and operators of facilities that treat, store, or dispose of hazardous waste are required to provide proof that they will have sufficient funds to pay for the clean up, closure, and post-closure care of their facilities.

Date of Government Version: 09/23/2019 Date Data Arrived at EDR: 09/24/2019 Date Made Active in Reports: 12/20/2019 Number of Days to Update: 87

Source: Environmental Protection Agency Telephone: 202-566-1917 Last EDR Contact: 12/19/2019 Next Scheduled EDR Contact: 04/06/2020 Data Release Frequency: Quarterly

### EPA WATCH LIST: EPA WATCH LIST

EPA maintains a "Watch List" to facilitate dialogue between EPA, state and local environmental agencies on enforcement matters relating to facilities with alleged violations identified as either significant or high priority. Being on the Watch List does not mean that the facility has actually violated the law only that an investigation by EPA or a state or local environmental agency has led those organizations to allege that an unproven violation has in fact occurred. Being on the Watch List does not represent a higher level of concern regarding the alleged violations that were detected, but instead indicates cases requiring additional dialogue between EPA, state and local agencies - primarily because of the length of time the alleged violation has gone unaddressed or unresolved.

Date of Government Version: 08/30/2013	Source: Environmental Protection Agency
Date Data Arrived at EDR: 03/21/2014	Telephone: 617-520-3000
Date Made Active in Reports: 06/17/2014	Last EDR Contact: 10/31/2019
Number of Days to Update: 88	Next Scheduled EDR Contact: 02/17/2020
	Data Release Frequency: Quarterly

### 2020 COR ACTION: 2020 Corrective Action Program List

The EPA has set ambitious goals for the RCRA Corrective Action program by creating the 2020 Corrective Action Universe. This RCRA cleanup baseline includes facilities expected to need corrective action. The 2020 universe contains a wide variety of sites. Some properties are heavily contaminated while others were contaminated but have since been cleaned up. Still others have not been fully investigated yet, and may require little or no remediation. Inclusion in the 2020 Universe does not necessarily imply failure on the part of a facility to meet its RCRA obligations.

Date of Government Version: 09/30/2017 Date Data Arrived at EDR: 05/08/2018 Date Made Active in Reports: 07/20/2018 Number of Days to Update: 73 Source: Environmental Protection Agency Telephone: 703-308-4044 Last EDR Contact: 11/08/2019 Next Scheduled EDR Contact: 02/17/2020 Data Release Frequency: Varies

### TSCA: Toxic Substances Control Act

Toxic Substances Control Act. TSCA identifies manufacturers and importers of chemical substances included on the TSCA Chemical Substance Inventory list. It includes data on the production volume of these substances by plant site.

Date of Government Version: 12/31/2016 Date Data Arrived at EDR: 06/21/2017 Date Made Active in Reports: 01/05/2018 Number of Days to Update: 198 Source: EPA Telephone: 202-260-5521 Last EDR Contact: 12/20/2019 Next Scheduled EDR Contact: 03/30/2020 Data Release Frequency: Every 4 Years

#### TRIS: Toxic Chemical Release Inventory System

Toxic Release Inventory System. TRIS identifies facilities which release toxic chemicals to the air, water and land in reportable quantities under SARA Title III Section 313.

Date of Government Version: 12/31/2017	Source: EPA
Date Data Arrived at EDR: 11/16/2018	Telephone: 202-566-0250
Date Made Active in Reports: 11/21/2019	Last EDR Contact: 11/22/2019
Number of Days to Update: 370	Next Scheduled EDR Contact: 03/02/2020
	Data Release Frequency: Annually

#### SSTS: Section 7 Tracking Systems

Section 7 of the Federal Insecticide, Fungicide and Rodenticide Act, as amended (92 Stat. 829) requires all registered pesticide-producing establishments to submit a report to the Environmental Protection Agency by March 1st each year. Each establishment must report the types and amounts of pesticides, active ingredients and devices being produced, and those having been produced and sold or distributed in the past year.

Date of Government Version: 09/30/2018	Source: EPA
Date Data Arrived at EDR: 04/24/2019	Telephone: 202-564-4203
Date Made Active in Reports: 08/08/2019	Last EDR Contact: 10/23/2019
Number of Days to Update: 106	Next Scheduled EDR Contact: 02/03/2020
	Data Release Frequency: Annually

### ROD: Records Of Decision

Record of Decision. ROD documents mandate a permanent remedy at an NPL (Superfund) site containing technical and health information to aid in the cleanup.

Date of Government Version: 10/25/2019	Sourc
Date Data Arrived at EDR: 11/07/2019	Telep
Date Made Active in Reports: 11/20/2019	Last E
Number of Days to Update: 13	Next S

ce FPA phone: 703-416-0223 EDR Contact: 01/03/2020 Scheduled EDR Contact: 03/16/2020 Data Release Frequency: Annually

### RMP: Risk Management Plans

When Congress passed the Clean Air Act Amendments of 1990, it required EPA to publish regulations and guidance for chemical accident prevention at facilities using extremely hazardous substances. The Risk Management Program Rule (RMP Rule) was written to implement Section 112(r) of these amendments. The rule, which built upon existing industry codes and standards, requires companies of all sizes that use certain flammable and toxic substances to develop a Risk Management Program, which includes a(n): Hazard assessment that details the potential effects of an accidental release, an accident history of the last five years, and an evaluation of worst-case and alternative accidental releases; Prevention program that includes safety precautions and maintenance, monitoring, and employee training measures; and Emergency response program that spells out emergency health care, employee training measures and procedures for informing the public and response agencies (e.g the fire department) should an accident occur.

Date of Government Version: 04/25/2019 Date Data Arrived at EDR: 05/02/2019 Date Made Active in Reports: 05/23/2019 Number of Days to Update: 21

Source: Environmental Protection Agency Telephone: 202-564-8600 Last EDR Contact: 10/21/2019 Next Scheduled EDR Contact: 02/03/2020 Data Release Frequency: Varies

## RAATS: RCRA Administrative Action Tracking System

RCRA Administration Action Tracking System. RAATS contains records based on enforcement actions issued under RCRA pertaining to major violators and includes administrative and civil actions brought by the EPA. For administration actions after September 30, 1995, data entry in the RAATS database was discontinued. EPA will retain a copy of the database for historical records. It was necessary to terminate RAATS because a decrease in agency resources made it impossible to continue to update the information contained in the database.

Date of Government Version: 04/17/1995 Date Data Arrived at EDR: 07/03/1995 Date Made Active in Reports: 08/07/1995 Number of Days to Update: 35

Source: EPA Telephone: 202-564-4104 Last EDR Contact: 06/02/2008 Next Scheduled EDR Contact: 09/01/2008 Data Release Frequency: No Update Planned

PRP: Potentially Responsible Parties

A listing of verified Potentially Responsible Parties

Date of Government Version: 10/25/2019	Source: EPA
Date Data Arrived at EDR: 11/07/2019	Telephone: 202-564-6023
Date Made Active in Reports: 11/21/2019	Last EDR Contact: 01/03/2020
Number of Days to Update: 14	Next Scheduled EDR Contact: 02/17/2020
	Data Release Frequency: Quarterly

## PADS: PCB Activity Database System

PCB Activity Database. PADS Identifies generators, transporters, commercial storers and/or brokers and disposers of PCB's who are required to notify the EPA of such activities.

Date of Government Version: 10/09/2019	Source: EPA
Date Data Arrived at EDR: 10/11/2019	Telephone: 202-566-0500
Date Made Active in Reports: 12/20/2019	Last EDR Contact: 10/11/2019
Number of Days to Update: 70	Next Scheduled EDR Contact: 01/20/2020
Number of Days to Opdate. 70	Data Release Frequency: Annually

#### ICIS: Integrated Compliance Information System

The Integrated Compliance Information System (ICIS) supports the information needs of the national enforcement and compliance program as well as the unique needs of the National Pollutant Discharge Elimination System (NPDES) program.

Date of Government Version: 11/18/2016	Source: Environmental Protection Agency
Date Data Arrived at EDR: 11/23/2016	Telephone: 202-564-2501
Date Made Active in Reports: 02/10/2017	Last EDR Contact: 01/06/2020
Number of Days to Update: 79	Next Scheduled EDR Contact: 04/20/2020
	Data Release Frequency: Quarterly

FTTS: FIFRA/ TSCA Tracking System - FIFRA (Federal Insecticide, Fungicide, & Rodenticide Act)/TSCA (Toxic Substances Control Act) FTTS tracks administrative cases and pesticide enforcement actions and compliance activities related to FIFRA, TSCA and EPCRA (Emergency Planning and Community Right-to-Know Act). To maintain currency, EDR contacts the Agency on a quarterly basis.

Date of Government Version: 04/09/2009	Source: EPA/Office of Prevention, Pesticides and Toxic Substances
Date Data Arrived at EDR: 04/16/2009	Telephone: 202-566-1667
Date Made Active in Reports: 05/11/2009	Last EDR Contact: 08/18/2017
Number of Days to Update: 25	Next Scheduled EDR Contact: 12/04/2017
	Data Release Frequency: No Update Planned

FTTS INSP: FIFRA/ TSCA Tracking System - FIFRA (Federal Insecticide, Fungicide, & Rodenticide Act)/TSCA (Toxic Substances Control Act) A listing of FIFRA/TSCA Tracking System (FTTS) inspections and enforcements.

Date of Government Version: 04/09/2009	Source: EPA
Date Data Arrived at EDR: 04/16/2009	Telephone: 202-566-1667
Date Made Active in Reports: 05/11/2009	Last EDR Contact: 08/18/2017
Number of Days to Update: 25	Next Scheduled EDR Contact: 12/04/2017
	Data Release Frequency: No Update Planned

## MLTS: Material Licensing Tracking System

MLTS is maintained by the Nuclear Regulatory Commission and contains a list of approximately 8,100 sites which possess or use radioactive materials and which are subject to NRC licensing requirements. To maintain currency, EDR contacts the Agency on a quarterly basis.

Date of Government Version: 06/20/2019 Date Data Arrived at EDR: 06/20/2019 Date Made Active in Reports: 08/08/2019 Number of Days to Update: 49 Source: Nuclear Regulatory Commission Telephone: 301-415-7169 Last EDR Contact: 10/25/2019 Next Scheduled EDR Contact: 02/03/2020 Data Release Frequency: Quarterly

## COAL ASH DOE: Steam-Electric Plant Operation Data

A listing of power plants that store ash in surface ponds.

Date of Government Version: 12/31/2005	Source: Department of Energy
Date Data Arrived at EDR: 08/07/2009	Telephone: 202-586-8719
Date Made Active in Reports: 10/22/2009	Last EDR Contact: 12/04/2019
Number of Days to Update: 76	Next Scheduled EDR Contact: 03/16/2020
	Data Release Frequency: Varies

COAL ASH EPA: Coal Combustion Residues Surface Impoundments List A listing of coal combustion residues surface impoundments with high hazard potential ratings.

Date of Government Version: 01/12/2017	Source: Environmental Protection Agency
Date Data Arrived at EDR: 03/05/2019	Telephone: N/A
Date Made Active in Reports: 11/11/2019	Last EDR Contact: 11/25/2019
Number of Days to Update: 251	Next Scheduled EDR Contact: 03/16/2020
	Data Release Frequency: Varies

PCB TRANSFORMER: PCB Transformer Registra The database of PCB transformer registration	ation Database ns that includes all PCB registration submittals.
Date of Government Version: 05/24/2017 Date Data Arrived at EDR: 11/30/2017 Date Made Active in Reports: 12/15/2017 Number of Days to Update: 15	Source: Environmental Protection Agency Telephone: 202-566-0517 Last EDR Contact: 11/06/2019 Next Scheduled EDR Contact: 02/17/2020 Data Release Frequency: Varies
RADINFO: Radiation Information Database The Radiation Information Database (RADIN Environmental Protection Agency (EPA) regu	FO) contains information about facilities that are regulated by U.S. Ilations for radiation and radioactivity.

Date of Government Version: 07/01/2019 Date Data Arrived at EDR: 07/01/2019 Date Made Active in Reports: 09/23/2019 Number of Days to Update: 84 Source: Environmental Protection Agency Telephone: 202-343-9775 Last EDR Contact: 12/20/2019 Next Scheduled EDR Contact: 04/13/2020 Data Release Frequency: Quarterly

HIST FTTS: FIFRA/TSCA Tracking System Administrative Case Listing

A complete administrative case listing from the FIFRA/TSCA Tracking System (FTTS) for all ten EPA regions. The information was obtained from the National Compliance Database (NCDB). NCDB supports the implementation of FIFRA (Federal Insecticide, Fungicide, and Rodenticide Act) and TSCA (Toxic Substances Control Act). Some EPA regions are now closing out records. Because of that, and the fact that some EPA regions are not providing EPA Headquarters with updated records, it was decided to create a HIST FTTS database. It included records that may not be included in the newer FTTS database updates. This database is no longer updated.

Date of Government Version: 10/19/2006 Date Data Arrived at EDR: 03/01/2007 Date Made Active in Reports: 04/10/2007 Number of Days to Update: 40 Source: Environmental Protection Agency Telephone: 202-564-2501 Last EDR Contact: 12/17/2007 Next Scheduled EDR Contact: 03/17/2008 Data Release Frequency: No Update Planned

HIST FTTS INSP: FIFRA/TSCA Tracking System Inspection & Enforcement Case Listing

A complete inspection and enforcement case listing from the FIFRA/TSCA Tracking System (FTTS) for all ten EPA regions. The information was obtained from the National Compliance Database (NCDB). NCDB supports the implementation of FIFRA (Federal Insecticide, Fungicide, and Rodenticide Act) and TSCA (Toxic Substances Control Act). Some EPA regions are now closing out records. Because of that, and the fact that some EPA regions are not providing EPA Headquarters with updated records, it was decided to create a HIST FTTS database. It included records that may not be included in the newer FTTS database updates. This database is no longer updated.

Date of Government Version: 10/19/2006Source: Environmental Protection AgencyDate Data Arrived at EDR: 03/01/2007Telephone: 202-564-2501Date Made Active in Reports: 04/10/2007Last EDR Contact: 12/17/2008Number of Days to Update: 40Next Scheduled EDR Contact: 03/17/2008Data Release Frequency: No Update Planned

DOT OPS: Incident and Accident Data

Department of Transporation, Office of Pipeline Safety Incident and Accident data.

Date of Government Version: 07/01/2019	Source: Department of Transporation, Office of Pipeline Safety
Date Data Arrived at EDR: 07/31/2019	Telephone: 202-366-4595
Date Made Active in Reports: 10/24/2019	Last EDR Contact: 10/29/2019
Number of Days to Update: 85	Next Scheduled EDR Contact: 02/10/2020
	Data Release Frequency: Quarterly

CONSENT: Superfund (CERCLA) Consent Decrees

Major legal settlements that establish responsibility and standards for cleanup at NPL (Superfund) sites. Released periodically by United States District Courts after settlement by parties to litigation matters.

Date of Government Version: 09/30/2019 Date Data Arrived at EDR: 10/09/2019 Date Made Active in Reports: 12/20/2019 Number of Days to Update: 72 Source: Department of Justice, Consent Decree Library Telephone: Varies Last EDR Contact: 01/06/2020 Next Scheduled EDR Contact: 04/20/2020 Data Release Frequency: Varies

BRS: Biennial Reporting System

The Biennial Reporting System is a national system administered by the EPA that collects data on the generation and management of hazardous waste. BRS captures detailed data from two groups: Large Quantity Generators (LQG) and Treatment, Storage, and Disposal Facilities.

Date of Government Version: 12/31/2015 Date Data Arrived at EDR: 02/22/2017 Date Made Active in Reports: 09/28/2017 Number of Days to Update: 218 Source: EPA/NTIS Telephone: 800-424-9346 Last EDR Contact: 12/16/2019 Next Scheduled EDR Contact: 04/06/2020 Data Release Frequency: Biennially

## INDIAN RESERV: Indian Reservations

This map layer portrays Indian administered lands of the United States that have any area equal to or greater than 640 acres.

Date of Government Version: 12/31/2014 Date Data Arrived at EDR: 07/14/2015 Date Made Active in Reports: 01/10/2017 Number of Days to Update: 546 Source: USGS Telephone: 202-208-3710 Last EDR Contact: 01/07/2020 Next Scheduled EDR Contact: 04/20/2020 Data Release Frequency: Semi-Annually

## FUSRAP: Formerly Utilized Sites Remedial Action Program

DOE established the Formerly Utilized Sites Remedial Action Program (FUSRAP) in 1974 to remediate sites where radioactive contamination remained from Manhattan Project and early U.S. Atomic Energy Commission (AEC) operations.

Date of Government Version: 08/08/2017 Date Data Arrived at EDR: 09/11/2018 Date Made Active in Reports: 09/14/2018 Number of Days to Update: 3 Source: Department of Energy Telephone: 202-586-3559 Last EDR Contact: 11/04/2019 Next Scheduled EDR Contact: 02/17/2020 Data Release Frequency: Varies

#### UMTRA: Uranium Mill Tailings Sites

Uranium ore was mined by private companies for federal government use in national defense programs. When the mills shut down, large piles of the sand-like material (mill tailings) remain after uranium has been extracted from the ore. Levels of human exposure to radioactive materials from the piles are low; however, in some cases tailings were used as construction materials before the potential health hazards of the tailings were recognized.

Date of Government Version: 08/01/2019	Source: Department of Energy
Date Data Arrived at EDR: 08/21/2019	Telephone: 505-845-0011
Date Made Active in Reports: 11/11/2019	Last EDR Contact: 11/15/2019
Number of Days to Update: 82	Next Scheduled EDR Contact: 03/02/2020
	Data Release Frequency: Varies

#### LEAD SMELTER 1: Lead Smelter Sites

A listing of former lead smelter site locations.

Date of Government Version: 10/25/2019	Sour
Date Data Arrived at EDR: 11/07/2019	Tele
Date Made Active in Reports: 11/20/2019	Last
Number of Days to Update: 13	Next

Source: Environmental Protection Agency Telephone: 703-603-8787 Last EDR Contact: 01/03/2020 Next Scheduled EDR Contact: 04/13/2020 Data Release Frequency: Varies

## LEAD SMELTER 2: Lead Smelter Sites

A list of several hundred sites in the U.S. where secondary lead smelting was done from 1931and 1964. These sites may pose a threat to public health through ingestion or inhalation of contaminated soil or dust

Date of Government Version: 04/05/2001 Date Data Arrived at EDR: 10/27/2010 Date Made Active in Reports: 12/02/2010 Number of Days to Update: 36 Source: American Journal of Public Health Telephone: 703-305-6451 Last EDR Contact: 12/02/2009 Next Scheduled EDR Contact: N/A Data Release Frequency: No Update Planned

US AIRS (AFS): Aerometric Information Retrieval System Facility Subsystem (AFS)

The database is a sub-system of Aerometric Information Retrieval System (AIRS). AFS contains compliance data on air pollution point sources regulated by the U.S. EPA and/or state and local air regulatory agencies. This information comes from source reports by various stationary sources of air pollution, such as electric power plants, steel mills, factories, and universities, and provides information about the air pollutants they produce. Action, air program, air program pollutant, and general level plant data. It is used to track emissions and compliance data from industrial plants.

Date of Government Version: 10/12/2016 Date Data Arrived at EDR: 10/26/2016 Date Made Active in Reports: 02/03/2017 Number of Days to Update: 100	Source: EPA Telephone: 202-564-2496 Last EDR Contact: 09/26/2017 Next Scheduled EDR Contact: 01/08/2018 Data Release Frequency: Annually
US AIRS MINOR: Air Facility System Data	

US AIRS MINOR: Air Facility System Data A listing of minor source facilities.

> Date of Government Version: 10/12/2016 Date Data Arrived at EDR: 10/26/2016 Date Made Active in Reports: 02/03/2017 Number of Days to Update: 100

Source: EPA Telephone: 202-564-2496 Last EDR Contact: 09/26/2017 Next Scheduled EDR Contact: 01/08/2018 Data Release Frequency: Annually

MINES VIOLATIONS: MSHA Violation Assessment Data

Mines violation and assessment information. Department of Labor, Mine Safety & Health Administration.

Date of Government Version: 09/17/2019	Source: DOL, Mine Safety & Health Admi
Date Data Arrived at EDR: 09/18/2019	Telephone: 202-693-9424
Date Made Active in Reports: 12/03/2019	Last EDR Contact: 12/02/2019
Number of Days to Update: 76	Next Scheduled EDR Contact: 03/16/2020
	Data Release Frequency: Quarterly

US MINES: Mines Master Index File

Contains all mine identification numbers issued for mines active or opened since 1971. The data also includes violation information.

Date of Government Version: 08/01/2019 Date Data Arrived at EDR: 08/27/2019	Source: Department of Labor, Mine Safety and Health Administration Telephone: 303-231-5959
Date Made Active in Reports: 11/11/2019	Last EDR Contact: 11/25/2019
Number of Days to Update: 76	Next Scheduled EDR Contact: 03/09/2020
	Data Release Frequency: Semi-Annually

#### US MINES 2: Ferrous and Nonferrous Metal Mines Database Listing

This map layer includes ferrous (ferrous metal mines are facilities that extract ferrous metals, such as iron ore or molybdenum) and nonferrous (Nonferrous metal mines are facilities that extract nonferrous metals, such as gold, silver, copper, zinc, and lead) metal mines in the United States.

Date of Government Version: 12/05/2005	Source: USGS
Date Data Arrived at EDR: 02/29/2008	Telephone: 703-648-7709
Date Made Active in Reports: 04/18/2008	Last EDR Contact: 11/22/2019
Number of Days to Update: 49	Next Scheduled EDR Contact: 03/09/2020
	Data Release Frequency: Varies

### US MINES 3: Active Mines & Mineral Plants Database Listing

Active Mines and Mineral Processing Plant operations for commodities monitored by the Minerals Information Team of the USGS.

Date of Government Version: 04/14/2011 Date Data Arrived at EDR: 06/08/2011 Date Made Active in Reports: 09/13/2011 Number of Days to Update: 97 Source: USGS Telephone: 703-648-7709 Last EDR Contact: 11/22/2019 Next Scheduled EDR Contact: 03/09/2020 Data Release Frequency: Varies

#### ABANDONED MINES: Abandoned Mines

An inventory of land and water impacted by past mining (primarily coal mining) is maintained by OSMRE to provide information needed to implement the Surface Mining Control and Reclamation Act of 1977 (SMCRA). The inventory contains information on the location, type, and extent of AML impacts, as well as, information on the cost associated with the reclamation of those problems. The inventory is based upon field surveys by State, Tribal, and OSMRE program officials. It is dynamic to the extent that it is modified as new problems are identified and existing problems are reclaimed.

Date of Government Version: 09/10/2019 Date Data Arrived at EDR: 09/10/2019 Date Made Active in Reports: 10/17/2019 Number of Days to Update: 37 Source: Department of Interior Telephone: 202-208-2609 Last EDR Contact: 12/04/2019 Next Scheduled EDR Contact: 03/23/2020 Data Release Frequency: Quarterly

## FINDS: Facility Index System/Facility Registry System

Facility Index System. FINDS contains both facility information and 'pointers' to other sources that contain more detail. EDR includes the following FINDS databases in this report: PCS (Permit Compliance System), AIRS (Aerometric Information Retrieval System), DOCKET (Enforcement Docket used to manage and track information on civil judicial enforcement cases for all environmental statutes), FURS (Federal Underground Injection Control), C-DOCKET (Criminal Docket System used to track criminal enforcement actions for all environmental statutes), FFIS (Federal Facilities Information System), STATE (State Environmental Laws and Statutes), and PADS (PCB Activity Data System).

Date of Government Version: 08/12/2019 Date Data Arrived at EDR: 09/04/2019 Date Made Active in Reports: 12/03/2019 Number of Days to Update: 90 Source: EPA Telephone: (404) 562-9900 Last EDR Contact: 12/04/2019 Next Scheduled EDR Contact: 03/16/2020 Data Release Frequency: Quarterly

## DOCKET HWC: Hazardous Waste Compliance Docket Listing

A complete list of the Federal Agency Hazardous Waste Compliance Docket Facilities.

Date of Government Version: 05/31/2018	Source: Environmental Protection Agency
Date Data Arrived at EDR: 07/26/2018	Telephone: 202-564-0527
Date Made Active in Reports: 10/05/2018	Last EDR Contact: 11/20/2019
Number of Days to Update: 71	Next Scheduled EDR Contact: 03/09/2020
	Data Release Frequency: Varies

### UXO: Unexploded Ordnance Sites

A listing of unexploded ordnance site locations

Date of Government Version: 12/31/2017 Date Data Arrived at EDR: 01/17/2019 Date Made Active in Reports: 04/01/2019 Number of Days to Update: 74 Source: Department of Defense Telephone: 703-704-1564 Last EDR Contact: 10/10/2019 Next Scheduled EDR Contact: 01/27/2020 Data Release Frequency: Varies

ECHO: Enforcement & Compliance History Information

ECHO provides integrated compliance and enforcement information for about 800,000 regulated facilities nationwide.

Date of Government Version: 10/06/2019 Date Data Arrived at EDR: 10/08/2019 Date Made Active in Reports: 01/02/2020 Number of Days to Update: 86	Source: Environmental Protection Agency Telephone: 202-564-2280 Last EDR Contact: 01/07/2020 Next Scheduled EDR Contact: 04/20/2020 Data Release Frequency: Quarterly
FUELS PROGRAM: EPA Fuels Program Register This listing includes facilities that are register Programs. All companies now are required to	ed under the Part 80 (Code of Federal Regulations) EPA Fuels
Date of Government Version: 08/19/2019 Date Data Arrived at EDR: 08/20/2019 Date Made Active in Reports: 11/11/2019 Number of Days to Update: 83	Source: EPA Telephone: 800-385-6164 Last EDR Contact: 11/19/2019 Next Scheduled EDR Contact: 03/02/2020 Data Release Frequency: Quarterly
AIRS: Permitted Facilities Listing A listing of Air Resources Management perm	its.
Date of Government Version: 05/14/2019 Date Data Arrived at EDR: 05/16/2019 Date Made Active in Reports: 06/14/2019 Number of Days to Update: 29	Source: Department of Environmental Protection Telephone: 850-921-9558 Last EDR Contact: 10/23/2019 Next Scheduled EDR Contact: 02/10/2020 Data Release Frequency: Varies
ASBESTOS: Asbestos Notification Listing Asbestos sites	
Date of Government Version: 08/14/2019 Date Data Arrived at EDR: 08/20/2019 Date Made Active in Reports: 10/29/2019 Number of Days to Update: 70	Source: Department of Environmental Protection Telephone: 850-717-9086 Last EDR Contact: 11/14/2019 Next Scheduled EDR Contact: 03/02/2020 Data Release Frequency: Varies
data includes Hazardous Waste programs, S	ation Locator Map Listing eanup sites from various programs. The source of the cleanup site ite Investigation Section, Compliance and Enforcement Tracking, Drycleaning er state funded cleanup), Storage Tank Contamination Monitoring.
Date of Government Version: 08/26/2019 Date Data Arrived at EDR: 08/26/2019 Date Made Active in Reports: 11/05/2019 Number of Days to Update: 71	Source: Department of Environmental Protection Telephone: 866-282-0787 Last EDR Contact: 11/22/2019 Next Scheduled EDR Contact: 03/09/2020 Data Release Frequency: Quarterly
	at has been detected in drinking water wells. The amount found stated in Chapter 62-550 or 520. It is a potential threat to public health
Date of Government Version: 09/20/2019 Date Data Arrived at EDR: 09/24/2019 Date Made Active in Reports: 12/05/2019	Source: Department of Environmental Protection Telephone: 850-245-8335 Last EDR Contact: 12/11/2019

The Drycleaners database, maintained by the Department of Environmental Protection, provides information about permitted dry cleaner facilities.

Date of Government Version: 10/21/2019		
Date Data Arrived at EDR: 10/22/2019		
Date Made Active in Reports: 12/31/2019		
Number of Days to Update: 70		

Source: Department of Environmental Protection Telephone: 850-245-8927 Last EDR Contact: 10/22/2019 Next Scheduled EDR Contact: 02/03/2020 Data Release Frequency: Semi-Annually

### DWM CONTAM: DWM CONTAMINATED SITES

A listing of active or known sites. The listing includes sites that need cleanup but are not actively being working on because the agency currently does not have funding (primarily petroleum and drycleaning).

Date of Government Version: 01/28/2019 Date Data Arrived at EDR: 01/29/2019 Date Made Active in Reports: 03/28/2019 Number of Days to Update: 58 Source: Department of Environmental Protection Telephone: 850-245-7503 Last EDR Contact: 01/06/2020 Next Scheduled EDR Contact: 04/20/2020 Data Release Frequency: Varies

Financial Assurance 1: Financial Assurance Information Listing

A list of hazardous waste facilities required to provide financial assurance under RCRA.

Date of Government Version: 10/28/2019	Source: Department of Environmental Protection
Date Data Arrived at EDR: 10/29/2019	Telephone: 850-245-8793
Date Made Active in Reports: 01/06/2020	Last EDR Contact: 10/25/2019
Number of Days to Update: 69	Next Scheduled EDR Contact: 02/10/2020
	Data Release Frequency: Semi-Annually

## Financial Assurance 2: Financial Assurance Information Listing

A listing of financial assurance information for solid waste facilities.

Date of Government Version: 10/25/2019	Source: Department of Environmental Protection
Date Data Arrived at EDR: 10/29/2019	Telephone: 850-245-8743
Date Made Active in Reports: 01/06/2020	Last EDR Contact: 10/25/2019
Number of Days to Update: 69	Next Scheduled EDR Contact: 02/10/2020
	Data Release Frequency: Semi-Annually

## Financial Assurance 3: Financial Assurance Information Listing

A listing of financial assurance information for storage tanks sites.

Date of Government Version: 10/29/2019		
Date Data Arrived at EDR: 10/30/2019		
Date Made Active in Reports: 01/06/2020		
Number of Days to Update: 68		

Source: Department of Environmental Protection Telephone: 850-245-8853 Last EDR Contact: 10/25/2019 Next Scheduled EDR Contact: 02/10/2020 Data Release Frequency: Quarterly

## FL Cattle Dip. Vats: Cattle Dipping Vats

From the 1910's through the 1950's, these vats were filled with an arsenic solution for the control and eradication of the cattle fever tick. Other pesticides, such as DDT, were also widely used. By State law, all cattle, horses, mules, goats, and other susceptible animals were required to be dipped every 14 days. Under certain circumstances, the arsenic and other pesticides remaining at the site may present an environmental or public health hazard.

Source: Department of Environmental Protection Telephone: 850-245-4444 Last EDR Contact: 01/09/2020 Next Scheduled EDR Contact: 04/20/2020 Data Release Frequency: No Update Planned

RESP PARTY: Responsible Party Sites Listing Open, inactive and closed responsible party sites

Date of Government Version: 09/29/2019 Date Data Arrived at EDR: 10/01/2019 Date Made Active in Reports: 12/05/2019 Number of Days to Update: 65 Source: Department of Environmental Protection Telephone: 850-245-8758 Last EDR Contact: 01/02/2020 Next Scheduled EDR Contact: 04/13/2020 Data Release Frequency: Quarterly

SITE INV SITES: Site Investigation Section Sites Listing Statewide coverage of Site Investigation Section (SIS) sites. Site Investigation is a Section within the Bureau of Waste Cleanup, Division of Waste Management. SIS provides technical support to FDEP District Waste Cleanup Programs and conducts contamination assessments throughout the state.	
Date of Government Version: 08/19/2019 Date Data Arrived at EDR: 08/20/2019 Date Made Active in Reports: 10/30/2019 Number of Days to Update: 71	Source: Department of Environmental Protection Telephone: 850-245-8953 Last EDR Contact: 11/19/2019 Next Scheduled EDR Contact: 03/02/2020 Data Release Frequency: Quarterly
TIER 2: Tier 2 Facility Listing A listing of facilities which store or manufacture	e hazardous materials that submit a chemical inventory report.
Date of Government Version: 12/31/2018 Date Data Arrived at EDR: 06/13/2019 Date Made Active in Reports: 08/27/2019 Number of Days to Update: 75	Source: Department of Environmental Protection Telephone: 850-413-9970 Last EDR Contact: 12/05/2019 Next Scheduled EDR Contact: 03/23/2020 Data Release Frequency: Varies
UIC: Underground Injection Wells Database Listing A listing of Class I wells. Class I wells are used waste below the lowermost USDW.	d to inject hazardous waste, nonhazardous waste, or municipal
Date of Government Version: 10/17/2019 Date Data Arrived at EDR: 10/22/2019 Date Made Active in Reports: 12/24/2019 Number of Days to Update: 63	Source: Department of Environmental Protection Telephone: 850-245-8655 Last EDR Contact: 10/17/2019 Next Scheduled EDR Contact: 02/03/2020 Data Release Frequency: Varies
WASTEWATER: Wastewater Facility Regulation Da Domestic and industrial wastewater facilities.	atabase
Date of Government Version: 08/01/2019 Date Data Arrived at EDR: 08/06/2019 Date Made Active in Reports: 10/15/2019 Number of Days to Update: 70	Source: Department of Environmental Protection Telephone: 850-245-8600 Last EDR Contact: 11/05/2019 Next Scheduled EDR Contact: 02/17/2020 Data Release Frequency: Quarterly
MINES MRDS: Mineral Resources Data System Mineral Resources Data System	
Date of Government Version: 04/06/2018 Date Data Arrived at EDR: 10/21/2019 Date Made Active in Reports: 10/24/2019 Number of Days to Update: 3	Source: USGS Telephone: 703-648-6533 Last EDR Contact: 11/22/2019 Next Scheduled EDR Contact: 03/09/2020 Data Release Frequency: Varies
•	Next Scheduled EDR Contact: 03/09/2020

EDR MGP: EDR Proprietary Manufactured Gas Plants

The EDR Proprietary Manufactured Gas Plant Database includes records of coal gas plants (manufactured gas plants) compiled by EDR's researchers. Manufactured gas sites were used in the United States from the 1800's to 1950's to produce a gas that could be distributed and used as fuel. These plants used whale oil, rosin, coal, or a mixture of coal, oil, and water that also produced a significant amount of waste. Many of the byproducts of the gas production, such as coal tar (oily waste containing volatile and non-volatile chemicals), sludges, oils and other compounds are potentially hazardous to human health and the environment. The byproduct from this process was frequently disposed of directly at the plant site and can remain or spread slowly, serving as a continuous source of soil and groundwater contamination.

Date of Government Version: N/A Date Data Arrived at EDR: N/A Date Made Active in Reports: N/A Number of Days to Update: N/A Source: EDR, Inc. Telephone: N/A Last EDR Contact: N/A Next Scheduled EDR Contact: N/A Data Release Frequency: No Update Planned

### EDR Hist Auto: EDR Exclusive Historical Auto Stations

EDR has searched selected national collections of business directories and has collected listings of potential gas station/filling station/service station sites that were available to EDR researchers. EDR's review was limited to those categories of sources that might, in EDR's opinion, include gas station/filling station/service station establishments. The categories reviewed included, but were not limited to gas, gas station, gasoline station, filling station, auto, automobile repair, auto service station, service station, etc. This database falls within a category of information EDR classifies as "High Risk Historical Records", or HRHR. EDR's HRHR effort presents unique and sometimes proprietary data about past sites and operations that typically create environmental concerns, but may not show up in current government records searches.

Date of Government Version: N/A Date Data Arrived at EDR: N/A Date Made Active in Reports: N/A Number of Days to Update: N/A Source: EDR, Inc. Telephone: N/A Last EDR Contact: N/A Next Scheduled EDR Contact: N/A Data Release Frequency: Varies

## EDR Hist Cleaner: EDR Exclusive Historical Cleaners

EDR has searched selected national collections of business directories and has collected listings of potential dry cleaner sites that were available to EDR researchers. EDR's review was limited to those categories of sources that might, in EDR's opinion, include dry cleaning establishments. The categories reviewed included, but were not limited to dry cleaners, cleaners, laundry, laundromat, cleaning/laundry, wash & dry etc. This database falls within a category of information EDR classifies as "High Risk Historical Records", or HRHR. EDR's HRHR effort presents unique and sometimes proprietary data about past sites and operations that typically create environmental concerns, but may not show up in current government records searches.

Date of Government Version: N/A Date Data Arrived at EDR: N/A Date Made Active in Reports: N/A Number of Days to Update: N/A Source: EDR, Inc. Telephone: N/A Last EDR Contact: N/A Next Scheduled EDR Contact: N/A Data Release Frequency: Varies

## EDR RECOVERED GOVERNMENT ARCHIVES

## Exclusive Recovered Govt. Archives

RGA HWS: Recovered Government Archive State Hazardous Waste Facilities List

The EDR Recovered Government Archive State Hazardous Waste database provides a list of SHWS incidents derived from historical databases and includes many records that no longer appear in current government lists. Compiled from Records formerly available from the Department of Environmental Protection in Floridia.

Date of Government Version: N/A Date Data Arrived at EDR: 07/01/2013 Date Made Active in Reports: 12/30/2013 Number of Days to Update: 182 Source: Department of Environmental Protection Telephone: N/A Last EDR Contact: 06/01/2012 Next Scheduled EDR Contact: N/A Data Release Frequency: Varies

## RGA LF: Recovered Government Archive Solid Waste Facilities List

The EDR Recovered Government Archive Landfill database provides a list of landfills derived from historical databases and includes many records that no longer appear in current government lists. Compiled from Records formerly available from the Department of Environmental Protection in Floridia.

Date of Government Version: N/A	Source: Department of Environmental Protection
Date Data Arrived at EDR: 07/01/2013	Telephone: N/A
Date Made Active in Reports: 01/10/2014	Last EDR Contact: 06/01/2012
Number of Days to Update: 193	Next Scheduled EDR Contact: N/A
	Data Release Frequency: Varies

RGA LUST: Recovered Government Archive Leaking Underground Storage Tank

The EDR Recovered Government Archive Leaking Underground Storage Tank database provides a list of LUST incidents derived from historical databases and includes many records that no longer appear in current government lists. Compiled from Records formerly available from the Department of Environmental Protection in Floridia.

Last EDR Contact: 06/01/2012

Next Scheduled EDR Contact: N/A Data Release Frequency: Varies

Telephone: N/A

Source: Department of Environmental Protection

Date of Government Version: N/A Date Data Arrived at EDR: 07/01/2013 Date Made Active in Reports: 12/30/2013 Number of Days to Update: 182

### COUNTY RECORDS

#### ALACHUA COUNTY:

FACILITY LIST ALACHUA: Facility List List of all regulated facilities in Alachua County.

Date of Government Version: 03/25/2019Source: Alachua County Environmental Protection DepartmentDate Data Arrived at EDR: 03/26/2019Telephone: 352-264-6800Date Made Active in Reports: 04/30/2019Last EDR Contact: 12/17/2019Number of Days to Update: 35Next Scheduled EDR Contact: 04/06/2020Data Release Frequency: Annually

## BROWARD COUNTY:

AST BROWARD: Aboveground Storage Tanks Aboveground storage tank locations in Broward County.

Date of Government Version: 06/28/2019 Date Data Arrived at EDR: 07/01/2019 Date Made Active in Reports: 09/12/2019 Number of Days to Update: 73 Source: Broward County Environmental Protection Department Telephone: 954-818-7509 Last EDR Contact: 01/03/2020 Next Scheduled EDR Contact: 03/09/2020 Data Release Frequency: Varies

UST BROWARD: Underground Storage Tanks

All known regulated storage tanks within Broward County, including those tanks that have been closed

Date of Government Version: 06/28/2019	Source: Broward County Environmental Protection Department
Date Data Arrived at EDR: 07/01/2019	Telephone: 954-818-7509
Date Made Active in Reports: 09/12/2019	Last EDR Contact: 01/03/2020
Number of Days to Update: 73	Next Scheduled EDR Contact: 03/09/2020
	Data Release Frequency: Varies

### HILLSBOROUGH COUNTY:

LF HILLSBOROUGH: Hillsborough County LF Hillsborough county landfill sites.

> Date of Government Version: 05/02/2019 Date Data Arrived at EDR: 05/03/2019 Date Made Active in Reports: 06/06/2019 Number of Days to Update: 34

Source: Hillsborough County Environmental Protection Commission Telephone: 813-627-2600 Last EDR Contact: 01/06/2020 Next Scheduled EDR Contact: 04/20/2020 Data Release Frequency: Varies

MIAMI-DADE COUNTY:

## DADE CO AP: Air Permit Sites

Facilities that release or have a potential to release pollutants.

	Facilities that release or have a potential to release pollutants.		
	Date of Government Version: 08/26/2019 Date Data Arrived at EDR: 08/26/2019 Date Made Active in Reports: 11/05/2019 Number of Days to Update: 71	Source: Department of Environmental Resources Management Telephone: 305-372-6755 Last EDR Contact: 11/22/2019 Next Scheduled EDR Contact: 03/09/2020 Data Release Frequency: Semi-Annually	
	DADE CO AW: Agricultural Waste Listing A listing of agricultural waste sites		
	Date of Government Version: 08/26/2019 Date Data Arrived at EDR: 08/26/2019 Date Made Active in Reports: 11/05/2019 Number of Days to Update: 71	Source: Miami-Dade County Division of Environmental Resources Management Telephone: 305-372-6715 Last EDR Contact: 11/20/2019 Next Scheduled EDR Contact: 03/09/2020 Data Release Frequency: Varies	
	DADE CO LW: Liquid Waste Transporter List The Liquid Waste Transporter permit regulates the transportation of various types of liquid and solid waste, including hazardous waste, waste oil and oily waste waters, septic and grease trap waste, biomedical waste, spent radiator fluid, photo chemical waste, dry sewage sludge, and other types of non-hazardous industrial waste. The Liquid Waste Transporter permits needed to protect the environment and the public from improperly handled and transported waste.		
	Date of Government Version: 08/26/2019 Date Data Arrived at EDR: 08/26/2019 Date Made Active in Reports: 11/05/2019 Number of Days to Update: 71	Source: DERM Telephone: 305-372-6755 Last EDR Contact: 11/22/2019 Next Scheduled EDR Contact: 03/09/2020 Data Release Frequency: Quarterly	
DADE MOP: Marine Facilities Operating Permit What is this permit used for? Miami-Dade County Ordinance 89-104 and Section 24-18 of the Code of Miami-Dade County require the following types of marine facilities to obtain annual operating permits from DERM: All recreational boat docking facilities with ten (10) or more boat slips, moorings, davit spaces, and vessel tie-up spaces. All boat storage facilities contiguous to tidal waters in Miami-Dade County with ten (10) or more dry storage spaces including boatyards and boat manufacturing facilities.			
	Date of Government Version: 08/26/2019 Date Data Arrived at EDR: 08/26/2019 Date Made Active in Reports: 11/05/2019 Number of Days to Update: 71	Source: DERM Telephone: 305-372-3576 Last EDR Contact: 11/22/2019 Next Scheduled EDR Contact: 03/09/2020 Data Release Frequency: Quarterly	
DADE MRE: Maimi River Enforcement The Miami River Enforcement database files were created for facilities and in some instances vessels that were inspected by a workgroup within the Department that was identified as the Miami River Enforcement Group. The files do not all necessarily reflect enforcement cases and some were created for locations that were permitted by other Sections within the Department.			
	Date of Government Version: 06/05/2013 Date Data Arrived at EDR: 06/06/2013 Date Made Active in Reports: 08/06/2013 Number of Days to Update: 61	Source: DERM Telephone: 305-372-3576 Last EDR Contact: 11/22/2019 Next Scheduled EDR Contact: 03/09/2020 Data Release Frequency: Quarterly	

DADE\_IWP: Industrial Waste Permit Sites

Facilities that either generate more than 25,000 of wastewater per day to sanitary sewers or are pre-defined by EPA.

Date of Government Version: 08/26/2019 Date Data Arrived at EDR: 08/26/2019 Date Made Active in Reports: 11/05/2019 Number of Days to Update: 71 Source: Department of Environmental Resources Management Telephone: 305-372-6700 Last EDR Contact: 11/22/2019 Next Scheduled EDR Contact: 03/09/2020 Data Release Frequency: Semi-Annually

ENF: Enforcement Case Tracking System Sites

Enforcement cases monitored by the Dade County Department of Environmental Resources Management.

Date of Government Version: 08/26/2019	Source: Department of Environmental Resources Management
Date Data Arrived at EDR: 08/26/2019	Telephone: 305-372-6755
Date Made Active in Reports: 11/05/2019	Last EDR Contact: 11/22/2019
Number of Days to Update: 71	Next Scheduled EDR Contact: 03/09/2020
	Data Release Frequency: Semi-Annually

SPILLS DADE: Fuel Spills Cases

DERM documents fuel spills of sites that are not in a state program.

Date of Government Version: 01/08/2009	Source: Department of Environmental Resources Management
Date Data Arrived at EDR: 01/13/2009	Telephone: 305-372-6755
Date Made Active in Reports: 02/05/2009	Last EDR Contact: 11/22/2019
Number of Days to Update: 23	Next Scheduled EDR Contact: 03/09/2020
	Data Release Frequency: Semi-Annually

UST DADE: Storage Tanks

A listing of aboveground and underground storage tank site locations.

Date of Government Version: 02/26/2019 Date Data Arrived at EDR: 02/26/2019 Date Made Active in Reports: 04/30/2019 Number of Days to Update: 63 Source: Department of Environmental Resource Management Telephone: 305-372-6700 Last EDR Contact: 11/22/2019 Next Scheduled EDR Contact: 03/09/2020 Data Release Frequency: Semi-Annually

## PALM BEACH COUNTY:

LF PALM BEACH: Palm Beach County LF

Palm Beach County Inventory of Solid Waste Sites.

Date of Government Version: 09/01/2011 Date Data Arrived at EDR: 09/20/2011 Date Made Active in Reports: 10/10/2011 Number of Days to Update: 20 Source: Palm Beach County Solid Waste Authority Telephone: 561-640-4000 Last EDR Contact: 12/13/2019 Next Scheduled EDR Contact: 03/23/2020 Data Release Frequency: Varies

## OTHER DATABASE(S)

Depending on the geographic area covered by this report, the data provided in these specialty databases may or may not be complete. For example, the existence of wetlands information data in a specific report does not mean that all wetlands in the area covered by the report are included. Moreover, the absence of any reported wetlands information does not necessarily mean that wetlands do not exist in the area covered by the report.

CT MANIFEST: Hazardous Waste Manifest Data

Facility and manifest data. Manifest is a document that lists and tracks hazardous waste from the generator through transporters to a tsd facility.

Date of Government Version: 05/14/2019Source: Department of Energy & Environmental ProtectionDate Data Arrived at EDR: 05/14/2019Telephone: 860-424-3375Date Made Active in Reports: 08/05/2019Last EDR Contact: 11/11/2019Number of Days to Update: 83Next Scheduled EDR Contact: 02/24/2020Data Release Frequency: No Update Planned

NJ MANIFEST: Manifest Information Hazardous waste manifest information.	
Date of Government Version: 12/31/2018 Date Data Arrived at EDR: 04/10/2019 Date Made Active in Reports: 05/16/2019 Number of Days to Update: 36	Source: Department of Environmental Protection Telephone: N/A Last EDR Contact: 01/06/2020 Next Scheduled EDR Contact: 04/20/2020 Data Release Frequency: Annually
NY MANIFEST: Facility and Manifest Data Manifest is a document that lists and tracks hazardous waste from the generator through transporters to a facility.	
Date of Government Version: 01/01/2019 Date Data Arrived at EDR: 05/01/2019 Date Made Active in Reports: 06/21/2019 Number of Days to Update: 51	Source: Department of Environmental Conservation Telephone: 518-402-8651 Last EDR Contact: 10/29/2019 Next Scheduled EDR Contact: 02/10/2020 Data Release Frequency: Quarterly
PA MANIFEST: Manifest Information Hazardous waste manifest information.	
Date of Government Version: 06/30/2018 Date Data Arrived at EDR: 07/19/2019 Date Made Active in Reports: 09/10/2019 Number of Days to Update: 53	Source: Department of Environmental Protection Telephone: 717-783-8990 Last EDR Contact: 10/09/2019 Next Scheduled EDR Contact: 12/07/2020 Data Release Frequency: Annually
RI MANIFEST: Manifest information Hazardous waste manifest information	
Date of Government Version: 12/31/2018 Date Data Arrived at EDR: 10/02/2019 Date Made Active in Reports: 12/10/2019 Number of Days to Update: 69	Source: Department of Environmental Management Telephone: 401-222-2797 Last EDR Contact: 11/14/2019 Next Scheduled EDR Contact: 03/02/2020 Data Release Frequency: Annually
WI MANIFEST: Manifest Information Hazardous waste manifest information.	
Date of Government Version: 05/31/2018 Date Data Arrived at EDR: 06/19/2019 Date Made Active in Reports: 09/03/2019 Number of Days to Update: 76	Source: Department of Natural Resources Telephone: N/A Last EDR Contact: 12/18/2019 Next Scheduled EDR Contact: 03/23/2020 Data Release Frequency: Annually
	ts, Petrochemicals, Gas Liquids (LPG/NGL), and Specialty dle (Natural Gas, Gas Liquids (LPG/NGL), and Specialty Gases

Gases (Miscellaneous)) N = Natural Gas Bundle (Natural Gas, Gas Liquids (LPG/NGL), and Specialty Gases (Miscellaneous)). This map includes information copyrighted by Endeavor Business Media. This information is provided on a best effort basis and Endeavor Business Media does not guarantee its accuracy nor warrant its fitness for any particular purpose. Such information has been reprinted with the permission of Endeavor Business Media.

## Electric Power Transmission Line Data

Source: Endeavor Business Media

This map includes information copyrighted by Endeavor Business Media. This information is provided on a best effort basis and Endeavor Business Media does not guarantee its accuracy nor warrant its fitness for any particular purpose. Such information has been reprinted with the permission of Endeavor Business Media.

Sensitive Receptors: There are individuals deemed sensitive receptors due to their fragile immune systems and special sensitivity to environmental discharges. These sensitive receptors typically include the elderly, the sick, and children. While the location of all sensitive receptors cannot be determined, EDR indicates those buildings and facilities - schools, daycares, hospitals, medical centers, and nursing homes - where individuals who are sensitive receptors are likely to be located.

AHA Hospitals: Source: American Hospital Association, Inc. Telephone: 312-280-5991 The database includes a listing of hospitals based on the American Hospital Association's annual survey of hospitals. Medical Centers: Provider of Services Listing Source: Centers for Medicare & Medicaid Services Telephone: 410-786-3000 A listing of hospitals with Medicare provider number, produced by Centers of Medicare & Medicaid Services, a federal agency within the U.S. Department of Health and Human Services. Nursing Homes Source: National Institutes of Health Telephone: 301-594-6248 Information on Medicare and Medicaid certified nursing homes in the United States. **Public Schools** Source: National Center for Education Statistics Telephone: 202-502-7300 The National Center for Education Statistics' primary database on elementary and secondary public education in the United States. It is a comprehensive, annual, national statistical database of all public elementary and secondary schools and school districts, which contains data that are comparable across all states. **Private Schools** Source: National Center for Education Statistics Telephone: 202-502-7300 The National Center for Education Statistics' primary database on private school locations in the United States. Daycare Centers: Department of Children & Families Source: Provider Information Telephone: 850-488-4900

Flood Zone Data: This data was obtained from the Federal Emergency Management Agency (FEMA). It depicts 100-year and 500-year flood zones as defined by FEMA. It includes the National Flood Hazard Layer (NFHL) which incorporates Flood Insurance Rate Map (FIRM) data and Q3 data from FEMA in areas not covered by NFHL.

Source: FEMA Telephone: 877-336-2627 Date of Government Version: 2003, 2015

NWI: National Wetlands Inventory. This data, available in select counties across the country, was obtained by EDR in 2002, 2005 and 2010 from the U.S. Fish and Wildlife Service.

State Wetlands Data: Wetlands Inventory Source: Department of Environmental Protection Telephone: 850-245-8238

Current USGS 7.5 Minute Topographic Map Source: U.S. Geological Survey

## STREET AND ADDRESS INFORMATION

© 2015 TomTom North America, Inc. All rights reserved. This material is proprietary and the subject of copyright protection and other intellectual property rights owned by or licensed to Tele Atlas North America, Inc. The use of this material is subject to the terms of a license agreement. You will be held liable for any unauthorized copying or disclosure of this material.

# **GEOCHECK ®- PHYSICAL SETTING SOURCE ADDENDUM**

## TARGET PROPERTY ADDRESS

LITTLE RINGLING BRIDGE SR 789 BIRD KEY DR TO SARASOTA HARBOR WEST SARASOTA, FL 34236

## TARGET PROPERTY COORDINATES

Latitude (North):	27.323764 - 27° 19' 25.55"
Longitude (West):	82.567417 - 82° 34' 2.70"
Universal Tranverse Mercator:	Zone 17
UTM X (Meters):	344922.1
UTM Y (Meters):	3023101.0
Elevation:	4 ft. above sea level

## USGS TOPOGRAPHIC MAP

Target Property Map:	5676072 SARASOTA, FL
Version Date:	2012

EDR's GeoCheck Physical Setting Source Addendum is provided to assist the environmental professional in forming an opinion about the impact of potential contaminant migration.

Assessment of the impact of contaminant migration generally has two principle investigative components:

- 1. Groundwater flow direction, and
- 2. Groundwater flow velocity.

Groundwater flow direction may be impacted by surface topography, hydrology, hydrogeology, characteristics of the soil, and nearby wells. Groundwater flow velocity is generally impacted by the nature of the geologic strata.

## **GROUNDWATER FLOW DIRECTION INFORMATION**

Groundwater flow direction for a particular site is best determined by a qualified environmental professional using site-specific well data. If such data is not reasonably ascertainable, it may be necessary to rely on other sources of information, such as surface topographic information, hydrologic information, hydrogeologic data collected on nearby properties, and regional groundwater flow information (from deep aquifers).


## **TOPOGRAPHIC INFORMATION**

Surface topography may be indicative of the direction of surficial groundwater flow. This information can be used to assist the environmental professional in forming an opinion about the impact of nearby contaminated properties or, should contamination exist on the target property, what downgradient sites might be impacted.

## TARGET PROPERTY TOPOGRAPHY

General Topographic Gradient: Undeterminable

## SURROUNDING TOPOGRAPHY: ELEVATION PROFILES



Source: Topography has been determined from the USGS 7.5' Digital Elevation Model and should be evaluated on a relative (not an absolute) basis. Relative elevation information between sites of close proximity should be field verified.

## HYDROLOGIC INFORMATION

Surface water can act as a hydrologic barrier to groundwater flow. Such hydrologic information can be used to assist the environmental professional in forming an opinion about the impact of nearby contaminated properties or, should contamination exist on the target property, what downgradient sites might be impacted.

Refer to the Physical Setting Source Map following this summary for hydrologic information (major waterways and bodies of water).

### FEMA FLOOD ZONE

Flood Plain Panel at Target Property	FEMA Source Type		
1251500008C	FEMA Q3 Flood data		
Additional Panels in search area:	FEMA Source Type		
1251500009B 1251500012C 1251500013B	FEMA Q3 Flood data FEMA Q3 Flood data FEMA Q3 Flood data		
NATIONAL WETLAND INVENTORY			
NWI Quad at Target Property SARASOTA	NWI Electronic <u>Data Coverage</u> YES - refer to the Overview Map and Detail Map		

### HYDROGEOLOGIC INFORMATION

Hydrogeologic information obtained by installation of wells on a specific site can often be an indicator of groundwater flow direction in the immediate area. Such hydrogeologic information can be used to assist the environmental professional in forming an opinion about the impact of nearby contaminated properties or, should contamination exist on the target property, what downgradient sites might be impacted.

Site-Specific Hydrogeological Data*:		
Search Radius:	1.25 miles	
Status:	Not found	

## **AQUIFLOW®**

Search Radius: 1.000 Mile.

EDR has developed the AQUIFLOW Information System to provide data on the general direction of groundwater flow at specific points. EDR has reviewed reports submitted by environmental professionals to regulatory authorities at select sites and has extracted the date of the report, groundwater flow direction as determined hydrogeologically, and the depth to water table.

	LOCATION	GENERAL DIRECTION
MAP ID	FROM TP	GROUNDWATER FLOW
2	1/2 - 1 Mile West	E
1G	1/2 - 1 Mile West	E

For additional site information, refer to Physical Setting Source Map Findings.

## **GROUNDWATER FLOW VELOCITY INFORMATION**

Groundwater flow velocity information for a particular site is best determined by a qualified environmental professional using site specific geologic and soil strata data. If such data are not reasonably ascertainable, it may be necessary to rely on other sources of information, including geologic age identification, rock stratigraphic unit and soil characteristics data collected on nearby properties and regional soil information. In general, contaminant plumes move more quickly through sandy-gravelly types of soils than silty-clayey types of soils.

## **GEOLOGIC INFORMATION IN GENERAL AREA OF TARGET PROPERTY**

Geologic information can be used by the environmental professional in forming an opinion about the relative speed at which contaminant migration may be occurring.

## **ROCK STRATIGRAPHIC UNIT**

## **GEOLOGIC AGE IDENTIFICATION**

Era:	Cenozoic C	ategory:	Stratified Sequence
System:	Tertiary		
Series:	Miocene		
Code:	Tm (decoded above as Era, System & Series	s)	

Geologic Age and Rock Stratigraphic Unit Source: P.G. Schruben, R.E. Arndt and W.J. Bawiec, Geology of the Conterminous U.S. at 1:2,500,000 Scale - a digital representation of the 1974 P.B. King and H.M. Beikman Map, USGS Digital Data Series DDS - 11 (1994).

## DOMINANT SOIL COMPOSITION IN GENERAL AREA OF TARGET PROPERTY

The U.S. Department of Agriculture's (USDA) Soil Conservation Service (SCS) leads the National Cooperative Soil Survey (NCSS) and is responsible for collecting, storing, maintaining and distributing soil survey information for privately owned lands in the United States. A soil map in a soil survey is a representation of soil patterns in a landscape. Soil maps for STATSGO are compiled by generalizing more detailed (SSURGO) soil survey maps. The following information is based on Soil Conservation Service STATSGO data.

a hydric soil.

Soil Component Name:	WATER		
Soil Surface Texture:	Not reported		
Hydrologic Group:	Not reported		
Soil Drainage Class:	Not reported		
Hydric Status: Soil does not meet the requirements for			
Corrosion Potential - Uncoated Steel:	Not Reported		
Depth to Bedrock Min:	> 0 inches		
Depth to Bedrock Max:	> 0 inches		

No Layer Information available.

## LOCAL / REGIONAL WATER AGENCY RECORDS

EDR Local/Regional Water Agency records provide water well information to assist the environmental professional in assessing sources that may impact ground water flow direction, and in forming an opinion about the impact of contaminant migration on nearby drinking water wells.

## WELL SEARCH DISTANCE INFORMATION

DATABASE	SEARCH DISTANCE (miles)
Federal USGS	0.250
Federal FRDS PWS	Nearest PWS within 1 mile
State Database	0.250

## FEDERAL USGS WELL INFORMATION

		LOCATION
MAP ID	WELL ID	FROM TP
No Wells Found		

## FEDERAL FRDS PUBLIC WATER SUPPLY SYSTEM INFORMATION

		LOCATION
MAP ID	WELL ID	FROM TP
No DWG Guetara Found		

No PWS System Found


Note: PWS System location is not always the same as well location.

## STATE DATABASE WELL INFORMATION

MAP ID	WELL ID
1	FLSW90000000962

LOCATION FROM TP 0 - 1/8 Mile WSW

## **PHYSICAL SETTING SOURCE MAP - 5931196.2s**



## No contour lines were detected within this map area.

ADDRESS:		CONTACT: INQUIRY #: DATE:	5931196.2s January 10, 2020 11:46 am
Copyright © 2020 EDR, Inc. © 2015 TomTom Rel. 2015.			

#### **GEOCHECK®- PHYSICAL SETTING SOURCE MAP FINDINGS**

Map ID Direction Distance Elevation 1 WSW 0 - 1/8 Mile Higher				Database		R ID Number 19000000962
Database: Site ID: Withdrawal: Well Status: Well Use: Monitor Use Water Use: Permitted Ca Permitted Di Permitted St	asing Depth:	Water Well Permit Database (South 617247 7 Plugged Public Supply Not Reported PUBLIC SUPPLY Not Reported 12 Not Reported	west WMD) Revision: Permittee: Water Source: Monitor Type: Approval Status: Permitted Crop Protection Permitted Casing Diamon Permitted Total Depth:	With Not F Appr on: Not F		ta/Attn: Tom Barwin Groundwater
2 West 1/2 - 1 Mile Lower	Site ID: Groundwater Flow: Water Table Depth Date:			AQUIFLOW	3751	
1G West 1/2 - 1 Mile Lower	Site ID: Groundwater Flow: Water Table Depth Date:			AQUIFLOW	3751	

#### GEOCHECK® - PHYSICAL SETTING SOURCE MAP FINDINGS RADON

#### AREA RADON INFORMATION

State Database: FL Radon

Radon Test Results

Zip 	Total Buildings	% of sites>4pCi/L	Data Source
34236	49	10.2	Certified Residential Database
34236	38	0.0	Mandatory Non-Residential Database
34236	1	0.0	Mandatory Residential Database

Federal EPA Radon Zone for SARASOTA County: 3

Note: Zone 1 indoor average level > 4 pCi/L.

: Zone 2 indoor average level >= 2 pCi/L and <= 4 pCi/L. : Zone 3 indoor average level < 2 pCi/L.

Federal Area Radon Information for SARASOTA COUNTY, FL

#### Number of sites tested: 150

Area	Average Activity	% <4 pCi/L	% 4-20 pCi/L	% >20 pCi/L
Living Area	1.010 pCi/L	96%	4%	0%
Basement	Not Reported	Not Reported	Not Reported	Not Reported

#### **TOPOGRAPHIC INFORMATION**

USGS 7.5' Digital Elevation Model (DEM)

Source: United States Geologic Survey

EDR acquired the USGS 7.5' Digital Elevation Model in 2002 and updated it in 2006. The 7.5 minute DEM corresponds to the USGS 1:24,000- and 1:25,000-scale topographic quadrangle maps. The DEM provides elevation data with consistent elevation units and projection.

Current USGS 7.5 Minute Topographic Map Source: U.S. Geological Survey

#### HYDROLOGIC INFORMATION

Flood Zone Data: This data was obtained from the Federal Emergency Management Agency (FEMA). It depicts 100-year and 500-year flood zones as defined by FEMA. It includes the National Flood Hazard Layer (NFHL) which incorporates Flood Insurance Rate Map (FIRM) data and Q3 data from FEMA in areas not covered by NFHL.

Source: FEMA Telephone: 877-336-2627 Date of Government Version: 2003, 2015

NWI: National Wetlands Inventory. This data, available in select counties across the country, was obtained by EDR in 2002, 2005 and 2010 from the U.S. Fish and Wildlife Service.

State Wetlands Data: Wetlands Inventory

Source: Department of Environmental Protection Telephone: 850-245-8238

#### HYDROGEOLOGIC INFORMATION

AQUIFLOW<sup>R</sup> Information System

Source: EDR proprietary database of groundwater flow information

EDR has developed the AQUIFLOW Information System (AIS) to provide data on the general direction of groundwater flow at specific points. EDR has reviewed reports submitted to regulatory authorities at select sites and has extracted the date of the report, hydrogeologically determined groundwater flow direction and depth to water table information.

#### **GEOLOGIC INFORMATION**

#### Geologic Age and Rock Stratigraphic Unit

Source: P.G. Schruben, R.E. Arndt and W.J. Bawiec, Geology of the Conterminous U.S. at 1:2,500,000 Scale - A digital representation of the 1974 P.B. King and H.M. Beikman Map, USGS Digital Data Series DDS - 11 (1994).

#### STATSGO: State Soil Geographic Database

Source: Department of Agriculture, Natural Resources Conservation Service (NRCS) The U.S. Department of Agriculture's (USDA) Natural Resources Conservation Service (NRCS) leads the national Conservation Soil Survey (NCSS) and is responsible for collecting, storing, maintaining and distributing soil survey information for privately owned lands in the United States. A soil map in a soil survey is a representation of soil patterns in a landscape. Soil maps for STATSGO are compiled by generalizing more detailed (SSURGO) soil survey maps.

SSURGO: Soil Survey Geographic Database

Source: Department of Agriculture, Natural Resources Conservation Service (NRCS) Telephone: 800-672-5559

SSURGO is the most detailed level of mapping done by the Natural Resources Conservation Service, mapping scales generally range from 1:12,000 to 1:63,360. Field mapping methods using national standards are used to construct the soil maps in the Soil Survey Geographic (SSURGO) database. SSURGO digitizing duplicates the original soil survey maps. This level of mapping is designed for use by landowners, townships and county natural resource planning and management.

#### PHYSICAL SETTING SOURCE RECORDS SEARCHED

#### LOCAL / REGIONAL WATER AGENCY RECORDS

FEDERAL WATER WELLS

PWS: Public Water Systems

Source: EPA/Office of Drinking Water

Telephone: 202-564-3750

Public Water System data from the Federal Reporting Data System. A PWS is any water system which provides water to at least 25 people for at least 60 days annually. PWSs provide water from wells, rivers and other sources.

PWS ENF: Public Water Systems Violation and Enforcement Data

Source: EPA/Office of Drinking Water

Telephone: 202-564-3750

Violation and Enforcement data for Public Water Systems from the Safe Drinking Water Information System (SDWIS) after August 1995. Prior to August 1995, the data came from the Federal Reporting Data System (FRDS).

USGS Water Wells: USGS National Water Inventory System (NWIS) This database contains descriptive information on sites where the USGS collects or has collected data on surface water and/or groundwater. The groundwater data includes information on wells, springs, and other sources of groundwater.

STATE RECORDS

Well Construction Permitting Database Source: Northwest Florida Water Management District Telephone: 850-539-5999

Consumptive Use Permit Well Database Source: St. Johns River Water Management District Telephone: 386-329-4841

DEP GWIS - Generalized Water Information System Well Data Source: Department of Environmental Protection Telephone: 850-245-8507 Data collected for the Watershed Monitoring Section of the Department of Environmental Protection.

DOH and DEP Historic Study of Private Wells Source: Department of Environmental Protection Telephone: 850-559-0901 Historic database for private supply wells.

Permitted Well Location Database Source: South Florida Water Management District Telephone: 561-682-6877

Super Act Program Well Data

Source: Department of Health Telephone: 850-245-4250

This table consists of data relating to all privately and publicly owned potable wells investigated as part of the SUPER Act program. The Florida Department of Health's SUPER Act Program (per Chapter 376.3071(4)(g), Florida Statutes), was given authority to provide field and laboratory services, toxicological risk assessments, investigations of drinking water contamination complaints and education of the public.

Water Well Location Information Source: Suwannee River Water Management District Telephone: 386-796-7211

Water Well Permit Database Source: Southwest Water Management District Telephone: 352-796-7211

#### PHYSICAL SETTING SOURCE RECORDS SEARCHED

#### OTHER STATE DATABASE INFORMATION

Oil and Gas Permit Database Source: Department of Environmental Protection Telephone: 850-245-3194 Locations of all permitted wells in the state of Florida. Florida Sinkholes

Source: Department of Environmental Protection, Geological Survey Telephone: The sinkhole data was gathered by the Florida Sinkhole Research Institute, University of Florida.

#### RADON

State Database: FL Radon Source: Department of Health Telephone: 850-245-4288 Zip Code Based Radon Data

Area Radon Information

Source: USGS Telephone: 703-356-4020 The National Radon Database has been developed by the U.S. Environmental Protection Agency (USEPA) and is a compilation of the EPA/State Residential Radon Survey and the National Residential Radon Survey. The study covers the years 1986 - 1992. Where percessary data has been supplemented by information collected at

The study covers the years 1986 - 1992. Where necessary data has been supplemented by information collected at private sources such as universities and research institutions.

EPA Radon Zones Source: EPA Telephone: 703-356-4020 Sections 307 & 309 of IRAA directed EPA to list and identify areas of U.S. with the potential for elevated indoor radon levels.

#### OTHER

Airport Landing Facilities: Private and public use landing facilities Source: Federal Aviation Administration, 800-457-6656

Epicenters: World earthquake epicenters, Richter 5 or greater Source: Department of Commerce, National Oceanic and Atmospheric Administration

Earthquake Fault Lines: The fault lines displayed on EDR's Topographic map are digitized quaternary faultlines, prepared in 1975 by the United State Geological Survey

#### STREET AND ADDRESS INFORMATION

© 2015 TomTom North America, Inc. All rights reserved. This material is proprietary and the subject of copyright protection and other intellectual property rights owned by or licensed to Tele Atlas North America, Inc. The use of this material is subject to the terms of a license agreement. You will be held liable for any unauthorized copying or disclosure of this material.

# CSER APPENDIX B


ETDM Number: 14384 Ringling / SR 789

Efficient Transportation Decision Making	g Tool dress or place	and state and st	Close interactive Map
Enter a project number to view all analysis areas for that project. To view just a specific analysis area, enter as project-analysis area ID, e.g. "1234-1".		Manuel	Contraction of the second

# ETDM Number: 14384 Ringling / SR 789

Environmental Screening To Map Viewer	Close Interactive Map
Mag Viewer Cader Apy Viewer e Data yers yers cader Apy fr Pr Fr Fr Fr Fr Fr Fr Fr Fr Fr Fr Fr Fr Fr Fr Fr F	
e Data e Data yers See A Fk Pr Fk Pr Fk Pr Fk Etd Fk Etd Fk Etd Fk Etd Fk Etd Fk Etd Fk Etd Fk Etd Fk Etd Fk Ft Fk Ft	Basemap
e Data yers yers A F F F F F F F F F F F F F F F F F F F	
e Data yers yers R Fk Etd Fk Etd Fk Etd Fk Etd Fk Etd f Revis Fk Etd Fk Etd Fk Etd Fk Etd Fk Etd Fk Etd Fk Etd Fk Ft Fk Ft Fk Ft Fk Ft Fk Ft Fk Ft Fk Ft Fk Ft Fk Ft Fk Ft Fk Fk Ft Fk Ft Fk Fk	Batt
yers yers See A R Fk Etd Fk Etd Fk Etd Fk Etd Fk Etd Fk Etd Fk Etd Fk Etd Seg Seg	
Vers se a ojects	R.V.e
ojects	
ojects	
ojects	
ojects +	
ojects +	
ojects +	
Fk Mil	Contract of the second s
+	Bay P
	Harbor Q.
Street Name SR 789 (Ringling)	
conter a project number to view all analysis areas for that project To view instruction and the provident of the provident To view instruction of the provident To view instruction of the provident of the provid	
project: no view just a specific analysis area, enter as	
Length 0.741	4
Current Status ETAT Review Complete	
A Tavers Alternative 1	A A A A A A A A A A A A A A A A A A A





64182742	iculus database	801	On-going groundwater monitoring program	819	
6418	rough O	9700801	gram	8520819	2
2 Marina Plaza	No documents available through Oculus database	481 John Ringling Blvd	Petroleum Restoration Program	Exxon – St. Armands 1 N Blvd of Presidents	Site Assessment: Feb 2012
Jack Graham, Inc.		Foxy Lady		Exxon – St. Armand	
Sarasota		St. Armands:			

Low Scored Site Initiative (LSSI)

Map Direct Search Results Tue Sep 08 2020 11:28:53 GMT-0400 (Eastern Daylight Time)

#### Search Made:

Search Box 251 feet wide at 27.31928986 x -82.57608306 27°19'9.4435" x -82°34'33.8990"

#### Search Results: 1

 DEP Cleanup Sites
 STCM source database name
 FOXY LADY business name
 64189895


CEP CLEANUP SITE KEY



https://prodenv.dep.state.fl.us/DepNexus/public/electronic-documents/9700801/facility!search



481 JOHN RINGLING BLVD SARASOTA, FL 34236-Address



(SD) South Regulatory District



.

CLCC CLEANUP CATEGORY KEY

DPHO CMC2 COORDINATE METHOD ID

TK CPAC PROGRAM AREA ID

1999 doqs MAP SOURCE

FACIL OIC OBJECT OF INTEREST ID

**O** APPRX PC2 PROXIMITY ID

**O**ACTIVE rsc2 remediation status key

FL STCD1 STATE ID

DPHO Verified coordinate method id



0

09/08/2020 DATA LOAD DATE

05/03/2005 collect date

9/8/202	0	
Ĩ	05/03/2005 VERIFICATION DATE	
2	ROSELLI_J collect username	
2	DEPARTMENT OF ENVIRONMENTAL PR	
2	ROSELLI_J verifier username	
2	DEPARTMENT OF ENVIRONMENTAL PR	
	4 CALC COORD ACCURACY LEVEL ID	
	923 MAP SOURCE SCALE	
	Latitude: 27° 19' 9.76"	
	Longitude: 82° 34' 33.89" Datum: HARN	

Disclaimer: This report is only intended to be used as an approximation of the possibility of nearby regulated features. It is not intended for legal purposes. Neither the State of Florida, nor the FDEP, makes any warranty, expressed or implied, including the warranties of merchantability and fitness for a particular purpose arising out of the use or inability to use the data, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Use of information contained on the FDEP web pages constitutes understanding and acceptance of our disclaimer.

#### Mendez, Steven

Mendez, Steven
Wednesday, August 5, 2020 12:09 PM
stevev@gearengineer.com
Correia, Matthew; Porto, Janice; Team 5 PRP Deliverable; Witt, Graham; Davis, J. Lance
Foxy Lady (58/9700801) Task-3 Deliverable Review Letter

August 5, 2020

(Sent via email only to addressee at stevev@gearengineer.com)

Mr. Steve Volpe, P.G. AGuA, LLC 1928 Boothe Circle Longwood, FL 32750

Subject: <u>Task-3 Deliverable (Template Site Assessment Report) Review Letter</u> Foxy Lady 481 John Ringling Blvd Sarasota, Sarasota County FDEP Facility ID# 58/9700801 Discharge Date: June 17, 1997 (PCPP) Priority Score: 07 Purchase Order, Task #: B57442, Task 3 Task Assignment: GC861-073A

Dear Mr. Volpe:

The Petroleum Restoration Program (PRP) has reviewed the Task-3 Deliverable (Template Site Assessment Report) dated May 22, 2020 (received June 03, 2020) and Response to Comments dated July 24, 2020 (received July 24, 2020), submitted for this facility. The field work is acceptable, but the deliverable is incomplete. The following items need to be addressed before the work outlined in Purchase Order #B57442 for Task 3 is completed:

- 1. Please report MTBE, EDC, and EDB for MW-7 on Table 3 and on Table 5 for MW-7-2 (soil).
- 2. Please create a table and document the groundwater results of the 19 Pesticide analytes reported in the laboratory analytical report for MW-7 and MW-7-2 (soil).
- 3. Please create a table and document the groundwater results of the 7 PCB analytes reported in the laboratory analytical report for MW-7 and MW-7-2 (soil).
- 4. Please create a table and report the soil and groundwater results for Priority Pollutant Volatile Organic Halocarbons per Table B of 62-780 for Petroleum Product COC and Dry Cleaning Solvent COC:
- 5. Additional Non-Priority Pollutant Organics that should be reported for groundwater only are as follows:
  - a. Isopropyl Benzene (Cumene)
  - b. 1,2,4-Trimethylbenzene

- c. 1,3,5-Trimethylbenzene
- 6. Please resubmit the updated tables in excel file.

Please submit the revised TSAR addressing the comments by September 8, 2020. If you should have any questions about the review, please contact me at (813) 684-4400, extension 4820 or at the address in the signature of this email.

#### Thank you,

#### **Steven Mendez**

Associate Geologist FDEP Petroleum Restoration Program, Team Five



eFax: 1 813 435 2085 24 Hour Emergency Response: 800.283.2933 www.NorthStar.com | SMendez@NorthStar.com

Industrial & Commercial Demolition | Environmental Remediation | Emergency Response | Asset Recovery | Nuclear Decommissioning

Confidentiality Note: This e-mail, and any attachment to it, contains privileged and confidential information intended only for the use of the individual(s) or entity named on the e-mail. If the reader of this e-mail is not the intended recipient, or the employee or agent responsible for delivering it to the intended recipient, you are hereby notified that reading it is strictly prohibited. If you have received this e-mail in error, please immediately return it to the sender and delete it from your system. Thank you.

Florida Depariment of Environmental J	OER FUR # 17.94(4239
Florida Department of Environmental 1	DER F.W. 0 17.7818339
Willing Will Twin Turen Office and a second of Environmental 1	
Strand A	Regulation From the Obstander Apporting Form
Road Road And Road An	1011ds 3235-2400 (14 200 citien Ho
Discharge Reporting	Form
Use this form to notify the Department of Environmental Regulation of	
Possilla of task News	of receipt of test test ut.
<ol> <li>Petroleum discharges exceeding 25 gallons on pervicus surfaces as described in Section</li> <li>Hazardous substance (CERC) A constant. June</li> </ol>	of receipt of test posult.
<ol> <li>Hazardous substance (CERCLA regulated), discharges exceeding applicable reportations working day of the discovery.</li> </ol>	on 17-761.460 F.A.C Anin Abin Tking dax Diacovery.
4. Within one working day of discovery of suspected releases confirmed by: (a) release the surrounding area, (b) unusual and unexplained storage system operating condition or from a tank closure assessment that indicate a release may have occurred, or (d) or less, exceeding ten gallons per weekly test or five gallons averaged over four or	sed regulated substances or pollutants discovered in
Mail to the DER District Office in your area listed on the re	averee side of this form
PLEASE DONIT OF WIGH	HONE AND DEDING TOTAL
5819100301 Complete all applicable blanks	
DER Facility ID Number: Pending 2. Tank Number: Unkn	nown 3. Delo: 6/26/97
Fecility Name: Former Chevron (Foxy Lady Site)	3. Dalo:
Fachily Owner or Operator MS. Lorry Eible	
Facility Address: _ 481 John Ringling Boulevard, Saraso	ota, Florida 34236
Telephona Number: (941) 349-3871 County: Sarasota	The second secon
Mailing Address: _ 853 Slesta Key Circle, Sarasota, F1	
	orida 34242
Date of receipt of test results or discovery: 6/17/97	monlh/day/year
C. Tightness test (underground tasks ost a	Vapor or visible signs of a discharge in the visinity. Closure: (explain)
Estimated number of gallons discharged: Unknown	) Other: <u>Environmental Site Ass</u> essmi Lab Results
that dad id storates has been been been been been been been bee	Q
ype of regulated substance discharged, (circle all that apply) A Dispenser B	Pipe C. Filling D. Tank O Unknown
(D) vehicular diasal	20 F 00
Dunleaded gasoline F. aviation gas 1.1 diesei chlorine i	and derivatives (write in name or Chemical Abstract
. gasonol G. jet fuel O newfuele oil Service (	CAS number)
ause of leak. (circle all that apply)	inte in name)
UNZAGINA C. Loose connection E. Puggiusa O. Ball	<u></u>
Split D. Corrosion F Installation (siture H Ovortill	
be of financial responsibility. (ourcle one) Third party insurance provided by the state insurance contractor O Noi applies Self-insurance pursuant to Chapter 17 700 500 5110	ene line
	1. Mar
the best of my knowledge and bellet all information submitted on this form y	True, accurate, and complete.
LOYNG FIELD	Casto
nted Namo of Owner, Operator or Authorized Representative Signature of On	wher Operator or Authorized Representative

TR	UMAN
----	------

· ·									TR	UMAN
A CONSTRUCTION OF CONSTRUCT OF CONSTRUCTO OF CONSTRUCT OF C		Twin Tow				ntal Protect nassee, Florida 32396		Effective Date	7-761.900(2) age Tank Registr December 10, 19 h No f	00
A. C.	JUL 8	nciale S	torage	Tank	Regis	stration	For	m 97 JUL		
£	Annes	Pleas	e Print or T	ype - Revie	w Instructi	ons Before Co	mpleti	ng Form d	CF SYSTE	1. UN INS SMENT
. DER	Facility ID Num	ber:	970	680	)/	2.	Facility	Type:	GENTER	
	Registration	/	New Owner D	Promote la		cility Revision	-	Tank Revisi	on 🗆	
. Coun	ty and Code of	tank(s) loc	ation: <u>SA</u>	RASOT	A		-	_1_5	8	
5. Facili	y Name:F	DXYL	ADY (FO	RMER (	CHEVEO	(4)				
						BOULEVAI	22			
City/S	tate/Zip:	SARI	ASOTA	FL -	34236					
	te Manager/Co	176 A.S. Cont				On Site Tel	ephone	<u> </u>		
	cial Responsibi					Account Ov				
	owner Signatur n (optional) Latiti Con	ude: 29	• <u>19</u> • <u>09</u> •• Line For I	" Longi Each Tank	At This Fac	3 <u>4 ' 34</u> " cility (Use Cod - 19 for tanks out	les - Se			/
9	10	11	12	13	14	15	16	17	18	19
1	1000	D	X/X	U	C	B	x	B		618
2	2000	A	×/x	U	С	В	×	В		618
3	2.000	B	×/x	U	C	B	×	В		6/80
4	550	_ <u> </u>	×/× ×/×	0	C	R	x	B		6/80
						DPR#		J		
	w tank installa		c removal			Depart	ment of	Professional Re	gulation Lice	nse Numbe
	5 <u>CHCT2A</u> & title of owner				- Mulue	n is true, accurat Cherner nature	e and c		7-1-97 Dai	2

Northwest District 160 Governmental Center Pensacola, Florida 32501-5794 904-463-8300

Northeast District 7825 Baymeedows Way, Suite B200 Jacksonville, Florida 32256-7577 904-448-4300 Central District 3319 Maguire Btvd, Suite 232 Ortando, Florida 32803-3767 407-894-7555

1

Southwest District 3804 Coconut Palm Dr. Tampa, Florida 33619 813-744-6100

South District 2295 Victoria Ave., Suite 364 Fort Myers, Florida 33901 813-332-6975

Southeast District 1900 S. Congress Ave. Suite A, West Paim Beach, Florida 3341( 407-433-2650

2 - FACILITY TYPE		新たいたというでありいたとのかがあるのが必要がながないないないないないである。			
<ol> <li>Retail station</li> </ol>					4
E. Residence		Stelle government Loss: government	N		
Fuel user/non-retail		County government	т	A DESCRIPTION OF A DESC	ulk petroleum or chemical storage
<ul> <li>Inland bulk petroleum storage</li> <li>Industrial plant</li> </ul>		L. Collection station	V	. Marine fu	eling facility
E. Industrial plan! F. Federal government		<ul> <li>iniand bulk chemical storage</li> <li>Chemical user</li> </ul>	Z.	Other; ple	base specify
<b>9</b>	-			**********	
#6 - FINANCIAL RESPONSIBILITY					19 - TANK ID NUMBER
A, Si B Si	ate Pro	ogram Third party liability/State contractor (FPLIPA/	AIG).		(number sequentially, 1,2,3; or provide
ВЗ	alt Pro	cher leaderal financial responsibility me	carner;		specific identifying name or number;
C. C	iner co	veraço meeting tecaral financial responsibility requirem	ients.		6 characters, maximum)
D. No	DNE			#1	0 - TANK SIZE IN GALLONS
11 - CONTENT	JEPAN	crins, uligen skrifter te kreken beren berne skrifter fra s	**************	**********	*************
A. Leaded gasoline		Fuel - generator or pump		R.	Ammonia compound
B. Unleaded gasoline				S.	(1) ( ) (1) (1) (1) (1) (1) (1) (1) (1)
C. Gasohol D. Vehicular diesel		L. Waste oil L. Fuel oil: on-site neat use only: all USTs or AS	a second and	τ.	Hazardous substance (CERCLA)
E. Aviation gasoline		<ul> <li>Fuel oil: on-site neat use only; all USTs or AS</li> <li>Fuel oil: distribution, or on-site heat use ASTs</li> </ul>	STs <30K gals	U. V.	Mineral acid Grades 5 & 6, bunker 'C' residual oils
F. Jet fuel		C. New & lube oil	s > our gas	w.	
G. Fuel - emergency generator		C. Posticide		х.	Other, miscellaneous petroleum-base product
12 · INSTALLATION		rt: - TANK PLACEMENT A = Abc		Color Constant	*******
DATE (mm/yy)		U = Und	oveground tank derground tank	D =	Aboveground Compression Vessel Underground Compression Vessel
14 - TANK CONSTRUCTION - cho	ose on	e primery conciruction and all other codes that app	oly; primary is inne	r tank constru	uction for double wall tanks
Primary Construction:	С,	Sieci			
	D. E.	Unknown Fiberglass	X.	0.0000000	
	F.	Froergiess-clao sieel	Y. Z.		ne Rapproved tank material
				Offici DEI	approved tank material
Overfil/Split:		Ball check valve	м.		inment bucket
	N. C.	Flow shut-off Tight fir	P.		es, high-level alarms
			ο.	Other DEP	approved protection method
Corrosion Protection:	G.	Calheoic protection - sacrificial anode	н.	Cathodic p	rotection - impressed current
Secondary Containment:		Double wall construction: single material; outer tank	material same as in	ner tank mate	rial
	R. J.	Double wall construction: dual material; outer tank c	constructed of concre	ete, approved	synthetic material or tank "jacket"
	K.	Synthetic liner in tank excavation Concrete, synthetic material, and/or offsite days ben	asth AST and in con	tainmont	
	5.	Other DER approved secondary containment system		namment area	21
	-				
Miscellaneous attributes:	E. L,	Internal lining Compartmented	υ.	Field erecte	ed tank
		***************************************			***************************************
15 - PIPING CONSTRUCTION - CHO	B.	ne primary construction and all other codes that app Siee! or galvanized metal	ply; primary is inne Y.	Unknown	uction for double wall piping
Primary Construction:	C.	Fiberglass	Z.		approved piping material
Primary Construction:	K.	Approved synthetic material		Contraction of the second	
Primary Construction:	IX.	External protective coating			
Primary Construction:					
Primary Construction: Corrosion Protection:	D.		toomun hose		
Primary Construction:		Callodically protected with sacrificial anode or impre-	ssed current		
Primary Construction:	D. E. F.	Calinodically protected with sacrificial anode or impre- Double wall construction: single material; outer pipe in	material same as inv		
Primary Construction: Corrosion Protection:	D. E. F.	Calinodically protected with sacrificial anode or impre- Double wall construction: single material; outer pipe of Double wall construction: dual material; outer pipe oc	material same as in onstructed of approv	ed synthetic m	
Primary Construction: Corrosion Protection:	D. E. F.	Called cally protected with sacrificial anode or impre- Double wall construction: single material; outer pipe in	material same as in onstructed of approv	ed synthetic m	
Primary Construction: Corrosion Protection:	D. E. F.	Calinodically protected with sacrificial anode or impre- Double wall construction: single material; outer pipe of Double wall construction: dual material; outer pipe oc	material same as in onstructed of approv	ed synthetic m	naterial or pipe "jacket"
Primary Construction: Corrosion Protection: Secondary Containment:	D. E. F. G. I.	Cathoo cally protected with sacrificial anode or impre- Double wall construction: single material; outer pipe of Double wall construction: dual material; outer pipe or Synthetic liner or box/trench liner in piping excavation Aboveground, no contact with soil Suction piping system	material same as inu onstructed of approv n or pipe containmen K. L.	ed synthetic m It area Dispenser li Bulk produc	naterial or pipe "jacket" ners 1 system
Primary Construction: Corrosion Protection: Secondary Containment:	D. E. F. K. G.	Cathod cally protected with sacrificial anode or impret Double wall construction: single material; outer pipe of Double wall construction: dual material; outer pipe of Synthetic liner or box/trench liner in piping excavation Aboveground, no contact with soil Suction piping system Pressurized piping system	material same as inn onstructed of approv n or pipe containmen K. L. H.	ed synthetic m I area Dispenser li Bulk produc Airport/seap	naterial or pipe "jacket" ners 1 system wrt hydrant system
Primary Construction: Corrosion Protection: Secondary Containment: Miscellaneous attributes:	D. E. F. K. G. I. J.	Calhod cally protected with sacrificial anode or impre- Double wall construction: single material; outer pipe of Double wall construction: dual material; outer pipe of Synthetic finer or box/trench liner in piping excavation Aboveground, no contact with soil Suction piping system Pressurized piping system	material same as inu onstructed of approv n or pipe containmen K. L.	ed synthetic m I area Dispenser li Bulk produc Airport/seap	naterial or pipe "jacket" ners 1 system
Primary Construction: Corrosion Protection: Secondary Containment: Miscellaneous attributes:	D. E. F. K. G. I. J.	Calhod cally protected with sacrificial anode or impre- Double wall construction: single material; outer pipe of Double wall construction: dual material; outer pipe of Synthetic finer or box/trench liner in piping excavation Aboveground, no contact with soil Suction piping system Pressurized piping system	material same as inn onstructed of approv n or pipe containmen K. L. H.	ed synthetic m I area Dispenser li Bulk produc Airport/seap	naterial or pipe "jacket" ners 1 system xort hydrant system
Primary Construction: Corrosion Protection: Secondary Containment: Miscellaneous attributes: 6 - LEAK DETECTION METHODS -	D. E. F. G. I. J. choos A. C.	Calhod cally protected with sacrificial anode or impres Double wall construction: single material; outer pipe of Double wall construction: dual material; outer pipe of Synthetic liner or box/trench liner in piping excavation Aboveground, no contact with soil Suction piping system Pressurized piping system e all that apply Automatically sampled wells Groundwater monitoring plan	material same as inc onstructed of approv n or pipe containmen K. L. H. B. D.	ed synthetic m It area Dispenser li Bulk produc Airport/seap Manually sa SPCC Plan	naterial or pipe "jacket" ners 1 system xort hydrant system mpled wells
Primary Construction: Corrosion Protection: Secondary Containment: Miscellaneous attributes: 6 - LEAK DETECTION METHODS -	D, E, F, G, I, J, choos A, C, N,	Calhod cally protected with sacrificial anode or impres Double wall construction: single material; outer pipe of Double wall construction: dual material; outer pipe of Synthetic liner or box/trench liner in piping excavation Aboveground, no contact with soil Suction piping system Pressurized piping system e all that apply Automatically sampled wells Groundwater monitoning plan Groundwater monitoning system	material same as inn onstructed of approv n or pipe containmen K. L. H. B. D. O.	ed synthetic rr t area Dispenser li Bulk produc Airport/seap Manually sa SPCC Plan Vapor monit	naterial or pipe "jacket" ners 1 system port hydrant system mpled wells poring system
Primary Construction: Corrosion Protection: Secondary Containment: Miscellaneous attributes: 6 - LEAK DETECTION METHODS -	D, E, K, G, I, J, choos A, C, N, I,	Calhod cally protected with sacrificial anode or impres Double wall construction: single material; outer pipe of Double wall construction: dual material; outer pipe of Synthetic liner or box/trench liner in piping excavation Aboveground, no contact with soil Suction piping system Pressurized piping system are all that apply Automatically sampled wells Groundwater monitoring plan Groundwater monitoring system Not required - see rule for exemptions	material same as in onstructed of approv n or pipe containmen K. L. H. B. D. O. X.	ed synthelic rr I area Dispenser li Bulk produc Airport/seap Manually sa SPCC Plan Vapor monit None	naterial or pipe "jacket" ners 1 system wort hydrant system mpled wells loring system
Primary Construction: Corrosion Protection: Secondary Containment: Miscellaneous attributes: 6 - LEAK DETECTION METHODS -	D, E, F, G, I, J, choos A, C, N,	Calhod cally protected with sacrificial anode or impres Double wall construction: single material; outer pipe of Double wall construction: dual material; outer pipe of Synthetic liner or box/trench liner in piping excavation Aboveground, no contact with soil Suction piping system Pressurized piping system e all that apply Automatically sampled wells Groundwater monitoning plan Groundwater monitoning system	material same as inn onstructed of approv n or pipe containmen K. L. H. B. D. O.	ed synthelic rr I area Dispenser li Bulk produc Airport/seap Manually sa SPCC Plan Vapor monit None	naterial or pipe "jacket" ners 1 system port hydrant system mpled wells poring system
Primary Construction: Corrosion Protection: Secondary Containment: Miscellaneous attributes: 6 - LEAK DETECTION METHODS -	D, E, K, G, I, J, choos A, C, N, I,	Calhod cally protected with sacrificial anode or impres Double wall construction: single material; outer pipe of Double wall construction: dual material; outer pipe of Synthetic liner or box/trench liner in piping excavation Aboveground, no contact with soil Suction piping system Pressurized piping system are all that apply Automatically sampled wells Groundwater monitoring plan Groundwater monitoring system Not required - see rule for exemptions	material same as in onstructed of approv n or pipe containmen K. L. H. B. D. O. X.	ed synthelic m I area Dispenser li Bulk produc Airport/seap Manually sa SPCC Plan Vapor monit None Other DER a Automatic ta	naterial or pipe "jacket" ners 1 system xort hydrant system impled wells toring system approved monitoring method unk gauging
Primary Construction: Corrosion Protection: Secondary Containment: Miscellaneous attributes: 6 - LEAK DETECTION METHODS - Site/general:	D. E. F. G. J. choos A. C. N. I. Y.	Callodically protected with sacrificial anode or impres Double wall construction: single material; outer pipe of Double wall construction: dual material; outer pipe of Synthetic liner or box/trench liner in piping excavation Aboveground, no contact with soil Suction piping system Pressurized piping system at that apply Automatically sampled wells Groundwater monitorng plan Groundwater monitorng system Not required - see rule for exemptions Unknown	material same as in onstructed of approv n or pipe containmen K. L. H. H. B. D. O. X. Z.	ed synthelic rr I area Dispenser li Bulk produc Airport/seap Manually sa SPCC Plan Vapor monit None Other DER i	naterial or pipe "jacket" ners 1 system xort hydrant system impled wells toring system approved monitoring method unk gauging
Primary Construction: Corrosion Protection: Secondary Containment: Miscellaneous attributes: 6 - LEAK DETECTION METHODS - Site/general: Tank monitoring:	D. E. F. M. G. J. chooss A. C. N. I. Y. E. F.	Calhod cally protected with sacrificial anode or impres Double wall construction: single material; outer pipe of Double wall construction: dual material; outer pipe of Synthetic liner or box/trench liner in piping excavation Aboveground, no contact with soil Suction piping system Pressurized piping system Pressurized piping system attrantically sampled wells Groundwater monitoring plan Groundwater monitoring system No: required - see rule for exemptions Unknown Interstitial space - tank/liner Interstitial space - double wall tank	material same as in onstructed of approv n or pipe containmen K. L. H. B. D. O. X. Z. L. M.	ed synthelic rr I area Dispenser li Bulk produc Airport/seap SPCC Plan Vapor monit None Other DER i Automatic ta Manual tank	naterial or pipe "jacket" ners 1 system port hydrant system mpled wells toring system approved monitoring method unk gauging : gauging
Primary Construction: Corrosion Protection: Secondary Containment: Miscellaneous attributes: 6 - LEAK DETECTION METHODS - Site/general:	D. E. F. M. G. J. chooss A. C. N. I. Y. E. F.	Calnos cally protected with sacrificial anode or impres Double wall construction: single material; outer pipe of Double wall construction: dual material; outer pipe of Synthetic finer or box/trench liner in piping excavation Aboveground, no contact with soil Suction piping system Pressurized piping system Pressurized piping system Se all that apply Automatically sampled wells Groundwater monitonng plan Groundwater monitonng system No: required - see rule for exemptions Unknown Interstitial space - tank/liner Interstitial space - double wall tank In-line detector, auto shut off	material same as inv onstructed of approv n or pipe containmen K. L. H. B. D. O. X. Z. L.	ed synthelic m I area Dispenser li Bulk produc Airport/seap SPCC Plan Vapor monit None Other DER a Automatic ta Manual tank Interstitial sp	naterial or pipe "jacket" ners 1 system xort hydrant system impled wells toring system approved monitoring method unk gauging
Primary Construction: Corrosion Protection: Secondary Containment: Miscellaneous attributes: 6 - LEAK DETECTION METHODS - Site/general: Tank monitoring:	D. E. F. M. G. J. c. No I. Y. E. F. G.	Calhod cally protected with sacrificial anode or impres Double wall construction: single material; outer pipe of Double wall construction: dual material; outer pipe of Synthetic liner or box/trench liner in piping excavation Aboveground, no contact with soil Suction piping system Pressurized piping system Pressurized piping system attrantically sampled wells Groundwater monitoring plan Groundwater monitoring system No: required - see rule for exemptions Unknown Interstitial space - tank/liner Interstitial space - double wall tank	material same as in onstructed of approv n or pipe containmen K. L. H. B. D. O. X. Z. L. M. J.	ed synthelic m I area Dispenser li Bulk produc Airport/seap SPCC Plan Vapor monit None Other DER a Automatic ta Manual tank Interstitial sp	naterial or pipe "jacket" ners 1 system wort hydrant system mpled wells loring system approved monitoring method unk gauging ; gauging bace - piping/liner
Primary Construction: Corrosion Protection: Secondary Containment: Miscellaneous attributes: 6 - LEAK DETECTION METHODS - Site/general: Tank monitoring: Piping monitoring: 7 - TANK STATUS &/or TANK DISP	D. E. F. M. G. J. Cchoos A. C. N. I. Y. E. F. G. H. OSAL	Calnodically protected with sacrificial anode or impres Double wall construction: single material; outer pipe of Double wall construction: dual material; outer pipe of Synthetic liner or box/trench liner in piping excavation Aboveground, no contact with soil Suction piping system Pressurized piping system Pressurized piping system automatically sampled wells Groundwater monitoring plan Groundwater monitoring system No: required - see rule for exemptions Unknown Interstitial space - tank/liner Interstitial space - double wall tank In-line detector, auto shut off In-line flow restrictor	material same as in onstructed of approv n or pipe containmen K. L. H. B. D. O. X. Z. L. M. J. K.	ed synthelic m I area Dispenser li Bulk produc Airport/seap SPCC Plan Vapor monit None Other DER a Automatic ta Manual tank Interstitial sp	naterial or pipe "jacket" ners 1 system wort hydrant system mpled wells toring system approved monitoring method ank gauging gauging pace - piping/liner pace - double wall piping #18 - GALLONS LEFT
Primary Construction: Corrosion Protection: Secondary Containment: Miscellaneous attributes: 6 - LEAK DETECTION METHODS - Site/general: Tank monitoring: Piping monitoring: 7 - TANK STATUS &/or TANK DISP Procenty closed in place - UST fill	D. E. F. M. G. J. c. N. L. J. C. N. L. Y. E. F. G. H. OSAL	Callodically protected with sacrificial anode or impres Double wall construction: single material; outer pipe of Double wall construction: dual material; outer pipe of Synthetic liner or box/trench liner in piping excavation Aboveground, no contact with soil Suction piping system Pressurized piping system Pressurized piping system Automatically sampled wells Groundwater monitorng plan Groundwater monitorng system No: required - see rule for exemptions Unknown Interstitial space - tank/liner Interstitial space - tank/liner Interstitial space - double wall tank In-line detector, auto shut off In-line flow restrictor	material same as in postructed of approv or pipe containmen K. L. H. B. D. O. X. Z. L. M. J. K.	ed synthelic m I area Dispenser li Bulk produc Airport/seap SPCC Plan Vapor monit None Other DER a Automatic ta Manual tank Interstitial sp Interstitial sp	neterial or pipe "jacket" ners 1 system nort hydrant system mpled wells toring system approved monitoring method unk gauging : gauging
Primary Construction: Corrosion Protection: Secondary Containment: Miscellaneous attributes: 6 - LEAK DETECTION METHODS - Site/general: Tank monitoring: Piping monitoring: Piping monitoring: 7 - TANK STATUS &/or TANK DISP Properly closed in place - UST fill Removed from the site A or	D. E. F. M. G. J. choose A. C. N. L. Y. E. F. G. H. OSAL ed with B: Clo	Callodically protected with sacrificial anode or impres Double wall construction: single material; outer pipe of Double wall construction: dual material; outer pipe of Synthetic liner or box/trench liner in piping excavation Aboveground, no contact with soil Suction piping system Pressurized piping system Pressurized piping system at all that apply Automaticality sampled wells Groundwater monitoring plan Groundwater monitoring plan Groundwater monitoring system Not required - see rule for exemptions Unknown Interstitial space - tank/liner Interstitial space - tank/liner Interstitial space - double wall tank In-line detector, auto shut off In-line flow restrictor	material same as in postructed of approv or pipe containmen K. L. H. B. D. O. X. Z. L. M. J. K. vnusable /12/91 (AST) - EDI a	ed synthelic m I area Dispenser li Bulk produc Airport/seap SPCC Plan Vapor monit None Other DER a Automatic ta Manual tank Interstitial sp Interstitial sp	neterial or pipe "jacket" ners 1 system wort hydrant system impled wells toring system approved monitoring method unk gauging gauging pace - piping/liner pace - double wall piping #18 - GALLONS LEFT in out-of-service tank d #19 - LAST USED DATE (mm/yy)
Primary Construction: Corrosion Protection: Secondary Containment: Miscellaneous attributes: 6 - LEAK DETECTION METHODS - Site/general: Tank monitoring: Piping monitoring: - TANK STATUS &/or TANK DISP Properly closed in place - UST fill Removed from the site A or	D. E. F. M. G. J. choose A. C. N. I. Y. E. F. G. H. OSAL ed with B. Clo	Callodically protected with sacrificial anode or impres Double wall construction: single material; outer pipe of Double wall construction: dual material; outer pipe of Synthetic liner or box/trench liner in piping excavation Aboveground, no contact with soil Suction piping system Pressurized piping system Pressurized piping system at all that apply Automaticality sampled wells Groundwater monitoring plan Groundwater monitoring plan Groundwater monitoring system Not required - see rule for exemptions Unknown Interstitial space - tank/liner Interstitial space - tank/liner Interstitial space - double wall tank In-line detector, auto shut off In-line flow restrictor	material same as in postructed of approv or pipe containmen K. L. H. B. D. O. X. Z. L. M. J. K. vnusable /12/91 (AST) - EDI a	ed synthelic m I area Dispenser li Bulk produc Airport/seap SPCC Plan Vapor monit None Other DER a Automatic ta Manual tank Interstitial sp Interstitial sp	neterial or pipe "jacket" ners 1 system nort hydrant system mpled wells toring system approved monitoring method unk gauging : gauging
Primary Construction: Corrosion Protection: Secondary Containment: Miscellaneous attributes: - LEAK DETECTION METHODS - Site/general: Tank monitoring: - TANK STATUS &/or TANK DISP Properly closed in place - UST fill Removed from the site - A or Tank construction modified to it	D. E. F. M. G. J. choose A. C. N. I. Y. E. F. G. H. OSAL ed with B. Clo	Callodically protected with sacrificial anode or impres Double wall construction: single material; outer pipe of Double wall construction: dual material; outer pipe of Synthetic liner or box/trench liner in piping excavation Aboveground, no contact with soil Suction piping system Pressurized piping system Pressurized piping system at all that apply Automaticality sampled wells Groundwater monitoring plan Groundwater monitoring plan Groundwater monitoring system Not required - see rule for exemptions Unknown Interstitial space - tank/liner Interstitial space - tank/liner Interstitial space - double wall tank In-line detector, auto shut off In-line flow restrictor	material same as in postructed of approv or pipe containmen K. L. H. B. D. O. X. Z. L. M. J. K. vnusable /12/91 (AST) - EDI a	ed synthelic m I area Dispenser li Bulk produc Airport/seap SPCC Plan Vapor monit None Other DER a Automatic ta Manual tank Interstitial sp Interstitial sp	neterial or pipe "jacket" ners 1 system wort hydrant system impled wells toring system approved monitoring method unk gauging gauging pace - piping/liner pace - double wall piping #18 - GALLONS LEFT in out-of-service tank d #19 - LAST USED DATE (mm/yy)



#### SARASOTA COUNTY GOVERNMENT SARASOTA, FLORIDA

#### **Natural Resources Department**

P.O. Box 8 Sarasota, Florida 34230 1301 Cattlemen Road, Bldg. A. Sarasota, Florida 34232 Telephone (941) 378-6113 FAX (941) 378-6067

July 3, 1997

Called Lot

William Truman, Environmental Manager Department of Environmental Protection Bureau of Petroleum Storage Systems 2600 Blair Stone Road Tallahassee, FL 32399-2400

Dear Mr. Truman:

Subject: Request for Assignment of Facility Number Foxy Lady (Former Chevron) 481 John Ringling Boulevard Sarasota, FL

Please find enclosed the Storage Tank Registration Form for the subject facility. This is a former Chevron Service Station that removed their underground tanks in June of 1984. A recent Phase II assessment yielded laboratory analyticals confirming petroleum contamination in the ground water.

The owner's agent has advised that they will apply for the Petroleum Cleanup Participation Program.

Please contact Dorene Starkey, Senior Secretary, at Suncom 522-6128 with the new facility number.

Sincerely,

unu

Eugene Cherno Environmental Supervisor Pollution Control Division

Enclosures

SC97-209



#### SARASOTA COUNTY GOVERNMENT SARASOTA, FLORIDA

#### **Natural Resources Department**

P.O. Box 8 Sarasota, Florida 34230 1301 Cattlemen Road, Bldg. A. Sarasota, Florida 34232 Telephone (941) 378-6113 FAX (941) 378-6067

July 28, 1997

Raphael Perez, Environmental Specialist II Department of Environmental Protection Petroleum Insurance Section 2600 Blair Stone Road Tallahassee, FL 32399-2400

Dear Mr. Perez:

Subject: Completed FPLIRP Inspection Package Facility #589700801 Foxy Lady (Former Chevron) 481 John Ringling Boulevard Sarasota, FL 34236

Please find enclosed a completed FPLIRP inspection package for the subject facility.

If there are any questions I can be reached at (941)378-6128.

Sincerely,

ugene Cherri ams

Eugène Cherno M Environmental Supervisor Pollution Control Division

Enclosures

**Printed on Recycled Paper** 

SC97-236

RE

30

30 AN 10

Site Name:Foxy LadyFacility ID #:58/9700801Date:May 22, 2020

### <u>SECTION I</u> - Facility & Discharge Information/Initial Abatement Southside Car Wash.

Cluster Site
Part Facility FDEP#

Site Name:

#### I-A) Site Description

Please provide a brief description of the site and a summary of site history and operations. What type of business or businesses (if any), non-petroleum as well as petroleum, operated at the former/present site? If petroleum, describe where all former and current fuel tanks, lines and dispensers were/are located (indicating how this information was obtained). Describe any access constraints (utility conduits, canopies, land cover, etc.) which also might influence the placement of monitoring wells and/or the installation of soil borings. Indicate whether there are any owner issues or traffic concerns which might affect when the work can be performed?

According to FDEP records, the Foxy Lady Site historically operated as a Chevron retail petroleum fueling and automobile repair facility. The Underground Storage Tanks (UST) system consisted on two 2,000-gallon USTs containing leaded and unleaded gasoline, one 1,000-gallon UST containing vehicular diesel and one 550-gallon UST containing used motor oil. The USTs were located in two separate pits, one of them located south of the former car wash building, and the other pit located west of the building. According to a FDEP Storage Tank Notification Form the USTs were removed from the site in 1984; however, there is no System Closure Report available in Oculus. The Site currently operates as a high-end clothing/fashion retailer.

Site map (Figure 1) illustrating all current & former tanks, lines and dispensers (including utilities, canopies, etc.) is included in Appendix B

#### I-B) Petroleum System/Tank History

List current and former UST's and/or AST's operated at site. Systems (PAST AND PRESENT) must be illustrated on Site Plan. This information should be a summary of the Department's STCM database, all tank closure reports (if applicable) and site owner & operator information.

<u>ID#</u>	AST or UST	<u>Size</u> (gallons)	Installation Date	<u>Contents</u> (unleaded gasoline/ diesel/etc.)	<u>Status</u> (active, removed or abandoned [in place])	Date Removed or Abandoned (if applicable)
1	UST	1,000	Unknown	Vehicular Diesel	Removed from Site	1984
2	UST	2,000	Unknown	Leaded Gasoline	Removed from Site	1984
3	UST	2,000	Unknown	Unleaded Gasoline	Removed from Site	1984
4	UST	550	Unknown	Used Oil	Removed from Site	1984

-If above information is different than the Department's STCM database, please indicate source of updated information:

#### I-B) Petroleum System/Tank History (continued)

Active Site? If yes, please indicate method, date and extent of latest tank and line tightness test (include copy of tightness test results). If tank tightness test results are not available, please explain why they are not necessary or indicate when next tightness test will be performed.

Site is presently an operating clothing/fashion store.

Copy of tightness test results included in Appendix

2020-08-13 - Foxy Lady - TSAR- revised.docx

YES

NO

X

Site Name:	Foxy Lady	
Facility ID #:	58/9700801	
Date:	May 22, 2020	

## **SECTION III** - Recent Site Assessment Activities III-A) Soil Investigation

Was soil (vadose zone and smear zone) investigated? If yes, please provide a brief discussion of soil sampling methodology, including the method(s) used to collect the laboratory samples. If no, please explain. X NO

AGuA, LLC (AGuA) was on-site on November 5, 2019, to conduct a soil assessment at the Site. Eleven soil borings (SB-1 through SB-11) were advanced in the approximate former UST and dispenser locations, with the exception of the Waste Oil UST the location for which was occupied by a unknown car at the time. The soil borings were advanced via stainless steel hand auger to three feet BLS with soil sample collection per the Scope of Work created by the Local Program Site Manager (LPSM); one sample was collected every foot down to borehole completion. Soil samples were collected in accordance with Florida Department of Environmental Protection (FDEP) guidelines and screened for organic vapors using an Organic Vapor Analyzer with Photo-Ionization Detector (OVA-PID). Upon discussing OVA results with the LPSM, AGuA was instructed to collect four laboratory samples (SB-1-1, SB-3-1, SB-4-1, and SB-8-1). The samples were collected in laboratory-provided sample containers per FDEP guidelines, placed on ice and submitted to Advanced Environmental Laboratories, Inc. (AEL), for analysis via EPA Method 8260B (BTEX & MTBE), EPA Method 8270 (PAHs) and the FL-PRO Method for TRPH, with additional material collected for contingent SPLP and TRPH Speciation analysis.

On April 16, 2020, AGuA returned to the site with Preferred Drilling Solutions, Inc (PDS) to perform soil sampling in the vicinity of the used oil UST, as well as delineation soil sampling in the vicinity of the former dispenser island. Prior to well installation soil samples were collected, via Direct-Push Technology (DPT), from the MW-7 borehole at 1-foot intervals down to four feet, then at 2-foot intervals down to twelve feet. Additionally, Five soil borings (SB-12 through SB-16) were advanced via stainless steel hand auger down to four feet BLS with soil sample collection every foot down to borehole completion. Soil samples were collected in accordance with FDEP guidelines and screened for organic vapors using an Organic Vapor Analyzer with Photo-Ionization Detector (OVA-PID). One sample was collected from the 2-foot interval of the aforementioned borings for laboratory analysis. The samples were collected in laboratory-provided sample containers per FDEP guidelines, placed on ice and submitted to AEL for analysis as follows:

- Samples SB-12-2, SB-13-2 and SB-14-2 were submitted for analysis via EPA Method 8270 (PAHs) and the FL-PRO Method for TRPH.
- Samples SB-15-2 and SB-16-2 were submitted for analysis via EPA Method 8270 (PAHs)
- Sample MW-7-2 was submitted for the suite of analyses as detailed in Table D of Chapter 62-780, F.A.C.

Date of last soil sc	reening	event (OVA data) with or withou	it la	borator	v sampling:	4/16/20	920	
Site map (Figure	4	) illustrating sampling locations is	s inc	luded in	Appendix	В		
Tabular su	mmary o	of soil screening results (Table	1	) is	included in	Appendix	Α	
Tabular summar	y of labo	pratory soil sampling results (Tables	8	thru 12	) are inclu	ded in Appen	dix	A
	Soi	l sampling logs (for laboratory samp	oles)	are inclu	ded in Appe	endix C		

Page 15 of 28

Site Name:	Foxy Lady	
Facility ID #:	58/9700801	
Date:	May 22, 2020	_

#### III-B) Groundwater Investigation (continued)

Was groundwater sampling performed? If yes, please provide a brief discussion of groundwater purging and sampling methodology and identify the wells that were sampled. If no, please explain.

On October 23, 2019, AGuA mobilized to the Site to collect groundwater samples from three
existing monitor wells (MW-2 through MW-4). Prior to sample collection a Depth-to-Water
(DTW) survey was conducted; all monitor wells were opened and allowed to equilibrate with
atmospheric pressure after which depth-to-water measurements were collected with an interface
probe. Additionally, a Top-of-Casing (ToC) survey was performed on the wells since historical
data for the monitor wells could not be located. AGuA personnel then collected groundwater
samples from the three wells in accordance with applicable FDEP SOPs. The samples were
collected in laboratory-provided sample containers per FDEP guidelines, placed on ice in a cooler
and submitted to AEL for analysis via EPA Methods 8260 for BTEX/MTBE and EDB, 8270 for
PAHs and 6010 for Total Lead, as well as via the FL-PRO Method for TRPH.

YES

X

NO

On April 20, 2020, AGuA remobilized to the Site to collect groundwater samples from monitor wells MW-2 through MW-7. Again, DTW and ToC survey were performed as described above. All of the samples were collected in laboratory-provided sample containers per FDEP guidelines, placed on ice in a cooler and submitted to AEL for analysis. Monitor well samples MW-2 through MW-6 were submitted for analysis via EPA Methods 8260 for BTEX/MTBE and 8270 for PAHs, as well as via the FL-PRO Method for TRPH, whereas the sample collected from MW-7 was submitted for the suite of analyses as detailed in Table D of Chapter 62-780, F.A.C.

If groundwater sampling not performed, indicate date of last sampling event (if applicable): Indicate wells sampled on that date (if applicable):

 Site map (Figure 6 ) illustrating the groundwater sampling results is included in Appendix
 B

 Tabular summary of groundwater sampling results (Table 3 thru 7 ) is included in Appendix
 A

 Groundwater field sampling logs are included in Appendix
 C

Groundwater samples (previous sampling events included) have been collected and analyzed for:

Required for	all suspected GAG/KAG	sites.
X BTEX/MTBE	X PAHs	X TRPHs
Required for all con	taminated GAG/KAG sites.	
X EDB	X Lead (Pb)	X VOHs
Required for all suspected u	sed oil (or unknown fuel type	) contaminated sites.
X Priority Pollutant Volatile Organics & Extractable Organics	X As, Cd, Cr, Pb	X TRPHs

Site Name:Foxy LadyFacility ID #:58/9700801Date:May 22, 2020

#### III-B) Groundwater Investigation (continued)

Was groundwater IDW generated? If yes, please explain why disposal on-site was not possible.	YES	NO	N/A
Volume of contaminated groundwater dispose	ed of:		drums
	YES	NO	N/A
Was groundwater contamination identified above the	X	direction of the	
applicable Cleanup Target Levels? If yes, indicate locations where highest concentrations detected with depths encountered. If "N/A", ple			
MW-2 which contained TRPH, 1-Methylnaphthalene and 2-Met exceeding their respective GCTLs, as well as Naphthalene excee the sample collected from MW-2 in October 2019 contained Lea Lead analysis was not performed on the MW-2 sample collected	eding its NA ad exceeding	DSC. Addit g its GCTL, 20.	ionally,
Approximate volume of contaminated groundwater:         Plume map [Figure       6       ] illustrating extent o         is included in Appendix       B	f groundwater	gallons contamination	i.
Has horizontal delineation been completed in the surfic aquifer? If no, please describe where additional sampling is required (indicating wells and needed analyses) and/or additional monitor proposed screened intervals for each). If "N/A", please explain.		NO X Id be installed	N/A
At least one additional shallow monitor well needs to be ins construction should be the same as monitor wells MW-5 through		west of MV	W-2; well
Site map (Figure7) illustrating proposed monitoring well location	ons is included	l in Appendix	B
II-B) Groundwater Investigation (continued)			
	YES	NO	N/A
Has vertical delineation been completed in the <u>plume</u>		X	
<b><i>area?</i></b> If no, please describe where additional sampling is required (indicating needed analyses) and/or identify locations where vertical extent w proposed screened intervals, single or double cased and length of surface cas		ALC: NOT THE REPORT OF THE	0
One vertical extent well should be installed adjacent to MW-2; with 5' of 0.01 slot screen and 18' of 6-inch outer casing.			
oposed screened intervals, single or double cased and length of surface cas ne vertical extent well should be installed adjacent to MW-2;	<i>sings). If "N/A</i> it should be	", please expla installed to	in. 25' BLS

Site Name:	Foxy Lady	
Facility ID #:	58/9700801	
Date:	May 22, 2020	

	YES	NO	Unknowi
Is the lower aquifer(s) contaminated? If yes, please describe			X
location and estimated depth of contamination. If unknown, please explain.		-	
There are no vertical extent wells on-site.			
Cross-section (Figures ) illustrating vertical extent of contamination Appendix	n is include	d in	
	YES		NO
Were natural attenuation parameters data collected? If yes,		1 1	v
please specify which parameters were collected (and where collected) and provide		$1 \leq 1$	Λ
interpretation of results.			
		6 P.	
Site map (Figure) illustrating natural attenuation parameter data is Tabular summary of parameter sampling results (Table) is in	cluded in A		
	YES	NO	Unknowi
Have any supply wells or surface waters been impacted?			X
If yes, please indicate concentration(s) of water sample(s) taken and the			Δ
wells/surface water body/bodies impacted. If unknown, please explain.		1	
Neither the nearby irrigation wells nor the nearby surface waters have	been test	ed.	
		-	
	YES	NO	Unknown
Is surface water and/or sediment sampling required? If yes,		X	
please indicate where samples should be collected, and the proposed analyses.		11	
Note: surface water sampling results should be summarized with the groundwater a compling results should be summarized with the soil angletical neults 1. If whereas the second states are the second			sediment
sampling results should be summarized with the soil analytical results.] If unknown The recent groundwater sampling events indicate the groundwater imp			emained
on-site, thus AGuA does not yet recommend sampling the nearby surf			
wells			
Site map (Figure) illustrating sampling locations is included in A	Appendix		
	YES	NO	Unknowi
Are there any potable wells that need to be sampled? If yes,	-	X	
please indicate wells to be sampled, and the proposed analyses. If unknown,	<u> </u>	- La come	÷
please explain.			

Map Direct Search Results Tue Sep 08 2020 11:29:51 GMT-0400 (Eastern Daylight Time)

Search Made:

Search Box 251 feet wide at 27.31883231 x -82.57792842 27°19'7.7963" x -82°34'40.5423"

#### Search Results: 1

▲ DEP Cleanup Sites STCM SOURCE DATABASE NAME EXXON-ST ARMANDS **BUSINESS NAME** 64191764 CLEANUP SITE KEY 8520819 SOURCE DATABASE ID https://prodenv.dep.state.fl.us/DepNexus/public/electronic-documents/8520819/facility!search DOCUMENTS **1 N BLVD OF PRESIDENTS** SARASOTA, FL 34236-1304 Address (58) Sarasota County CC2 COUNTY ID (SD) South Regulatory District OC3 OFFICE ID PETRO CLCC CLEANUP CATEGORY KEY **DPHO** . CMC2 COORDINATE METHOD ID TK CPAC PROGRAM AREA ID 1999 dogs . MAP SOURCE FACIL OIC OBJECT OF INTEREST ID VICIN . PC2 PROXIMITY ID PENDING . **RSC2 REMEDIATION STATUS KEY** FL STCD1 STATE ID DPHO . VERIFIED COORDINATE METHOD ID REVIEWED Status ID 09/08/2020 DATA LOAD DATE **4** 10/29/2003 COLLECT DATE

9/8/202	0
	10/29/2003 VERIFICATION DATE
2	WALL_K58 collect username
2	CONTRACTOR COLLECT AFFILIATION
2	WALL_K58 Verifier Username
2	CONTRACTOR Verifier Affiliation
67	4 CALC COORD ACCURACY LEVEL ID
	1957 MAP SOURCE SCALE
	Latitude: 27° 19' 8.2121" Longitude: 82° 34' 40.2889"
	Datum: HARN

Disclaimer: This report is only intended to be used as an approximation of the possibility of nearby regulated features. It is not intended for legal purposes. Neither the State of Florida, nor the FDEP, makes any warranty, expressed or implied, including the warranties of merchantability and fitness for a particular purpose arising out of the use or inability to use the data, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Use of information contained on the FDEP web pages constitutes understanding and acceptance of our disclaimer.

Map Direct Search Results

Department of Environmental Regula

# **Discharge Notification Form**

Form 17-1.218(3)

Use this form to notify the Department of Environmental Regulation of:

- 1. Results of tank testing which reveal a discharge within 3 working days of testing.
- 2. Discharges exceeding 100 gallons on pervious surfaces as described in Section 17-61.05(4)(b) within 3 working days of discover
- 3. Positive response of a detection device, monitoring well test of sample or laboratory report within 3 working days of discovery

Mall to the DER District Office in your district.

#### PLEASE PRINT OR TYPE Put "X" where answer is unknown.

1. Facility Number: 5	88520819 2. Tank Number: .	1, 2, 3, 4, 5 3. Date: 1/24/91	
4. Facilley Name: S	t. Armands Exxon		
Facility Operator: D	r. William G. James (owner)		
Facility Address: 1	N. Boulevard of Presidents,	, Sarasota, Florida	
Telephone Number:	1 416 1274-5303	County: Sarasota	
Malling Address: 1	Port Street East, Mississau	uga, Ontario 156 4N1	_
6. Date of test or discou	ery: 1/24/91	month/	'day
6. Method of Initial disc	covery. (circle one <u>only</u> )		
	tor in ground, monitoring	D. Emptying and inspection,	
well, or containm		E. Inventory control.	
	inderground tanks only).	E Odor or visible signs at facility or in vicinity.	
C, Manual test of m	onitoring well(s).	G. Other: UST Closure Assossment	(ext
7. Estimated number of	gallonsloss: Not Available -	ABANDONED BY PREVIOU OPERATO	R
		oly) A. Dispenser B. Pipe C. Fitting D. Tank E.U	
	rale the choices which describe the type.		
A. Abaveground	D. Underground	H. Sacrificial anode type	
8. Factory welded C. Field erected	E. Bare or asphalt-coated steel F. Fiberglass-clad steel	I. Impressed current type J. Double walled	
C. Field erected	G. Fiberglass	(M.)Other or Unknown	lex:
			1
10. Type of pollutant dis		a	
A. Leaded Gasoline.		E. Aviation fuel. Y. Other	
B. Unlesded gasolin C. Gasonol of sicohi		Z. Unknown	IAN
			19.7
11. Cause of leak. (circle			
0	Piping	Tank	
(A) Unknown	8. Split	G. Split J. Installation failure H. Corrosion P. Other	
	C. Loose connection	(H.)Corrosion P. Other	
		an te rivernetantit	
12. TO THE BEST OF	MY KNOWLEDGE AND BELIEF AL	L INFORMATION SUBMITTED ON THIS FORM IS TRU	UE
CURATE, AND COM			

Dr. William G. James Name of Owner Operator or Authorized Representative

Signature of Owner, Operator, or Authorized Represent

---

KEEP A COPY OF THIS FORM FOR YOUR RECORDS.

DER PO GM 17-L218(3) 9/1/04 (1/2)

A. GALLER!

# EARTH SCIENCE, INC.

Assessments, Consulting, Remediation, Research & Development 10112 E. Rivershore Drive SE, Alto, MI 49302 Phone (616) 891-0764 ~ (616) 891-0762 (fax) E-mail: earthscience1@earthlink.net Website: ESI-Environmental.com

February 22, 2012

Project #: 11-015

w

ENV

Ms. Michelle Allard, PG WRScompass Sr. Geologist Petroleum Cleanup Section Five Bureau of Petroleum Storage Systems Florida Department of Environmental Protection (FDEP) Bob Martinez Center 2600 Blair Stone Road, MS 4585 Tallahassee, FL 32399-2400

Dear Ms. Allard:

Subject:

First Event General Report – Low Scored Site Initiative (LSSI) Exxon - St. Armands 1 N. Boulevard of Presidents, Sarasota, FL Discharge Reporting Date: January 24, 1991 Eligibility: Abandoned Tank Restoration Program (ATRP) FAC #: 58/8520819; Priority Score: 8 Work Order #: 2012-95-W97105

RECEIVED III FEI 27 A D. 58 III FEI 27 A D. 58

Earth Science, Inc. is pleased to provide you with this First Event, General Report for that LSSI investigation performed for the discharge reporting at the subject site. The work order was performed in accordance with the scope of work specified for the First Event under Work Order #2012-95-W97105, with the following exceptions:


- Shallow monitor well MW-11, which is an off-site monitor well located in a median, could not be readily located in the field and presumed destroyed or covered by that landscaping material installed by others. Verbal notification that this well could not be located to perform groundwater sampling was provided to the FDEP from the field on January 30, 2012.
- Total petroleum hydrocarbon (TPH) analysis using the FLPRO method could not be performed on the groundwater sample collected from shallow monitor well MW-1. The Accutest Laboratories, extractions group used that sample aliquot provided for TPH analysis for an internal quality assurance (QA) for EPA method 8082. Email notification on this occurrence was provided to the FDEP on February 6, 2012.

#### Subject Site Location

The subject site is located at 1 N. Boulevard of Presidents, Sarasota, Sarasota County, FL (Figure 1). The geographic location is Section 26, Township 36S, Range 17E. As depicted in the following 2012, aerial photograph, the subject site is bound to the east by Boulevard of Presidents and St. Armands

Ms. Michelle Allard, PG February 22, 2012 Page 2

Circle. To the north and south the subject property is bound by zero-lot line, commercial parcels. To the west is an alley and then commercial property.



Source: Sarasola County, Geographic Information Systems, 2012.

The subject location occupies approximately 0.35-acres and is commercially operated, with 10 retail units. The Sarasota County Parcel ID # is 2014-05-0143. Figure 1 depicts the building layout and shows the historical underground storage tank (UST) system layout and well locations.


The one-story, 9,002 square foot  $(ft^2)$  building has masonry and metal exterior construction. The interior flooring is concrete, with various finished surface coverings. The parking areas are asphalt covered with concrete patchwork. The facility is serviced by public utilities for water and sewer.

The area of investigation was located in front and behind the building (Figure 1). Overhead restrictions in the area of investigation include overhead utilities. Subsurface utilities were also noted in the area of investigation and are denoted on Figure 1. Photo documentation of the area of investigation is provided as Attachment 1.

#### **Background and Description of Previous Assessment Work**

A discharge reporting was submitted for the subject site on January 24, 1991. The method of discovery was noted as "UST closure assessment." It was unknown as to the cause or what part of the storage system was leaking. The Florida Department of Environmental Protection (FDEP) correspondence dated June 28, 1991 documents that the contamination related to the storage of petroleum products at the site was eligible for state funded cleanup under the ATRP Program.

In 1991, multiple UST's that stored leaded and unleaded gasoline, as well as used oil, were excavated and removed from the subject site under the observation of Environmental Science & Engineering, Inc. The location of each former UST and the limits of excavations performed at the site are depicted on Figure 1. A copy of the Underground Storage Tank Removal Report is on file with the FDEP as Oculus file # 000643634. Excessively contaminated soils and groundwater impacts were documented at this site through the performance of a site assessment (Oculus file # 00064637). Proposed remedial actions (Oculus file #'s 00064574, 00064571, and 00064572) were subsequently approved by the FDEP on September 6, 1993 (Oculus file #00064552). The remedial system (soil vapor extraction) was operational in May 1994. Remedial actions were subsequently suspended when the reimbursement program ended and funding for the site was not available given its low priority score. The aboveground remedial equipment and fenced compound were subsequently removed from the site in 1999.



2				
1.5	D.		t Dourse 1	
FLORIDA Instructions		ischarge Report Form		DEP Form # 12-761 900(1).
				Lonn Tale Discharge Repair Form
SI SE IN		PLEASE PRINT OR T	III.	Effective Date
of the 1			1	10th
FLORIDA		s on the reverse side. Please com	plete all applicable blanks	. 6 St.
				19
Facilies ID Number (if t	constreed): 58 X6-2.	512-9 2. Date	of form completion: 10-	- 11- 02
	4C1	6507		£
. General information		Sarasuta Yach	atclub	
Facility name or response	ble party (it applicable	Surasite Yacht ( Lie		· · · · · · · · · · · · · · · · · · ·
· · · · ·	/ II	Telephone Munsher: /	141 1764141	County Suranta
Ver haven Die darson Ma	aling Address 1100)	Labor Bradlan D'iller	ACCA. MALLANDA F LA	
Location of Discharge (St	reet addressDD	John Angring Divisy	Kel Varia FL	ender
Latitude and Longitude o	f Discharge (if known)	· ···		
4. Date of receipt of test a	results or		5. Estimated number of	gellins discharged: Unknown
discovery of confirmed	discharge: /0-	11- 02 month/day/year		
				A STREET STREET STREET
6. Discharge affected:	I Air Nd Soil	M Groundwater     Drinking	g water well(s) [ ] Shorelin	ie     Surface water (water body name)
A had ad attaction of a	herk all that analy)			······································
7. Method of discovery (check all that apply)     Liquid detector (automatic or manual)		Internal inspection	De Closure/Closure Assessment	
Vapor detector (automatic or manual)		[ ] Inventory control		
Tighmens Icst		Monitoring wells	Soil analytical tests or	samples
Pressure lest		[   Automatic tank gauging	Visual observation	
) Statistical Inventory R	econciliation	Munual tank gauging	[ ] Other	
. Type of regulated subst	ance discharged: (ch	cck anc)		
Unknown	Used/waste uil	Jet fuel	Heating oil	) New/lube oil
1. & Caralina	L LA vision gas	(vd Diese)	[ ] Kerosenc	Mineral acid
Hazardous substance -	includes CERCLA sub	bstances from USTs above report	able quantities, pesticides, and	monia, chilonne, and derivatives
(write in name or Cher	nical Abstract Service	(CAS) number)		······································
Oiher				
. Source of Discharge: (c	heck all that apply)			
Dispensing system	1   Pipe	Barge	Pipeline	Vehicle
] Tank	Fitting	Tanker ship     Other Vessel	Railroad tankcar     Tank truck	Airplanc     Drum
D Unknown	Valve fuilure	[ ] Ouler verser	1 Tank uper	11
Other				
10. Cause of the discharge	e: (check all that apply	·)		
Loose connection	Puncture	[ ] Spill	(   Collision	I Corrosion
Fuclexplosion	Overfill	Human error	Vehicle Acciden	r f 1 10215(19000) tallmic
Do Other UnKour				1
1. Actions taken in respo	ase to the discharge:	Tanking Pixing	where removed and	replaced.
II. Acuans taken in respo	ase to the discharge:	Tanking Pixing	where removed and	replaced.
II. Actions taken in respo	nse to the discharge:	Tankian Pixing	where removed and	
	nse to the discharge:	Tankian Pixing	where removed and	
	nse to the discharge:	Tankian Pithay	where removed and	
	nse to the discharge:	Tankian Pithag	where removal and	
13. Comments:		Tankian Pithay	where removed and	
12. Comments:	pplicable):			
12. Comments: 13. Agencies notified (as # 1 ) State Warning Point	pplicable):     National Respo	onse Center     Flurida Ma	arine Patrol   } Fire Depart	ment. () DEP (district/person)
13. Comments: 13. Agencies notified (as # 1 ) State Warning Point 1-800 320-0519	pplicable):     National Respo  -800-424-880	onse Center     Flurida Ma 2 (800) 342	arine Patrol   } Fire Depart 2-5367	ment. ( ) DEP (district/person) County Tanks Program
13. Comments: 13. Agencies notified (as # 1 ) State Warning Point 1-800 320-0519	pplicable):     National Respo  -800-424-880	onse Center     Flurida Ma 2 (800) 342	arine Patrol   } Fire Depart 2-5367	ment. ( ) DEP (district/person) County Tanks Program
13. Comments: 13. Agencies notified (as # 1 ) State Warning Point 1-800 320-0519	pplicable):     National Respo  -800-424-880	onse Center     Flurida Ma	arine Patrol   } Fire Depart 2-5367	ment. ( ) DEP (district/person) County Tanks Program
12. Comments: 13. Agencies notified (as # 1 ) State Warning Point 1 -800 320-0519 14. To the base of my know KOM BIA	pplicable): 1   National Respondence 1-800-424-880 wledge and belief, all CASOC	onse Center     Flurida Ma 2 (800) 342 information submitted on third	arine Patrol 1 Fire Depart 2-5367 Torm Terrue, accurate, and c Tor BleffSD	ineni. (   DEP (district/person) 
13. Agencies notified (as # 1 ) State Warning Point 1-800 320-0519	pplicable): 1   National Respo 1-800-424-880 wiedge and belief, all CASO perator of Authorized I	onse Center     Flurida Ma 2 (800) 342 information submitted on third	arine Patrol 1 Fire Depart 2-5367 Torm Terrue, accurate, and c Tor BleffSD	Ineni. (   DEP (district/person) County Tanks Program complete.



# SARASOTA COUNTY

"Dedicated to Quality Service"

October 21, 2002

CERTIFIED MAIL RETURN RECEIPT REQUESTED

Ronald Bledsoe 1100 John Ringling Boulevard Sarasota, FL 34236

Subject: Facility #588516507 Sarasota Yacht Club 110 John Ringling Boulevard Sarasota, FL

Dear Mr. Bledsoe:

On July 10, 2002, Sarasota County Environmental Services, Air and Water Quality Protection, under contract with the Department of Environmental Protection (Department), conducted an inspection of your pollutant storage tank facility. Contamination was discovered on October 11, 2002 and a Discharge Reporting Form (DRF) was filed with the Department.

If free product attributable to this discharge is present at your site, the responsible party must take steps to obtain cleanup services for product recovery or initiate product recovery within three days of discovery of free product. Product recovery shall be performed in accordance with Rule 62-770.300, Florida Administrative Code (F.A.C.).

Further, you are obligated to initiate a Site Assessment within 30 days of discovery of the contamination in accordance with Chapter 62-770, F.A.C. Within 270 days of discovery of contamination, two copies of a Site Assessment Report (SAR) shall be submitted by the responsible party to:

Curtis R. Smith, Environmental Specialist III Air and Water Quality Protection 2817 Cattlemen Road Sarasota, FL 34232

After submittal of the SAR, please be advised that additional requirements for cleanup of the contamination may apply. Within 14 days after receipt of this letter, you must provide the **Department with written notification detailing actions to be taken.** If you have any questions, please contact me at (941) 861-6265.

4



SARASOTA COUNTY "Dedicated to Quality Service"



October 21, 2002

Lewis J. Cornman, Environmental Specialist III Department of Environmental Protection Storage Tank Regulation 2600 Blair Stone Road, MS 4525 Tallahassee, FL 32399-2400

Subject: Discharge Report Form

Dear Mr. Cornman:

Enclosed please find a Discharge Report Form for a site that has exceeded Chapter 62-770, Florida Administrative Code, standards.

Please call me at Suncom 549-6220 if you have any questions.

Sincerely,

Eugene Cherno, CECM

Environmental Supervisor Air and Water Quality Protection

Enclosures

cc: Leslie Pedigo, Environmental Specialist III, Storage Tanks, Department of Environmental Protection, Tampa

DRF02.011

Ronald Bledsoe Sarasota Yacht Club

October 21, 2002 Page 2

...

Option to apply for Site Rehabilitation Funding Allocation Agreement for sites with existing contamination eligible for state-funded cleanup.

If this site has previously existing petroleum contamination which is eligible for cleanup funding from the Inland Protection Trust Fund under the Early Detection Incentive Program, Abandoned Tank Restoration Program, Petroleum Liability and Restoration Insurance Program or Petroleum Cleanup Participation Program, Section 376.30714, Florida Statutes, provides interested persons an option to apply to the Department to enter into a Site Rehabilitation Funding Allocation agreement with the Department. The agreement will establish the respective funding allocations of the Department and the applicant for cleanup of the combined discharges, and will establish the priority in which such cleanup will occur. In such an agreement, the Department will be responsible for cleanup of no more than the existing eligible contamination and the applicant will be responsible for cleanup of no more than the new discharge. Applicants wishing to take advantage of this option must submit a Limited Contamination Assessment Report (LCAR) and Application for Site Rehabilitation Funding Allocation Agreement to the Department within 120 days of the date of discovery of the new discharge. Until such time as the application is submitted to the Department with a complete LCAR, you remain obligated to perform the site assessment activities set forth in Chapter 62-770, F.A.C. In all cases, the owner, operator or responsible party must remove free product attributable to the new discharge in accordance with Chapter 62-770, F.A.C. A copy of program information and requirements, minimum content of the LCAR, and application form, may be obtained by contacting the Bureau of Petroleum Storage Systems, at (850) 488-3935, or at the Bureau's internet web site address at www.dep.state.fl.us/waste/key\_areas/pss/default.htm.

Sincerely,

Curtis R. Smith Environmental Specialist III Air and Water Quality Protection

 cc: Grace Rivera, Environmental Manager, Bureau of Petroleum Storage Systems, Department of Environmental Protection, Tallahassee
 Leslie Pedigo, Environmental Specialist III, Tanks Section, Department of Environmental Protection, Tampa

Marc Swartz, Engineer II, Coordinator, Environmental Health Services

SAR02.091

#### **REMEDIAL ACTION PLAN** SARASOTA YACHT CLUB - 1100 JOHN RINGLING BOULEVARD SARASOTA, FLORIDA 34236

**Prepared for:** 



**Debbie Looney & Associates, Inc.** 9491 Cove Avenue Pensacola, Florida 32534

and



Sarasota Yacht Club **1100 John Ringling Boulevard** Sarasota, Florida 34236



**EnSafe Inc. 5724 Summer Trees Drive** Memphis, Tennessee 38134 (901) 372-7962 www.ensafe.com

Date:

April 4, 2006

PB Hardy Signature Ben Bratley

Signature

Vaire barnet Signature

Phil Hardy, CHMM Project Manager

Ben Brantley, P.G. Peer Reviewer

Claire Barnett, P.E. Professional Engineer/Reviewer

#### **EXECUTIVE SUMMARY**

EnSafe Inc. was retained by Debbie Looney & Associates, Inc. to prepare this Remedial Action Plan (RAP) to develop a technical strategy for addressing petroleum hydrocarbon constituents identified in soil at the Sarasota Yacht Club (SYC). The petroleum hydrocarbon constituents were above the Florida Department of Environmental Protection (FDEP) Soil Cleanup Target Levels (SCTLs) cited in Chapter 62-777, Florida Administrative Code (FAC). The Facility Identification Number for the SYC is 8516507. This RAP has been prepared in general accordance with Chapter 62-770, FAC, for review by the Sarasota County Environmental Services (SCES).

The SYC was incorporated in 1926 and has operated as a yacht club at its current location along Coon Key on Sarasota Bay since 1940. During 2002, a 2,000-gallon gasoline underground storage tank (UST) and a 4,000-gallon diesel UST were removed at the SYC, and replaced by a single 12,000-gallon gasoline UST. A closure assessment performed in May 2002 determined that petroleum hydrocarbon contamination was present in soil and groundwater in the former tank vault and the valve box area at the end of the pipe run. A site assessment performed in 2003 confirmed the presence of polynuclear aromatic hydrocarbons (PAHs) above the SCTLs. Minor PAH contamination was found in groundwater. Follow-up investigations were performed in 2003 and 2005. The 2003 follow-up determined the presence of benzo(a)pyrene in soil above the SCTL, while the 2005 assessment revealed benzo(a)pyrene equivalents above the SCTL.

The SCES has requested that the SYC develop a RAP to address petroleum-contaminated soil and groundwater at the site.

This RAP presents two alternatives: (1) excavation of hot spots and leachability criteria exceedances for unrestricted use, with offsite disposal; and (2) capping of contaminated soil, with no further action (NFA)/institutional controls. Per FDEP regulations and the SCES's requirements, one year of groundwater monitoring is required under both alternatives to ensure there is no leaching of petroleum constituents to site groundwater.

Under the soil removal alternative, approximately 84 cubic yards (yd<sup>3</sup>) (110 tons) of petroleum-contaminated soil would be removed from the site for thermal treatment and disposal. Clean soil would be used to backfill the excavated area. One year of quarterly groundwater monitoring would be conducted to ensure that petroleum products have not leached to site groundwater.

Under the capping alternative, approximately 2,100 square feet in the contaminated area would be capped with 4 inches of concrete or asphalt. One year of quarterly groundwater monitoring would be conducted to ensure that petroleum products have not leached to site groundwater. An



institutional control would be implemented for the capped area, and NFA with conditions granted after a year of site groundwater data is collected.

The selected alternative is excavation of hot spots and leachability criteria exceedances. This alternative is protective of the environment, precludes the need for capping the contaminated area and would allow for a future unrestricted reuse of the site. No maintenance or institutional controls will be required, and no precautions will be necessary for invasive work in the currently contaminated area under the soil removal alternative. After one year of groundwater monitoring data is collected, should these data show there is no petroleum contamination above FDEP standards, a Site Rehabilitation Completion Order for soil and groundwater can be requested from the SCES.

iii



ENSAFE

Remedial Action Plan Sarasota Yacht Club — 1100 John Ringling Boulevard Sarasota, Florida April 4, 2006

#### 2.0 SITE BACKGROUND AND ENVIRONMENTALHISTORY

#### 2.1 Background

The SYC was incorporated in 1926 and has operated as a yacht club at its current location along Coon Key on Sarasota Bay since 1940. Figure 1 is a site location map that shows the SYC relative to the local area. The SYC has a large club house and dining room, and indoor and outdoor recreational facilities. A large swimming pool is located south of the dining room. Three boat docking piers are located along the seawall to the east of the facility. A large parking lot is to the west. The SYC underwent improvements/expansion over the years, with new facilities added in 1958, 1963, 1971, 1978, 1991, and 1998.

#### 2.2 Environmental History

#### 2.2.1 Tank Closure Assessment

During 2002, a 2,000-gallon gasoline underground storage tank (UST) and a 4,000-gallon diesel UST were removed at the SYC, and replaced by a single 12,000-gallon gasoline UST. A Closure Assessment was performed by Environmental Safety Consultants, Inc. (ESC) in May 2002, and a Closure Assessment Report was published on September 25, 2002. The Closure Assessment Report determined that petroleum hydrocarbon contamination was present in soil and groundwater in the former tank vault and the valve box area at the end of the pipe run and that further assessment was required per the applicable FDEP regulations. On October 11, 2002, a Discharge Release Form outlining the release was submitted to the Sarasota County Environmental Services (SCES) (the agency under contract with the FDEP, Bureau of Petroleum Storage Systems to handle petroleum program issues in Sarasota County). Figure 2 shows the basic layout and location of the SYC's USTs and associated piping.

#### 2.2.2 2003 Site Assessment

During 2003, a contamination assessment was performed by ESC that included an organic vapor survey, the advancement of six soil borings with associated soil sampling, and the installation and sampling of four permanent monitoring wells and three temporary wells.

Soil analytical results reported in ESC's April 18, 2003, Site Assessment Report (SAR) revealed the presence of polynuclear aromatic hydrocarbons (PAHs) above the SCTLs. Minor PAH contamination was found in groundwater. ESC concluded that there would likely be no further impact to site groundwater if contaminated soils remained in place, and recommended to the SCES that the site be considered for natural attenuation monitoring. The SCES responded that further assessment was warranted to delineate soil and groundwater PAH contamination in the vicinity of boring B3 and well TMW-1 (see the map in the inset box on page 5).





3

Sarasota, Florida Sarasota Yacht Club — 1100 John Ringling Boulevard April 4, 2006 Remedial Action Plan



Table 1

B20 52.2 6.7.9 70.4 70.7 81.1 26.3 49.1 85.2 240 318 123 206 16.1 677 257 Q R 74 102.11<sup>a</sup> 29.3 80.6 25.8 57.9 11.6 53.3 64.8 36.4 70.4 48.2 B19 96.3 61.8 2 131 QN QN 204 37 280.68<sup>a</sup> 168ª 132.0 202.0 **B18** 11.6 31.2 82.6 78.2 388 224 109 129 617 180 18 QN 286 158 65 Sample Location 6,069.04<sup>a</sup> 3,730ª 8,630<sup>b</sup> 23,600 10,200 3,350 2,460 6,670 2,280 5,240 6,930 4,850 826 Q 2 QN 798 **B13** Q Q Benzo(a)pyrene Equivalent Concentrations (BEQs) Distribution of PAH Contamination Sarasota Yacht Club 501.47<sup>a</sup> 252<sup>a</sup> 1,230 42.5 28.3 169 16.7 449 340 128 213 316 300 260 237 132 356 127 88 QN 792.58<sup>a</sup> 461<sup>a</sup> 3,280 .,460 56.7 85.3 439 289 249 587 225 QN 804 608 83 QN Q 791 Q 427 1,200 8,000 160,000 3,100 8,500 8,000 2,100 27,000 2,500,000 32,000,000 1,200,000 250,000 880,000 Leachability SCTL 2,600,000 55,000 100 100 Residential 2,400 1,800,000 21,000,000 2,500,000 3,200,000 200,000 210,000 2,200,000 2,400,000 Indeno(1,2,3-cd)pyrene Dibenz(a,h)anthracene Benzo(b)fluoranthene Benzo(k)fluoranthene 1-Methylnaphthalene 2-Methylnaphthalene Benzo(g,h,i)perylene Benzo(a)anthracene Benzo(a)pyrene Acenaphtylene Acenaphthene Phenanthrene Fluoranthene Naphthalene Parameter Anthracene Fluorene Chrysene Pyrene BEQS

# Notes:

Ē

All concentrations listed are in micrograms per kilogram (µg/kg)

Exceeds leachability SCTL Exceeds residential SCTL 11 Ħ


11

Exceeds both residential and leachability SCTLs Benzo(a)pyrene equivalent concentration. Calculated for select PAHs based on guidance contained in Chapter 62-777, FAC, Table 2, Soil Cleanup Target Levels Not detected

PAH ND

Polynuclear Aromatic Hydrocarbon Soil Cleanup Target Level, from Chapter 62-777, FAC, Table 2, Soil Cleanup Target Levels

N





## Florida Department of Environmental Protection

Bob Martinez Center 2600 Blair Stone Road Tallahassee, Florida 32399-2400 Charlie Crist Governor

Jeff Kottkamp Lt. Governor

Michael W. Sole Secretary

August 1, 2008

#### CERTIFIED MAIL #7008 0150 0001 8479 8781 RETURN RECEIPT REQUESTED

Mr. Harry O. Maines Sarasota Yacht Club 1100 John Ringling Boulevard Sarasota, FL 34236

Date \_\_\_\_\_

Subject: <u>Site Rehabilitation Completion Order</u> Sarasota Yacht Club 1100 John Ringling Blvd Sarasota, Sarasota County FDEP Facility ID# 588516507 Discharge Date: October 11, 2002 (Non-program)

Dear Mr. Maines:

Sarasota County Air Quality/Storage Tank Management has reviewed the Site Rehabilitation Completion Report (SRCR) and No Further Action Proposal (NFAP) dated May 19, 2008 (received May 20, 2008), prepared and submitted by Florida Geotechnical Engineering, Inc., for the petroleum product discharge referenced above. Documentation submitted with the SRCR/NFAP confirms that criteria set forth in Subsection 62-770.680(1), Florida Administrative Code (F.A.C.), have been met. Please refer to the attached maps of the source property and analytical summary tables. The SRCR/NFAP is hereby incorporated by reference in this Site Rehabilitation Completion Order (SRCO). Therefore, you are released from any further obligation to conduct site rehabilitation at the facility for petroleum product contamination associated with the discharge referenced above, except as set forth below.

- (1) In the event concentrations of petroleum products' contaminants of concern increase above the levels approved in this Order, or if a subsequent discharge of petroleum or petroleum product occurs at the facility, the Florida Department of Environmental Protection (Department) may require site rehabilitation to reduce concentrations of petroleum products' contaminants of concern to the levels approved in the SRCR/NFAP or otherwise allowed by Chapter 62-770, F.A.C.
- (2) Additionally, you are required to properly abandon all monitoring wells within 60 days of receipt of this Order. The monitoring wells must be plugged and abandoned in accordance with the requirements of Subsection 62-532.500(4), F.A.C.

Mr. Harry O. Maines FDEP Facility ID# 588516507 August 1, 2008 Page two

#### Legal Issues

The Department's Order shall become final unless a timely petition for an administrative hearing is filed under Sections 120.569 and 120.57, Florida Statutes (F.S.), within 21 days of receipt of this Order. The procedures for petitioning for an administrative hearing are set forth below.

Persons affected by this Order have the following options:

- (A) If you choose to accept the Department's decision regarding the SRCR/NFAP you do not have to do anything. This Order is final and effective as of the date on the top of the first page of this Order.
- (B) If you choose to challenge the decision, you may do the following:
- (1) File a request for an extension of time to file a petition for an administrative hearing with the Department's Agency Clerk in the Office of General Counsel within 21 days of receipt of this Order; such a request should be made if you wish to meet with the Department in an attempt to informally resolve any disputes without first filing a petition for an administrative hearing; or
- (2) File a petition for an administrative hearing with the Department's Agency Clerk in the Office of General Counsel within 21 days of receipt of this Order.

Please be advised that mediation of this decision pursuant to Section 120.573, F.S., is not available.

#### How to Request an Extension of Time to File a Petition for an Administrative Hearing

For good cause shown, pursuant to Subsection 62-110.106(4), F.A.C., the Department may grant a request for an extension of time to file a petition for an administrative hearing. Such a request must be filed (received) by the Department's Agency Clerk in the Office of General Counsel at 3900 Commonwealth Boulevard, Mail Station 35, Tallahassee, Florida, 32399-3000, within 21 days of receipt of this Order. Petitioner, if different from Sarasota Yacht Club, shall mail a copy of the request to Sarasota Yacht Club at the time of filing. Timely filing a request for an extension of time tolls the time period within which a petition for an administrative hearing must be made.

#### How to File a Petition for an Administrative Hearing

A person whose substantial interests are affected by this Order may petition for an administrative hearing under Sections 120.569 and 120.57, F.S. The petition must contain the information set forth below and must be filed (received) by the Department's Agency Clerk in the Office of General Counsel at 3900 Commonwealth Boulevard, Mail Station 35, Tallahassee, Florida, 32399-3000, within 21 days of receipt of this Order. Petitioner, if different from Sarasota Yacht Club, shall mail a copy of the petition to Sarasota Yacht Club at the time of filing. Failure to file a petition within this time period shall waive the right of anyone who may request an administrative hearing under Sections 120.569 and 120.57, F.S.

#### Mr. Harry O. Maines FDEP Facility ID# 588516507 August 1, 2008 Page three

Pursuant to Subsection 120.569(2), F.S. and Rule 28-106.201, F.A.C., a petition for an administrative hearing shall contain the following information:

- (a) The name, address, and telephone number of each petitioner; the name, address, and telephone number of the petitioner's representative, if any; the facility owner's name and address, if different from the petitioner; the FDEP facility number, and the name and address of the facility;
- (b) A statement of when and how each petitioner received notice of the Department's action or proposed action;
- (c) An explanation of how each petitioner's substantial interests are or will be affected by the Department's action or proposed action;
- (d) A statement of the disputed issues of material fact, or a statement that there are no disputed facts;
- (e) A statement of the ultimate facts alleged, including a statement of the specific facts the petitioner contends warrant reversal or modification of the Department's action or proposed action;
- (f) A statement of the specific rules or statutes the petitioner contends require reversal or modification of the Department's action or proposed action; and
- (g) A statement of the relief sought by the petitioner, stating precisely the action petitioner wishes the Department to take with respect to the Department's action or proposed action.

This Order is final and effective as of the date on the top of the first page of this Order. Timely filing a petition for an administrative hearing postpones the date this Order takes effect until the Department issues either a final order pursuant to an administrative hearing or an Order Responding to Supplemental Information provided to the Department pursuant to meetings with the Department.

#### Judicial Review

Any party to this Order has the right to seek judicial review of it under Section 120.68, F.S., by filing a notice of appeal under Rule 9.110 of the Florida Rules of Appellate Procedure with the Department's Agency Clerk in the Office of General Counsel at 3900 Commonwealth Boulevard, Mail Station 35, Tallahassee, Florida, 32399-3000, and by filing a copy of the notice of appeal accompanied by the applicable filing fees with the appropriate district court of appeal. The notice of appeal must be filed within 30 days after this Order is filed with the Department's clerk (see below).

#### Questions

Any questions regarding Sarasota County Air Quality/Storage Tank Management's review of your SRCR/NFAP should be directed to Donald H. Simpson at (941) 861-6229. Questions regarding legal issues should be referred to the Department's Office of General Counsel at (850) 245-2242. Contact with any of the above does not constitute a petition for an administrative hearing or a request for an extension of time to file a petition for an administrative hearing.

Mr. Harry O. Maines FDEP Facility ID# 588516507 August 1, 2008 Page four

The FDEP Facility Number for this facility is 588516507. Please use this identification on all future correspondence with the Department or Sarasota County Air Quality/Storage Tank Management.

Sincerely. Michael E. Ashey, Chief Bureau of Petroleum Storage Systems

MEA/dhs

Attachments

cc: Laurel Culbreth, FDEP Southwest District Office Donald H. Simpson, Sarasota County Air Quality/Storage Tank Management Christian Gunn, Florida Geotechnical Engineering, Inc. P.O. Box 76006, Tampa, FL. 33675-1006

Marc Swartz, Department of Health, Sarasota County File

FILING AND ACKNOWLEDGMENT FILED, on this date, pursuant to §120.52 Florida Statutes, with the designated Department Clerk, receipt of which is hereby acknowledged.

Clerk (or Deputy Clerk)

8-1-2008

Date

#### P.E. CERTIFICATION

Site Rehabilitation Completion Report/No Further Action Proposal dated May 19, 2008 (received May 20, 2008), for Sarasota Yacht Club, located at 1100 John Ringling Blvd., Sarasota, FL, DEP Facility ID #588516507.


I hereby certify that in my professional judgment, the components of this Site Rehabilitation Completion Report/No Further Action Proposal prepared for the October 11, 2002 petroleum product discharge discovered at the above-referenced facility satisfy the requirements set forth in Chapter 62-770, Florida Administrative Code (F.A.C.), and that the conclusions in this report on the effectiveness of the remedial action which has been conducted (confirmed by subsequent Natural Attenuation Monitoring) provide reasonable assurances that the site rehabilitation objectives stated in Chapter 62-770, F.A.C., have been met.

\_\_\_\_ I personally completed this review.

X This review was conducted by Donald H. Simpson, Environmental Specialist III, working under my direct supervision.



RAP08.249



E.


1

je-

and the

and the second second

No. of the local division of the local divis



#### **Facility Information:**

Facility ID:	8516507	County: SARASOTA	Inspection Date: 04/12/2018
Facility Type:	V - Marine/Coastal Fuel		a calvarous a construction we be a set
Facility Name:	SARASOTA YACHT CLUB		# of Inspected ASTs: 0
	1100 JOHN RINGLING BLVD		USTs: 1
	SARASOTA, FL 34236		Mineral Acid Tanks: 0
Latitude:	27° 19' 19.567"		
Longitude:	82° 34' 6.2878"		
LL Method:	DPHO		

#### **Inspection Result:**

Result: In Compliance

#### Signatures:

TKSRPC - SARASOTA COUNTY AIR QUALITY/STORAGE TANK MGMT (941) 861-0814

#### Storage Tank Program Office and Phone Number

Maggie A Murphy

Will Stocke

**Inspector Name** 

Representative Name

Mmp

No Signature

**Representative Signature** 

Inspector Signature Principal Inspector SARASOTA COUNTY AIR QUALITY/STORAGE TANK MGMT

Owners of UST facilities are reminded that the Federal Energy Policy Act of 2005 and 40 CFR 280 Subpart J, requires Operator Training at all facilities by October 13, 2018. For further information please visit: https://floridadep.gov/waste/permitting-compliance-assistance/content/underground-storage-tank-operator-training

#### Financial Responsibility:

Financial Responsibility:	INSURANCE		
Insurance Carrier:	COMMERCE & INDUSTRY		
Effective Date:	03/03/2017	Expiration Date:	03/03/2019

#### Findings:

No training certificates are present.

#### **Completed System Tests**

Туре	Date Completed	Results	Reviewed	Next Due Date	Comment
Annual Operability Test	04/12/2018	Passed	04/26/2018	04/12/2019	
Annual Inline Leak Detector Test	07/01/2015	Passed	04/07/2016	07/01/2016	MLLD testing
Annual Inline Leak Detector Test	04/12/2018	Passed	04/24/2018	04/12/2019	MLLD
Annual Inline Leak Detector Test	03/07/2016	Passed	04/07/2016	03/07/2017	MLLD Testing

#### **Reviewed Records**

Record Category	Record Type	From Date	To Date	Reviewed Record Comment
Two Years	Monthly Maint. Visual Examinations and Results	04/06/2016	04/12/2018	
Two Years	Repair, Operation and Maintenance Records	04/06/2016	04/12/2018	

#### Site Visit Comments

04/12/2018

Inspection Date: 4/12/2018

By: Maggie Murphy of Sarasota county accompanied by Will Stocke.

Inspection Covers: One (1) registered in service underground storage tanks (USTs).

• Tank #6 –12000 gallons –two compartments- Diesel on dockside- regular on club house side.

• Vent risers and caps presented as unremarkable.

**Overfill Protection:** 

- Positive Shut off valves in drop tubes
- Drop tubes at the Fill risers appeared to be satisfactory.
- The fill ports were properly marked at the time of the inspection.
- The fill cap gaskets all presented in good condition.

Facility ID: 8516507

• The spill buckets appeared to be intact with no visible breaches or tears.

• Integrity test on spill buckets performed on 4/12/2018 by petroleum technicians, passed. PIPING/SUMPS: pressurized system, with double-walled, fiberglass underground STP system.

- The piping is equipped with mechanical line leak detectors.
- Line leak detector test performed by Petroleum Technicians on 4/12/2018 passed
- All visible piping under dock presented in good condition.
- Both STP sumps were dry, pump and components had minimal corrosion.
- Transition sump was dry and had minimal corrosion (next to dock master office).

• STP and Piping sump integrity test performed by Petroleum Technicians on 4/12/2018 passed.

**DISPENSERS:** 

- One dock dispenser presented as unremarkable with a dry liner.
- Shear valves all properly anchored and secured.
- All fuel hoses, nozzles and break-away fittings presented as generally unremarkable.
- NO latch open devises on nozzles.
- Dispenser pan hydro test performed by Petroleum Technicians on 4/12/2018 passed.

Release Detection: The release detection method for the facility's UST system is visual monitoring for the interstice of UST including both STP Sumps, Dispenser liner, transition sump, and the double-wall spill buckets.

• Visual Maintenance logs and all relevant work orders and test. Reviewed 3/01/2016 to 4/12/2018 and found them to be complete and accurate.

Additional Records Reviewed:

• Placard: Current placard on display Dates: 2017 – 2018.

Insurance Commerce and Industry 3/3/2016-3/3/2019.

Unable to capture signature copy of report provided via email to Will Stocke will. stocke@sarasotayachtclub.org

#### Inspection Photos

Added Date 04/25/2018

Added Date 04/25/2018

tank field







 Facility ID:
 8516507

 Added Date
 04/25/2018

### dispenser



Added Date 04/25/2018

sump stp





Florida	Department	of	Environmental	Regulation

Twin Towers Office Bldg. • 2600 Blair Stone Road • Tallahassee, Florida 32399-2400

JEH FOR	Underground Storage Tack Installation I
form 1 de	Removal Form for Certified Contractors
	Date December 10, 1990   Ling
	the second reaction of the first start of
DER ADD	Cation No
	(17) 14 S VAFHedun by DERL

17.701 000001

## Underground Storage Tank Installation and Removal Form For Certified Contractors

Pollutant Storage System Specialty Contractors as defined in Section 489.113, Florida Statutes (Certified contractors as defined in Section 17-761.200 Florida Administrative Code) shall use this form to certify that the installation, replacement or removal of the storage tank system(s) located at the address listed below was performed in accordance with Department Reference Standards.

#### General Facility Information

1.	DER Facility Identification No.: 58/95000 95	
2.	Facility Name: PLYMOUTH HARBOR	
З.	Street Address (physical location): JOU JOHN RINGLING !	Soulolaps
	SARASOTA FC 34236	

4. Owner Name: PLY MULTH HARBAR JUC Telephone: (941) 361-7514 5. Owner Address:

6. Number of Tanks: a. Installed at this time 1 AST b. ABMUDDATED

- 7. Tank(s) Manufactured by: \_\_\_\_\_\_ UNKNOWN
- 8. Date Work Initiated: \_\_\_\_\_\_ 5-1-97\_\_\_\_\_\_ 9. Date Work Completed: \_\_\_\_\_

#### Underground Pollutant Tank Installation Checklist

Please certify the completion of the Yollowing installation requirements by placing an (X) in the appropriate box.

- 1. The tanks and piping are corrosion resistant and approved for use by State and Federal Laws.
- 2. Excavation, backfill and compaction completed in accordance with NFPA (National Fire Protection Association) 30(87), API (American Petroleum Institute) 1615, PEI (Petroleum Equipment Institute) RP100-87 and the manufacturers' specifications.
- Tanks and piping pretested and installed in accordance with NFPA 30(87), API 1615, PEI/RP100(87) and the manufacturers' specifications.
- 4. Steel tanks and piping are cathodically protected in accordance with NFPA 30(87), API 1632, UL (Underwriters Laboratory) 1746, STI (Steel Tank Institute) R892-89 and the manufacture 's specifications.
- 5. Tanks and piping tested for tightness after installation in accordance with NFPA 30(87) and PEI/RP100-87.
- 6. Monitoring well(s) or other leak detection devices installed and tested in accordance with Section 17-761.640, Florida Administrative Code (F.A.C.)
- 7. Spill and overfill protection devices installed in accordance with Section 17-761.500, F.A.C.
- 8. Secondary containment installed for tanks and piping as applicable in accordance with Section 17-761.500, F.A.C.

Please Note: The numbers following the abbreviations (e.g. API 1615) are publication or specification numbers issued by these instututions

#### Underground Pollutant Tank Removal Checklist

- 1. Closure assessment performed in accordance with Section 17-761.800, F.A.C.
- 2. Underground tank removed and disposed of as specified in API 1604 in acordance with Section 17-761.800, F.A.C. N/12-


17-781.900(5) woround Storage oval Form to: Cer Tank Instantat December 10, 1990 Date DER Application No. (Fried in by DER)

## Certification

I hereby certify and attest that I am familiar with the facility that is registered with the Florida Department of Environmental Regulation; that to the best of my knowledge and belief, the tank installation, replacement or removal at this facility was conducted in accordance with Chapter 489 and Section 376:303, Florida Statutes and Chapter 17-761, Florida Administrative Code (and its adopted reference sources from publications and standards of the National Fire Protection Association (NFPA), the American Petroleum Institute (API), the National Association of Corrosion Engineers (NACE), American Society for Testing and Materials (ASTM); Petroleum Equipment Institute (PEI); Steel Tank Institute (STI); Underwriters Laboratory (UL); and the tank and integral piping manufacturers' specifications; and that the operations on the checklist were performed accordingly.

JACK H, EUBANK 051757 (Type or Print) Certified Pollutant Tank Contractor Name PSSSC Number Pollutant Storage System Specialty Contractor License Number (PSSSC) 50/0 Date Certified Tank Contractor Signature (Type or Print) Field Supervisor Name Date Field Supervisor Signature Date

The owner or operator of the facility must register the tanks with the Department at least 10 days before the installation. The installer must submit this form no more than 30 days after the completion of installation to the Department of Environmental Regulation at the address printed at the top of page one.



#### **Facility Information:**

Facility ID:	9500095	County:	SARASOTA	Inspection Date: 07/02/2010
Facility Type:	C -Fuel user/Nor	-retail		
Facility Name:	PLYMOUTH HAI	RBOR INC		# Of Inspected ASTs: 1
	700 JOHN RINGLING BLVD			USTs: 0
	SARASOTA, FL	34236		Mineral Acid Tanks: 0
Latitude:	27° 19' 14.0108"			
Longitude:	82° 34' 11.1041"			
LL Method:	AGPS			
Inspection Res	ult:			
Result :	In Compliance			
Description:	Facility is In Co	mpliance.		

Financial Responsibility:	INSURANCE	
Insurance Carrier:	COMMERCE &	INDUSTRY
Effective Date:	11/21/2009	Expiration Date: 11/21/2010

#### Signatures:

TKSRPC - SARASOTA COUNTY AIR QUALITY/STORAGE TANK MGT

#### Storage Tank Program Office

(941) 861-6230

#### Storage Tank Program Office Phone Number

Kenneth Wall
INSPECTOR NAME

Rick Battaglia
REPRESENTATIVE NAME

Kinnih Wall

Reette

INSPECTOR	SIGNATURE
-----------	-----------

#### REPRESENTATIVE SIGNATURE

**Reviewed Records** 

Facility ID: 9500095

#### **Reviewed Records**

Record Categ	ory Record Type	From Date	To Date	Reviewed Record Comment
Two Years	Repair, Operation and Maintenance Records	12/18/2008	07/02/2010	
Life Time	Written Release Detection Response Level Info	07/02/2010	07/02/2010	
Two Years	Certificate of Financial Responsiblity	11/21/2009	11/21/2010	
Two Years	Monthly Maint. Visual Examinations and Results	12/18/2008	07/02/2010	

#### Site Visit Comments

#### 07/02/2010

Release detection methods for the facility's AST system are outlined on the RDRL, and the RDRL is attached to the Facility Information.

Current tank registration placard is on site.

CFR was completed during the inspection.

Monthly release detection check records for the AST system for January 2009 through June 2010 are satisfactory and well organized.

The 3,000-gallon double-wall steel UL-142 AST is in good condition.

Above ground steel supply and return product piping, between the AST and the transfer pump located on the ground floor, are satisfactory.

A mechanical antisiphon valve is installed on the supply product line at the AST. Block valves are installed on the product lines at the AST.

The steel spill container is satisfactory, and the spill container is marked to identify the product stored in the tank (a lock is installed on the spill container).

The Kruger level gauge appears to be OK.



#### **Facility Information:**

Facility ID:9500095County: SARASOTAFacility Type:C - Fuel user/Non-retailFacility Name:PLYMOUTH HARBOR ON SARASOTA BAY<br/>700 JOHN RINGLING BLVD<br/>SARASOTA, FL 34236-1542Latitude:27° 19' 14.6347"Longitude:82° 34' 13.2444"LL Method:DPHO

Inspection Date: 09/26/2018

# of Inspected ASTs: 1 USTs: 0 Mineral Acid Tanks: 0

#### **Inspection Result:**

Result: In Compliance

#### Signatures:

TKSRPC - SARASOTA COUNTY AIR QUALITY/STORAGE TANK MGMT (941) 861-0814

#### Storage Tank Program Office and Phone Number

Maggie A Murphy Marty Martel **Inspector Name Representative Name** No Signature **Inspector Signature Representative Signature Principal Inspector** SARASOTA COUNTY AIR QUALITY/STORAGE **Plymouth Harbor** TANK MGMT Jeremy Randall Keith Floyd **Representative Name Representative Name** No Signature No Signature **Representative Signature Representative Signature Power Secure Power Secure** 

#### Facility ID: 9500095

Owners of UST facilities are reminded that the Federal Energy Policy Act of 2005 and 40 CFR 280 Subpart J, requires Operator Training at all facilities by October 13, 2018. For further information please visit: https://floridadep.gov/waste/permitting-compliance-assistance/content/underground-storage-tank-operator-training

#### Financial Responsibility:

Financial Responsibility:	INSURANCE		
Insurance Carrier:	COMMERCE & INDUSTRY		
Effective Date:	11/21/2018	Expiration Date:	11/21/2019

#### **Completed System Tests**

Туре	Date Completed	Results	Reviewed	Next Due Date	Comment
Breach of Integrity Test	10/25/2018	Passed	12/17/2018	10/25/2018	secondairy containment integrity test crompco
Annual Operability Test	11/28/2018	Passed	12/17/2018	11/28/2019	overfill and leak detection alarms.

#### **Site Visit Comments**

#### 09/20/2018

#### 09/20/2018

> Received notification from Marty Martel that Power Secure had installed a new tank at the site that will replace the current 3000-gallon tank. The tank is an 8000-gal UL 2085 and is currently at the site and installed into the system. I visited the site immediately to observe the changes and advise the representatives of the needed test. The old tank (3000 gallon had been relocated to the lower cement slab with no evidence of any leaks.) Sludge masters filtered and transferred 2600 gallons of fuel from the old tank into the new tank. The new tank was utilizing the existing steel piping with mechanical anti siphon valve

#### 09/27/2018

9/27/2018 Received an email from Adam Daniel with information regarding the new tank not limited to insurance policy placard tank specs and EQ #s would meet at site next day to go over what is needed next.

#### 09/28/2018

9/28/2018 Met with representative of Powersecure to go over needed test to be performed on the newly installed tank.; The following tank and components were present and have corresponding EQ #'s if applicable; Tank Envirosafe 8,000-gallon tank: EQ-239

TMS300 Pneumercator: EQ-303

Facility ID: 9500095

Krueger Leak Gauge: EQ-675 Morrison Clock Gauge ( with alarm and STD. float) 918: EQ-861 Overfill Protection Valve: EQ-851. On top of tank aluminum overspill bucket Two Emergency vents One stack vent One Manway

11/25/2018

Jim Sullivan of Crompco performed integrity test on the tank 10/25/2018. The secondary containment test on the tank outer wall (sub basin) passed.

Test was two hour Hg test that was stated at 1:38 with starting pressure at 6 and completed at 3:39 with ending pressure at 6. I was unable to witness the test and certified results were provided to me by email.

11/28/2018

Met with Jeremy Randall and Keith Floyd of Power secure on 11/28/2018 to see that overfill alarm and leak detection alarm worked properly. The sensors both alarmed on the Pneumercator which was located on the wall of the garage next to tank. This date would be used as the last annual test performed

#### Attachment Documents

- integrity test
- manifest for fuel transfer

#### **Inspection Photos**

Added Date 12/17/2018

end of new tank




Added Date 12/17/2018

New tank with all components



Facility ID: 9500095 Added Date 12/17/2018

## piping



Added Date 12/17/2018

pneumercator tms 3000



	0	C	)		-
1	rida Department of Enu owers Office Bldg.			Transfords)	
****		fied Contractors		al Por	n Control Asida 11110168
orida Administrative Coo	specialty Contractors as defined in Section de) shall use this form to certify that the www.was performed in accordance with	e installation, replacement or ren	noval of the stora		
eneral Facility Inf	formation		REG	TOR	n D D D
. DER Facility Identifica	ation No.: N/A 58940	1473		m.	mm.
	243 Robin Drive HARA		e: ( <u>708</u> ) <u>61</u>	<u>5-0200</u>	
		sota, Florida 34236	÷	ē	
. Owner Name:	Mr. David Harris		ne: (708 ) 61	5-0200	
	190 Ahwahnee Road, Lake				
Number of Tanks:	a. Installed at this time		7.4 ····	Ф.	
. Tank(s) Manufactured	t by:N/A				
B. Date Work Initiated: _	5 /3 0 / 0 /	9. Date Work Completed:	5/19/94		
ease certify the complet . The tanks and piping 2. Excavation, backfill ar	tant Tank Installation Checkl tion of the following installation require are corrosion resistant and approved and compaction completed in accordan	ments by placing an (X) in the ap for use by State and Federal La nce with NFPA (National Fire Pro	ws.	on) 30(87), A	[ API [
	Institute) 1615, PEI (Petroleum Equipn tested and installed in accordance wit		e.		
. Steel tanks and piping	g are cathodically protected in accord Institute) R892-89 and the manufactur	ance with NFPA 30(87), API 163: er's specifications.	2, UL (Underwrit	ers Laborate	ory) [
Tanks and piping test	ted for tightness after installation in acc	cordance with NFPA 30(87) and	PEI/RP100-87.		[
	other leak detection devices installed a	and tested in accordance with Se	ection 17-761.640,	Florida	[
Monitoring well(s) or of Administrative Code (I	other leak detection devices installed a F.A.C.) ection devices installed in accordance		ection 17-761.640,	Florida	[
Monitoring well(s) or of Administrative Code (I Spill and overfill prote	(F.A.C.)	with Section 17-761.500, F.A.C.		1	[ [
Monitoring well(s) or of Administrative Code (I Spill and overfill prote Secondary containme	F.A.C.) ection devices installed in accordance	with Section 17-761.500, F.A.C.	tion 17-761.500; f	AC.	[ [ e instutution
Monitoring well(s) or of Administrative Code (I Spill and overfill prote Secondary containme case Note: The numbe	F.A.C.) ection devices installed in accordance	with Section 17-761,500, F.A.C. oplicable in accordance with Sec 1615) are publication or specifica	tion 17-761.500; f	AC.	[ [ e instututior
Monitoring well(s) or of Administrative Code (l Spill and overfill prote Secondary containme ease Note: The numbe nderground Pollut	F.A.C.) ection devices installed in accordance ent installed for tanks and piping as ap ers following the abbreviations (e.g. API	with Section 17-761,500, F.A.C. oplicable in accordance with Sect 1615) are publication or specifica	tion 17-761.500; f	AC.	[ [ e instutution [

÷

.

ł

.

	0	· · · · ·	$\bigcirc$	an a
A STANDARD CONTRACTOR	- 7	and the second second	1. 4 ×	DER Form e 17-761.800(5) Underground Storage Tank Installation & Form Tela Removal Form for Certified Contractors
HAY 1894			•	DER Application No
Division	x*	Certification		× • •

なる

I hereby certify and attest that I am familiar with the facility that is registered with the Florida Department of Environmental Regulation; that to the best of my knowledge and belief, the tank installation, replacement or removal at this facility was conducted in accordance with Chapter 489 and Section 376303, Florida Statutes and Chapter 17-761, Florida Administrative Code (and its adopted reference sources from publications and standards of the National Fire Protection Association (NFPA), the American Petroleum Institute (API), the National Association of Corrosion Engineers (NACE), American Society for Testing and Materials (ASTM); Petroleum Equipment Institute (PEI); Steel Tank Institute (STI); Underwriters Laboratory (UL); and the tank and integral piping manufacturers' specifications; and that the operations on the checklist were performed accordingly. 1.

.

1

James Nuwer II	PCC 048381
(Type or Print) Certified Pollutant Tank Contractor Name Pollutant Storage System Specialty Centractor License Number (PSSSC)	PSSSC Number
Gentilted Tank Contractor Signature	5/19/94
James Nuwer H	Date 5/19/94
(fype or Print) Field Supervisor Name	Date
Field Supervisor Signature	5/19/94 Date
A C	

The owner or generator of the facility must register the tanks with the Department at least 10 days before the installation. The installer must submit this form no more than 30 days after the completion of installation to the Department of Environmental Regulation at the address printed at the top of page one. 1.00

water of a

en la serve des e

Section 1 -

Street. A lateration

a. \* . . . .

5. gri.

Acres 1 . .

5 - 10 1

Pag. 14

	DUNKELBERGER ENGINEERING & TESTING, INC.
	Geötechnical • Materials Testing/Inspection • Environmental
Sarasota C	County Department of Environmental Services May 22, 2006
And Natur	O Doomerse
2817 Cattl	emen Road Project No. SAR-05-352
	Florida 34232
and the second	SARASOTA COUNTY AIR QUALITY
1 2. J.	MAX 2 4 2000
Attention:	Susan Murray MAY 2 4 2006
0 10 10 44	Environmental Specialist III STORAGE TANK MGMT.
 2	
···	
Subject:	Soil and Groundwater Analysis
len i star	243 Robin Drive
1.1.1.1.1.1	DEP Facility #589401473
· · · · · · · · · · · · · · · · · · ·	Sarasota, Florida
	Sal asola, Tiorida
Deer C	
Dear Susan	
1. 1. M	
m	
	s to address the comments stated in your letter dated February 17, 2006

#### Comment #1

The site map provided with our initial report date December 20, 2005 is correct. The former tank location and excavation area were discussed with Mr. Wilkening, who was present during the initial excavation. Construction plans for the current residence were viewed and discussed with Mr. Wilkening to judge the excavation area placement with respect to the former and current structures on-site. The site plan provided by Environmental Science and Engineering places the excavation area off the Wilkening property and is in error with respect to the direction of north. Please refer to Attachment A for details.

#### Comment #2

The soil and groundwater sample location is outside of the former tank excavation area, within 2 to 3 feet to the northwest. Please refer to Attachment A for details.

#### Comment #3

A copy of the chain of custody is included as Attachment B.

#### Comment #4

A certification page for the document dated December 20, 2005 is included as Attachment C.

#### \_000

8260 Vico Court, Unit B • Sarasota, Florida 34240 Phone (941) 379-0621 • Fax (941) 379-5061 State of Florida Board of Professional Engineers Authorization No 6870 Very truly yours,

**DUNKELBERGER ENGINEERING & TESTING, INC.** 

Ian Hanson, E.I.

Staff Engineer



Attachment A:

Attachment B:


SE Site plan showing corrected north area and December 7 sample location Chain of custody for December 7, 2005 soil samples and the December 9, 2005 groundwater samples.

Attachment C:

Professional Engineer's Statement for document dated December 20, 2005

Cc: Kurt Wilkening





FDEP Storage Tank Inspection Cover Page for: 9401473

#### Florida Department of Environmental Protection Bureau of Petroleum Storage Systems Facility Inspection Cover Page Facility Information

District: SD County: Sarasota Facility ID#: 9401473 Name: Harris Residence 243 Robin Dr Sarasota, FL 34236 Contact:

Phone: 708-615-0200

Account Owner Information Name: Harris, David 190 Ahwahnee Rd Lake Forest, IL 60045 Phone: 708-615-0200

Tank Owner Information Name: Harris, David 190 Ahwahnee Rd Lake Forest, IL 60045 Phone: 708-615-0200 Type: Residential Status: Closed Latitude: 27:19:25.3519 Longitude: 82:33:35.2037 LL Method: DPHO LL Status: REVIEWED Status Date: 07//07/2008

> Effective Date: 08/18/1994 Placard#/Date: -

> > Effective Date: 08/18/1994

Tank #	Size	Content	Installed	Placement	Status	Const	Pipe	Monitor
1	300	Fuel Oil - Onsite Heat		UNDER	В			

\*\*\*Note: Construction, Piping, and Monitoring Info not shown for CLOSED tanks (Status of A or B).

#### No Insurance Documents found!

No OPEN violations found!

**Discharge Information** 

Discharge Date	Cleanup Status	Score	Eligibility Info	Site Manager	Phone
05/19/1994	Completed	9	<u>م</u>	Murray_S	(941)861-0605

End of Data for Facility #: 9401473

mhtml:file://S:\PROJECTS\14100 Projects\14103 SR 789 Little Ringling Bridge\C ... 1/27/2020

Page 1 of 1

# CSER APPENDIX C

## **Little Ringling Bridge**

SR 789 Bird Key Dr to Sarasota Harbor West Sarasota, FL 34236

Inquiry Number: 5931196.5 January 13, 2020

## The EDR Aerial Photo Decade Package



6 Armstrong Road, 4th floor Shelton, CT 06484 Toll Free: 800.352.0050 www.edrnet.com

## EDR Aerial Photo Decade Package

#### Site Name:

#### Client Name:

01/13/20

Little Ringling Bridge SR 789 Bird Key Dr to Sarasota Sarasota, FL 34236 EDR Inquiry # 5931196.5

#### Madrid Engineering Group, Inc. 2030 State Road 60 East Bartow, FL 33830 Contact: Scott Nyhof



Environmental Data Resources, Inc. (EDR) Aerial Photo Decade Package is a screening tool designed to assist environmental professionals in evaluating potential liability on a target property resulting from past activities. EDR's professional researchers provide digitally reproduced historical aerial photographs, and when available, provide one photo per decade.

Search Results:				
Year	Scale	Details	Source	
2017	1"=500'	Flight Year: 2017	USDA/NAIP	
2013	1"=500'	Flight Year: 2013	USDA/NAIP	
2010	1"=500'	Flight Year: 2010	USDA/NAIP	
2007	1"=500'	Flight Year: 2007	USDA/NAIP	
1998	1"=500'	Acquisition Date: December 31, 1998	USGS/DOQQ	
1985	1"=500'	Flight Date: December 20, 1985	FDOT	
1979	1"=500'	Flight Date: January 15, 1979	USGS	
1971	1"=500'	Flight Date: December 31, 1971	USGS	
1969	1"=500'	Flight Date: November 06, 1969	USGS	
1962	1"=500'	Flight Date: March 28, 1962	USGS	
1957	1"=500'	Flight Date: March 23, 1957	USDA	
1948	1"=500'	Flight Date: February 02, 1948	USDA	


When delivered electronically by EDR, the aerial photo images included with this report are for ONE TIME USE ONLY. Further reproduction of these aerial photo images is prohibited without permission from EDR. For more information contact your EDR Account Executive.


#### **Disclaimer - Copyright and Trademark Notice**


This Report contains certain information obtained from a variety of public and other sources reasonably available to Environmental Data Resources, Inc. It cannot be concluded from this Report that coverage information for the target and surrounding properties does not exist from other sources. NO WARRANTY EXPRESSED OR IMPLIED, IS MADE WHATSOEVER IN CONNECTION WITH THIS REPORT. ENVIRONMENTAL DATA RESOURCES, INC. SPECIFICALLY DISCLAIMS THE MAKING OF ANY SUCH WARRANTIES, INCLUDING WITHOUT LIMITATION, MERCHANTABILITY OR FITNESS FOR A PARTICULAR USE OR PURPOSE. ALL RISK IS ASSUMED BY THE USER. IN NO EVENT SHALL ENVIRONMENTAL DATA RESOURCES, INC. BE LIABLE TO ANYONE, WHETHER ARISING OUT OF ERRORS OR OMISSIONS, NEGLIGENCE, ACCIDENT OR ANY OTHER CAUSE, FOR ANY LOSS OF DAMAGE, INCLUDING, WITHOUT LIMITATION, SPECIAL, INCIDENTAL, CONSEQUENTIAL, OR EXEMPLARY DAMAGES. ANY LIABILITY ON THE PART OF ENVIRONMENTAL DATA RESOURCES, INC. IS STRICTLY LIMITED TO A REFUND OF THE AMOUNT PAID FOR THIS REPORT. Purchaser accepts this Report "AS IS". Any analyses, estimates, ratings, environmental risk levels or risk codes revision or prediction or forecast of, any environmental risk for any property. Only a Phase I Environmental Ste Assessment performed by an environmental professional can provide information regarding the environmental risk for any property. Additionally, the information provide in this Report is not to be construed as legal advice.

Copyright 2020 by Environmental Data Resources, Inc. All rights reserved. Reproduction in any media or format, in whole or in part, of any report or map of Environmental Data Resources, Inc., or its affiliates, is prohibited without prior written permission.


EDR and its logos (including Sanborn and Sanborn Map) are trademarks of Environmental Data Resources, Inc. or its affiliates. All other trademarks used herein are the property of their respective owners.


































# CSER APPENDIX D

Little Ringling Bridge SR 789 Bird Key Dr to Sarasota Harbor West Sarasota, FL 34236

Inquiry Number: 5931196.3 January 13, 2020

### **Certified Sanborn® Map Report**



6 Armstrong Road, 4th floor Shelton, CT 06484 Toll Free: 800.352.0050 www.edrnet.com

#### Certified Sanborn® Map Report

#### Site Name:

Little Ringling Bridge SR 789 Bird Key Dr to Sarasota Sarasota, FL 34236 EDR Inquiry # 5931196.3

#### Client Name:

Madrid Engineering Group, Inc. 2030 State Road 60 East Bartow, FL 33830 Contact: Scott Nyhof



01/13/20

The Sanborn Library has been searched by EDR and maps covering the target property location as provided by Madrid Engineering Group, Inc. were identified for the years listed below. The Sanborn Library is the largest, most complete collection of fire insurance maps. The collection includes maps from Sanborn, Bromley, Perris & Browne, Hopkins, Barlow, and others. Only Environmental Data Resources Inc. (EDR) is authorized to grant rights for commercial reproduction of maps by the Sanborn Library LLC, the copyright holder for the collection. Results can be authenticated by visiting www.edrnet.com/sanborn.

The Sanborn Library is continually enhanced with newly identified map archives. This report accesses all maps in the collection as of the day this report was generated.

#### Certified Sanborn Results:

Certification # 2ABE-48EF-A6A0

**PO #** 14103

**Project** 14103

#### **UNMAPPED PROPERTY**

This report certifies that the complete holdings of the Sanborn Library, LLC collection have been searched based on client supplied target property information, and fire insurance maps covering the target property were not found.



Sanborn® Library search results Certification #: 2ABE-48EF-A6A0

The Sanborn Library includes more than 1.2 million fire insurance maps from Sanborn, Bromley, Perris & Browne, Hopkins, Barlow and others which track historical property usage in approximately 12,000 American cities and towns. Collections searched:

	Library of	Congress
--	------------	----------



EDR Private Collection

The Sanborn Library LLC Since 1866™

#### Limited Permission To Make Copies

Madrid Engineering Group, Inc. (the client) is permitted to make up to FIVE photocopies of this Sanborn Map transmittal and each fire insurance map accompanying this report solely for the limited use of its customer. No one other than the client is authorized to make copies. Upon request made directly to an EDR Account Executive, the client may be permitted to make a limited number of additional photocopies. This permission is conditioned upon compliance by the client, its customer and their agents with EDR's copyright policy; a copy of which is available upon request.

#### **Disclaimer - Copyright and Trademark Notice**

This Report contains certain information obtained from a variety of public and other sources reasonably available to Environmental Data Resources, Inc. It cannot be concluded from this Report that coverage information for the target and surrounding properties does not exist from other sources. NO WARRANTY EXPRESSED OR IMPLIED, IS MADE WHATSOEVER IN CONNECTION WITH THIS REPORT. ENVIRONMENTAL DATA RESOURCES, INC. SPECIFICALLY DISCLAIMS THE MAKING OF ANY SUCH WARRANTIES, INCLUDING WITHOUT LIMITATION, MERCHANTABILITY OR FITNESS FOR A PARTICULAR USE OR PURPOSE. ALL RISK IS ASSUMED BY THE USER. IN NO EVENT SHALL ENVIRONMENTAL DATA RESOURCES, INC. BE LIABLE TO ANYONE, WHETHER ARISING OUT OF ERRORS OR OMISSIONS, NEGLIGENCE, ACCIDENT OR ANY OTHER CAUSE, FOR ANY LOSS OF DAMAGE, INCLUDING, WITHOUT LIMITATION, SPECIAL, INCIDENTAL, CONSEQUENTIAL, OR EXEMPLARY DAMAGES. ANY LIABILITY ON THE PART OF ENVIRONMENTAL DATA RESOURCES, INC. IS STRICTLY LIMITED TO A REFUND OF THE AMOUNT PAID FOR THIS REPORT. Purchaser accepts this Report "AS IS". Any analyses, estimates, ratings, environmental risk levels or risk codes provided in this Report are provided for illustrative purposes only, and are not intended to provide, nor should they be interpreted as providing any facts regarding, or prediction or forecast of, any environmental risk for any property. Only a Phase I Environmental Site Assessment performed by an environmental professional can provide information regarding the environmental risk for any property. Additionally, the information provided in this Report is not to be construed as legal advice.

Copyright 2020 by Environmental Data Resources, Inc. All rights reserved. Reproduction in any media or format, in whole or in part, of any report or map of Environmental Data Resources, Inc., or its affiliates, is prohibited without prior written permission.

EDR and its logos (including Sanborn and Sanborn Map) are trademarks of Environmental Data Resources, Inc. or its affiliates. All other trademarks used herein are the property of their respective owners.

# CSER APPENDIX E

## Asbestos Survey and Metals-Based Paint Coatings Sampling Report

Bridge Number 170022 (Westbound) SR 789 (Little Ringling Bridge) over Coon Key Waterway Sarasota, Sarasota County, Florida

Prepared for: Florida Department of Transportation District 1 801 North Broadway Avenue Bartow, Florida 33830

Prepared by: CB&I Environmental & Infrastructure, Inc. 1228 Winter Garden Vineland Road Winter Garden, Florida 34787

FDOT Contract BDV75 FDOT FPID 436545-1-C2-32, LOA 47 CB&I Project 154316 July 2015

#### ASBESTOS SURVEY TITLE SHEET

Facility Name:	Bridge 170022
	SR 789 (Little Ringling Bridge) Over Coon Key Waterway
Address/Location:	1.4 miles West of US 41
City, County, State:	Sarasota, Sarasota County, Florida
Owner Agency:	Florida Department of Transportation, District 1
Date of Survey:	May 12 and 13, 2015
Consultant:	CB&I Environmental & Infrastructure, Inc.
Consultant Address:	1228 Winter Garden Vineland Road
City, State, Zip Code:	Winter Garden, Florida 34787
Telephone Number:	407-287-3210 (Shawn Flynn, PG; Contract Manager)

1 July 9, 2015

David W. Mosher, PE, LAC Licensed Asbestos Consultant, EA-0000078

#### **TABLE OF CONTENTS**

#### **ACRONYMS AND ABBREVIATIONS**

- SECTION 1 SURVEY SUMMARY FORMS SURVEY OVERVIEW ASBESTOS SURVEY REPORT – FORM 1 ASBESTOS SURVEY AND ASSESSMENT – FORM 2 PERSONNEL SUMMARY – FORM 3
- SECTION 2 BRIDGE DIAGRAM(S)
- SECTION 3 PHOTOGRAPHS
- SECTION 4 LABORATORY ANALYTICAL DATA AND CHAIN OF CUSTODY FORM(S)
- SECTION 5 CREDENTIALS FOR CONSULTANT, INSPECTOR, AND LABORATORY
- SECTION 6 ASBESTOS OPERATIONS AND MAINTENANCE (O&M) PLAN AND RESPONSE ACTION
- SECTION 7 DISCLAIMER

#### METALS-BASED PAINT COATINGS SAMPLING REPORT

SECTION 8 INTRODUCTION

SAMPLE RESULTS

RECOMMENDATIONS FOR PERSONNEL HEALTH AND SAFETY

**RECOMMENDATIONS FOR MATERIAL/WASTE HANDLING, TRANSPORTATION, AND DISPOSAL** 

- FIGURES PAINT COATING SAMPLE LOCATION MAP
- ATTACHMENT A PHOTOGRAPHS
- ATTACHMENT B LABORATORY ANALYTICAL DATA AND CHAIN OF CUSTODY FORMS

#### ACRONYMS AND ABBREVIATIONS

#### **Surfacing Materials**

- SAS acoustical/sprayed surfacing material
- SAT acoustical/troweled surfacing material
- SFP fireproofing/structural

#### **Thermal Materials**

- TPI pipe insulation
- TPC pipe cover
- TPE pipe elbow/joint
- TPM pipe mastic

#### **Miscellaneous Materials**

- MAS mastic/adhesive
- MBB vinyl baseboard
- MBP bearing pad
- MCA carpet adhesive
- MCC concrete
- MCK caulk/sealant
- MCM cementitious material/patch
- MCT ceiling tile
- MDI duct insulation
- MDM duct mastic
- MEJ expansion joint
- MFD fire door
- MFT floor tile
- MGS gasket
- MJC joint compound
- MMB moisture barrier (felt)
- MPC "popcorn" textured ceiling finish
- MPL plaster
- MRM reflector mastic
- MRP railing pads
- MSI sink insulation
- MST stucco
- MSV sheet vinyl/flooring
- MTC cementitious/Transite-type conduit/pipe
- MTP cementitious/Transite-type panel
- MVD vibration damper
- MVP vibration pads
- MWB wallboard
- MWG window glazing
- MWP wallpaper/covering

#### **Roofing Materials**

- RBU built-up roofing
- RAS asphalt shingle
- RFT tarpaper and felt
- RRM rolled membrane
- RFM flashing mastic
- RTP Transite-type panel/shingle

#### **SECTION 1**

#### SURVEY SUMMARY FORMS

#### ASBESTOS SURVEY OVERVIEW

As part of transportation improvement activities, the Florida Department of Transportation (FDOT), District 1, will be performing renovations to Bridge Number 170022 (or Little Ringling Bridge, westbound) located along SR 789 over the Coon Key Waterway in Sarasota, Sarasota County, Florida, and has requested that an asbestos survey be performed to determine the presence, if any, of asbestos-containing materials (ACM). CB&I Environmental & Infrastructure Inc. (CB&I) has provided a map (Figure 1) illustrating the location of the subject bridge. Sampling locations are provided on Figure 2. Provided on FORM 1 is detailed information regarding the bridge and the asbestos survey.

In addition to the asbestos survey, the FDOT requested sampling of the bridge paint coatings with laboratory analysis for heavy metals. The metals-based paint coatings survey was performed on May 13, 2015, and the results have been incorporated in this submittal (**Section 8**) immediately following the asbestos survey.

Survey activities described below were performed in accordance with the Asbestos Hazard Emergency Response Act (AHERA) sampling protocol and comply with the National Emission Standards for Hazardous Air Pollutants (NESHAP).

The FDOT provided CB&I with the following information:

- Bridge Plans, dated 1955
- Bridge Rehabilitation Final Plans, prepared by the FDOT, dated 1986
- Bridge Rehabilitation Final Plans, prepared by the FDOT, dated 1993
- Bridge Repair Plans (60% Submittal), prepared by T.Y. Lin International, dated February 10,2015

Thomas Gregory and Daniel Roebke of CB&I performed the asbestos survey on May 12 and 13, 2015, to determine the location, extent, and condition of suspect ACM.

During the asbestos survey, random samples of the following materials were collected to determine asbestos content: concrete, mortar, asphalt paper, rubber sealer, mastic, Class 5 coating, fiberglass, and sealant (FORM 2). No suspect drains were identified on the bridge structure.

Under the AHERA definitions and sampling protocol, 22 homogenous areas (HA) were identified during this survey as miscellaneous materials (see **FORM 2**). A homogeneous area is an application of surfacing material, thermal system insulation material, or miscellaneous materials that is uniform in color, texture, and vintage of application. Miscellaneous material is defined by the United States Environmental Protection Agency (US EPA) as interior building

material on structural components, structural members, or fixtures (such as floor tiles, adhesives, and mastics) and does not include surfacing material or thermal system insulation (40 CFR Part 763.83).

Also, during the survey, the quantification and extent of each HA was estimated and the friability of the material was determined. A material is considered friable that, when dry, can be crumbled, pulverized, or reduced to a powder by hand pressure as defined by the US EPA. At a minimum, three samples of each HA were collected for analysis, as recommended by the US EPA (*100 Commonly Asked Questions About the New AHERA Asbestos-in-Schools Rule*, US EPA, May 1988) and required by CB&I protocol. Three additional samples were collected randomly for quality assurance/quality control (QA/QC) purposes. The total number of samples collected from this bridge was 70 (66 from 22 HAs and 4 QA/QC). Provided on **FORM 3** is a list of survey team (personnel and laboratories) and their appropriate license or certificate numbers.

Samples of suspect materials were submitted for asbestos analysis to an independent laboratory certified by the National Voluntary Laboratory Accreditation Program (NVLAP). Additionally, as per FDOT requirements, QA/QC samples were collected and submitted for analysis to a second NVLAP-certified laboratory. All samples were analyzed for asbestos of bulk materials by EPA Method 600/R-93/116 using Polarized Light Microscopy.

Laboratory analysis of the collected suspect samples indicated that the sampled materials did not contain asbestos. Renovation or demolition can proceed without any engineering controls. However, the use of wet demolition methods is recommended during renovation or demolition of these sampled materials.

Estimates related to the cost of abatement (including disposal) and on-site air monitoring are provided on **FORM 2** for each HA that contains asbestos. These estimates are based on our previous experience for similar abatement projects in similar locations and do not include the costs for replacement materials or labor following the abatement work. However, because no asbestos was identified, no abatement costs are noted.

#### **ASBESTOS SURVEY REPORT – FORM 1**

#### **BRIDGE IDENTIFICATION**

County:	Sarasota
Agency:	Florida Department of Transportation District 1
Bridge Names:	Little Ringling Bridge (Westbound) over Coon Key Waterway
Bridge Numbers:	170022
Address and/or Geographi	c Location: <u>Along SR 789, 1.4 Miles West of US 41</u>
Asbestos Contact Person:	Jeffrey W. James Telephone Number: <u>863-519-2625</u>
FDOT Contact:	W. James Telephone Number: <u>863-519-2625</u>

#### SURVEY IDENTIFICATION

Date of Survey:	May 12 and 13, 2015 Date of Report: July 9, 2015
Contract No.:	BDV75
FM No.:	436545-1-C2-32
Consultant's Name:	David W. Mosher, PE, LAC License No.: <u>EA-0000078</u>
Name of Firm:	CB&I Environmental & Infrastructure, Inc.
Address:	1228 Winter Garden Vineland Road, Winter Garden, Florida 34787
Telephone Number:	407-287-3210 (Shawn Flynn, PG, Contract Manager)

#### **BRIDGE INFORMATION**

Year of Construction: _	1958		
Renovation Dates:	Unknown		
Bridge Documents/Drav	wings Available/Con	nsulted:	
Types: Plans	⊠Yes □No	Location	Several pages from 1955, 1986, 1993
			and 2015 bridge plan set
Specifications	□Yes ⊠No	Location	
Other	□Yes ⊠No	Location	
Asbestos Docur	nents □Yes ⊠No	Location	
	⊠Yes □No	Location	uglybridges.com
	□Yes □No	Location	

#### STRUCTURAL DATA

Vertical Support:	Prestressed concrete piles Horizontal: Prestressed concrete
Decking:	Concrete, Cast-In-Place
Span:	21 Spans, Longest 47.9', Total Length 1,010.2' Gaskets: NA
Bearing Pads:	Noted as "Bearing Plates" Railings: Concrete
If applicable:	
Roof:	NA
Floors:	NA Ceilings: NA
Exterior Walls:	NA Partition Walls: NA
HVAC System:	$\Box$ Yes $\boxtimes$ No Type: <u>NA</u>

of Survey: N	May 12 and 13, 2015	-	stbound) – SR 789 over Coon Key Agency:	Flori	da Depa	rtment of	Contract N Transport	No.: <u>BDV</u> tation, Dist	75 trict 1
ıltant: <u> </u>	CB&I Environmental & Ir	nfrastructu	re, Inc. FDOT Contact Perso	n: Jeffre	ey W. Ja	ames	-		
Sample No. or Assumed	Material Description	Homo- geneous Area No.	Area Description	Quantity (Total for HA)	Friable Y/N	Asbestos Type & % or Assumed	Response Cost	Air Monitoring Cost	Replace Cost
1.1	CONCRETE	1	BENT COLUMNS	5600 CF	N	NAD	0	0	0
1.2	CONCRETE	1	BENT COLUMNS	5600 CF	Ν	NAD	0	0	0
1.3	CONCRETE	1	BENT COLUMNS	5600 CF	Ν	NAD	0	0	0
2.1	CONCRETE	2	BENT CAPS	4662 CF	Ν	NAD	0	0	0
2.2	CONCRETE	2	BENT CAPS	4662 CF	Ν	NAD	0	0	0
2.3	CONCRETE	2	BENT CAPS	4662 CF	Ν	NAD	0	0	0
3.1	CONCRETE	3	SEA WALLS	1540 CF	Ν	NAD	0	0	0
3.2	CONCRETE	3	SEA WALLS	1540 CF	Ν	NAD	0	0	0
3.3	CONCRETE	3	SEA WALLS	1540 CF	Ν	NAD	0	0	0
4.1	CONCRETE	4	ABUTMENT WALL	1036 CF	Ν	NAD	0	0	0
4.2	CONCRETE	4	ABUTMENT WALL	1036 CF	Ν	NAD	0	0	0
4.3	CONCRETE	4	ABUTMENT WALL	1036 CF	Ν	NAD	0	0	0
5.1	MORTAR	5	ABUTMENT WALL	11520 CF	Ν	NAD	0	0	0
5.2	MORTAR	5	ABUTMENT WALL	11520 CF	N	NAD	0	0	0
5.3	MORTAR	5	ABUTMENT WALL	11520 CF	N	NAD	0	0	0
COMMENTS/N Y – Yes N – No NA – Not Appli	Subtot	als for thi	s page	0	0	0			
NAD - No Asbestos Detected LF - Linear feetPC - Point Count Analysis PS - Analyzed to first positive stop Trace - Less than 1%cro crocidolite				Consultant Fees					
<ol> <li>All quantities given in square feet unless otherwise indicated.</li> <li>All costs provided assume one mobilization.</li> </ol>					O & M Costs				
		ntoining M-t	arial (ACM) as assumed ACM						
o. Snaded and	bold text indicates Asbestos-Co	ntaining wat	enai (ACM) or assumed ACM.		TOTAL				

# ASBESTOS SURVET AND ASSESSMENT – FORM 2 Bridge Names: 170022 (Little Ringling Bridge, Westbound) – SR 789 over Coon Key Waterway Contract No.: BDV75 Date of Survey: May 12 and 13, 2015 Agency: Florida Department of Transportation, District 1 Consultant: CB&I Environmental & Infrastructure, Inc. FDOT Contact Person: Jeffrey W. James

Sample No. or Assumed	Material Description	Homo- geneous Area No.	Area Description	Quantity (Total for HA)	Friable Y/N	Asbestos Type & % or Assumed	Response Cost	Air Monitoring Cost	Replace Cost
6.1	CONCRETE	6	END BENT PILE CAP	1230 CF	N	NAD	0	0	0
6.2	CONCRETE	6	END BENT PILE CAP	1230 CF	N	NAD	0	0	0
6.3	CONCRETE	6	END BENT PILE CAP	1230 CF	N	NAD	0	0	0
6.4 QA/QC	CONCRETE	6	END BENT	1230 CF	N	NAD	0	0	0
7.1	CONCRETE	7	DIAPHRAM	2220 CF	N	NAD	0	0	0
7.2	CONCRETE	7	DIAPHRAM	2220 CF	N	NAD	0	0	0
7.3	CONCRETE	7	DIAPHRAM	2220 CF	N	NAD	0	0	0
8.1	ASPHALT PAPER	8	SUBGIRDER BEARING PADS	400 SF	N	NAD	0	0	0
8.2	ASPHALT PAPER	8	SUBGIRDER BEARING PADS	400 SF	N	NAD	0	0	0
8.3	ASPHALT PAPER	8	SUBGIRDER BEARING PADS	400 SF	N	NAD	0	0	0
9.1	CONCRETE	9	GIRDERS	22725 CF	N	NAD	0	0	0
9.2	CONCRETE	9	GIRDERS	22725 CF	N	NAD	0	0	0
9.3	CONCRETE	9	GIRDERS	22725 CF	N	NAD	0	0	0
10.1	MORTAR	10	GIRDERS	10100 SF	N	NAD	0	0	0
10.2	MORTAR	10	GIRDERS	10100 SF	N	NAD	0	0	0
COMMENTS/NOTES:       CF – Cubic Feet       chry chrysotile         Y – Yes       CAT I – Category I       amo amosite         N – No       CAT II – Category II       trem tremolite         NA – Not Applicable       CAT II – Category II       trem tremolite					als for this	spage	0	0	0
NAD - No Asbestos Detected LF - Linear feetPC - Point Count Analysiscro crocidoliteSF - Square feetPC - Linear feetPC - Point Count Analysiscro crocidoliteSF - Square feetPC - Linear feetPC - Point Count Analysiscro crocidolite				Consultant Fees					
	es given in square feet unless other rovided assume one mobilization.	wise indicate	d.	0	& M Cost	S			
3. Shaded and bold text indicates Asbestos-Containing Material (ACM) or assumed ACM.				TOTAL					

	70022 (Little Ringling Bridge, We			-	-			t No.: <u>BD</u>	
			Agency:				of Transpo	ortation, Di	Istrict I
iltant: <u>C</u>	CB&I Environmental & Infrastruct	ure, Inc.	FDOT Contact Pers	on: <u>Jeff</u>	rey W.	James			
Sample No. or Assumed	Material Description	Homo- geneous Area No.	Area Description	Quantity (Total for HA)	Friabl e Y/N	Asbestos Type & % or Assumed	Response Cost	Air Monitoring Cost	Replace Cost
10.3	MORTAR	10	GIRDER	10100 SF	N	NAD	0	0	0
11.1	ASPHALT PAPER	11	SUBDECK BEARING PADS	5050 SF	N	NAD	0	0	0
11.2	ASPHALT PAPER	11	SUBDECK BEARING PADS	5050 SF	N	NAD	0	0	0
11.3	ASPHALT PAPER	11	SUBDECK BEARING PADS	5050 SF	N	NAD	0	0	0
12.1	RUBBER SEALER	12	EXPANSION JOINTS	814 LF	N	NAD	0	0	0
12.2	RUBBER SEALER	12	EXPANSION JOINTS	814 LF	N	NAD	0	0	0
12.3	RUBBER SEALER	12	EXPANSION JOINTS	814 LF	N	NAD	0	0	0
12.4 QA/QC	RUBBER SEALER	12	EXPANSION JOINTS	814 LF	Ν	NAD	0	0	0
13.1	CONCRETE	13	RAILING – RAIL	2273 CF	N	NAD	0	0	0
13.2	CONCRETE	13	RAILING – RAIL	2273 CF	N	NAD	0	0	0
13.3	CONCRETE	13	RAILING – RAIL	2273 CF	Ν	NAD	0	0	0
14.1	CONCRETE	14	END CAP	144 CF	Ν	NAD	0	0	0
14.2	CONCRETE	14	END CAP	144 CF	Ν	NAD	0	0	0
14.3	CONCRETE	14	END CAP	144 CF	Ν	NAD	0	0	0
15.1	CONCRETE	15	CURB	1616 CF	N	NAD	0	0	0
Y – Yes N – No NA – Not App	N – No NA Not Applicable CAT I – Category I CAT II – Category I			Subtota	als for th	is page	0	0	0
NA - Not ApplicablePC - Point Count AnalysisNAD - No Asbestos DetectedPC - Point Count AnalysisLF - Linear feetPS - Analyzed to first positive stopSF - Square feetTrace - Less than 1%			cro crocidolite	Con	Consultant Fees				
<ol> <li>All quantitie</li> <li>All costs pro</li> </ol>		0	& M Cos	sts					
3. Shaded and	d bold text indicates Asbestos-Containing N	Naterial (AC	M) or assumed ACM.		TOTAL				

		-	stbound) – SR 789 over Coon Ke Agency:	-				No.: <u>BDV</u> tation, Dist	
iltant: <u>C</u>	B&I Environmental & In	nfrastructu	re, Inc. FDOT Contact Perso	on: <u>Jeffre</u>	ey W. Ja	ames	-		
Sample No. or Assumed	Material Description	Homo- geneous Area No.	Area Description	Quantity (Total for HA)	Friable Y/N	Asbestos Type & % or Assumed	Response Cost	Air Monitoring Cost	Replace Cost
15.2	CONCRETE	15	CURB	1616 CF	Ν	NAD	0	0	0
15.3	CONCRETE	15	CURB	1616 CF	Ν	NAD	0	0	0
16.1	CONCRETE	16	DECK	37370 CF	Ν	NAD	0	0	0
16.2	CONCRETE	16	DECK	37370 CF	Ν	NAD	0	0	0
16.3	CONCRETE	16	DECK	37370 CF	Ν	NAD	0	0	0
17.1	CONCRETE	17	RAILING – POST	13635 CF	Ν	NAD	0	0	0
17.2	CONCRETE	17	RAILING – POST	13635 CF	Ν	NAD	0	0	0
17.3	CONCRETE	17	RAILING – POST	13635 CF	Ν	NAD	0	0	0
18.1	MORTAR	18	DECK	681 SF	Ν	NAD	0	0	0
18.2	MORTAR	18	DECK	681 SF	Ν	NAD	0	0	0
18.3	MORTAR	18	DECK	681 SF	Ν	NAD	0	0	0
18.4 QA/QC	MORTAR	18	DECK	681 SF	Ν	NAD	0	0	0
19.1	BLACK ADHESIVE MASTIC	19	DECK REFLECTORS	70 SF	Ν	NAD	0	0	0
19.2	BLACK ADHESIVE MASTIC	19	DECK REFLECTORS	70 SF	N	NAD	0	0	0
19.3	BLACK ADHESIVE MASTIC	19	DECK REFLECTORS	70 SF	N	NAD	0	0	0
COMMENTS/NC Y – Yes N – No NA – Not Applic NAD – No Asbes	Subtotals for this page		s page	0	0	0			
LF – Linear feet SF – Square fee	PS – Analyze	ive stop	Cor	nsultant F	ees				
<ol> <li>All quantities given in square feet unless otherwise indicated.</li> <li>All costs provided assume one mobilization.</li> </ol>					O & M Costs				
3. Shaded and bold text indicates Asbestos-Containing Material (ACM) or assumed ACM.									
		-			TOTAL				

		-	stbound) – SR 789 over Coon K						
of Survey:	May 12 and 13, 2015 CB&I Environmental & Ir	fue at my at a	Agency: re, Inc. FDOT Contact Pers	FIOI	<u>ida Dep</u>	bartinent (	of Transpor	rtation, Dis	strict I
unant:	CB&I Environmental & Ir	IIrastructu	<u>re, Inc.</u> FDOT Contact Pers	son: <u>Jenn</u>	tey w	James			
Sample No. or Assume	Material Description	Homo- geneous Area No.	Area Description	Quantity (Total for HA)	Friable Y/N	Asbestos Type & % or Assumed	Response Cost	Air Monitoring Cost	Replace Cost
20.1	CLASS 5 COATING	20	VARIOUS LOCATIONS ON GIRDERS	250 SF	N	NAD	0	0	0
20.2	CLASS 5 COATING	20	VARIOUS LOCATIONS ON GIRDERS	250 SF	Ν	NAD	0	0	0
20.3	CLASS 5 COATING	20	VARIOUS LOCATIONS ON GIRDERS	250 SF	Ν	NAD	0	0	0
21.1	FIBERGLASS	21	PILE JACKET	3200 SF	Ν	NAD	0	0	0
21.2	FIBERGLASS	21	PILE JACKET	3200 SF	Ν	NAD	0	0	0
21.3	FIBERGLASS	21	PILE JACKET	3200 SF	Ν	NAD	0	0	0
21.4 QA/0	C FIBERGLASS	21	PILE JACKET	3200 SF	Ν	NAD	0	0	0
22.1	SEALANT (WITHIN THE SPACE BETWEEN PILE AND PILE JACKET)	22	PILE JACKET	1600 SF	Ν	NAD	0	0	0
22.2	SEALANT (WITHIN THE SPACE BETWEEN PILE AND PILE JACKET)	22	PILE JACKET	1600 SF	N	NAD	0	0	0
22.3	SEALANT (WITHIN THE SPACE BETWEEN PILE AND PILE JACKET)	22	PILE JACKET	1600 SF	Ν	NAD	0	0	0
Y – Yes N – No NA – No					Subtotals for this page		0	0	0
LF – Line					Consultant Fees				
1. All qua	<ol> <li>All quantities given in square feet unless otherwise indicated.</li> <li>All costs provided assume one mobilization.</li> </ol>					S			
2. All cost						.5			
3. Shade	d and bold text indicates Asbestos-C	ontaining M	aterial (ACM) or assumed ACM.		TOTAL				


#### ASBESTOS SURVEY REPORT – FORM 3 PERSONNEL SUMMARY


Facility/Bridge Name:	SR 789 (Little Ringling Bridge) over Coon Key Waterway
Bridge No.:	170022
Date of Survey:	May 12 and 13, 2015

Name and Address	Task Performed	License or Certificate
David W. Mosher, PE, LAC	Asbestos Consultant	EA-0000078
CB&I Environmental & Infrastructure, Inc. 9143 Philips Highway, Suite 400 Jacksonville, FL 32256	Asbestos Business	ZA-317
Thomas Gregory CB&I Environmental & Infrastructure, Inc. 1228 Winter Garden Vineland Road Winter Garden, Florida 34787	Asbestos Inspector	161984
Daniel Roebke CB&I Environmental & Infrastructure, Inc. 1228 Winter Garden Vineland Road Winter Garden, Florida 34787	Asbestos Inspector	140627-4599
EMSL Analytical, Inc. (EMSL) 5125 Adanson Street, Suite 900 Orlando, FL 32804	Bulk Analysis	NVLP No. 101151-0
International Asbestos Testing Laboratory (IATL) 9000 Commerce Parkway, Suite B Mt. Laurel, New Jersey 08054	Quality Assurance	NVLAP No. 101165-0

#### **SECTION 2**

#### **BRIDGE DIAGRAM(S)**





#### **SECTION 3**

#### PHOTOGRAPHS

N:\Clients\FDOT FILES\FDOT 1 (BDV 75)\PROJECTS\154316 (LOA 47) - SE 789 (Little Ringling Bridge) asbestos survey\5.0 Reports\Bridge 170022\154316 - Br 170022\_AsbSurv, Paint Survey\_070815 FINAL.docx



PHOTO 1 – 5/12/15 BRIDGE NO. 170022 – SR 789 OVER COON KEY WATERWAY – VIEW TOWARDS SOUTHEAST SARASOTA, SARASOTA COUNTY, FL




PHOTO 2 – 5/12/15 BRIDGE NO. 170022 – SR 789 OVER COON KEY WATERWAY – VIEW TOWARDS NORTHEAST SARASOTA, SARASOTA COUNTY, FL



PHOTO 3 – 5/12/15 BRIDGE NO. 170022 – SR 789 OVER COON KEY WATERWAY – VIEW TOWARDS NORTHEAST SARASOTA, SARASOTA COUNTY, FL

g. The second	
- ACM SAMPLE	
JECT NO. 154316 FDOT 1 FDOT 1	
PROJECT NO. FDOT 1 LIENT: FDOT 1 PROJECT LOCATION: SACAGENT PL BUILDING NAME: SK 780 OUL (ON KUL WARNY) BUILDING NAME: SK 780 OUL (ON KUL WARNY) ROOM NO. 100221 (JA ROOM NO. 100221 (JA	
B00111 12-167 1.3	
HA NO SCRIPTIONS	
HA CONUTS: NO PACINI	
FRIABLE CATIN N	
	- · N
were stilled	
PHOTO 4 – 5/13/15 – SAI CONCRET MIDDLE BENT, C	ſE




MIDDLE BENT, COLUMNS

11212 - LUG - ACM SAMPLE DJECT NO. 154316 PROJECT LOCATION: Socialista FL FDOT 1 780 Over Com Key Ustanny BUILDING NAME: SE ROOM NO. 1706 22 WB DATE: 5:12-15 2.3 INSPECTOR: Green 2.2 blams - concrete HA NO. 512415 HA DESCRIPTION: CC055 HA CONDITION: COMMENTS: NO RACM: YES FRIABLE --CATI CAT I: \_

PHOTO 7 – 5/12/15 – SAMPLE 2.1 – HA 2 CONCRETE BENT CAPS

	1
	2
	120
	1
	た
PRO ACIA SAMPLE	
	1
CLIENT.	S.
PROJECT LOCATION: Set Soft Set	A COL
Provide the second	
ROOM NO. 1760 22 UVE	del
DATE:15	
INSPECTOR: Grancing	
44 NO BOOK 24 22 23	
HA DESCRIPTION: COSS blans - converte	
HA CONDITION:	
HA CONTRACT	
COMMENTS:NO	
FRIADLE CATII:	
FRIABLE - YES RACM	1
V) actor mastic	
VI retrector mostic	
PHOTO 8 – 5/12/15 – SAMPLE 2.2 – HA 2	
CONCRETE	
BENT CAPS	
DENIGARO	







PHOTO 11 – 5/12/15 – SAMPLE 3.2 – HA 3 CONCRETE SEAWALL (NOTED AS ABUTMENT WALL ON PHOTO LOG)

121	
PHOTOGRAPH LOG - ACM SAMPLE PROJECT NO CLIENT: PROJECT LOCATION: Subjets PROJECT LOCATION: Subjets	8
BUILDING NAME: <u>SR</u> 780 and Good Key Waldward ROOM NO. <u>120022</u> WB DATE: <u>5:1215</u> INSPECTOR: <u>Guagoy</u> HA NO. <u>21</u> <u>3:7</u> <u>3:3</u> HA DESCRIPTION: <u>Abrutment</u> wall - concrete	
HA CONDITION: aread	

PHOTO 12 – 5/12/15 – SAMPLE 3.3 – HA 3 CONCRETE SEAWALL (NOTED AS ABUTMENT WALL ON PHOTO LOG)



	MAN TA COMPANY
and the second se	
OFOGRAPH LOG - ACM SAMPLE	
PROJECT NO. 154316	
CLIENT: FDOT 1	348 208 248 35
PROJECT LOCATION: Sanossta, FL	
BUILDING NAME: SR 780 over Coon key Wat	Turnel And
ROOM NO. 170022 WB	
DATE: 5-12-15	
INSPECTOR: GORDAN	
HA NO. 42 4-3	
HA DESCRIPTION: Abutment Concrete	
HA CONDITION: Lain	
HA CONDITION:	
A CONTRACT OF A	
FRIABLE - YES K NO	
CAT I: CAT II: RACM:	
users'illiomas gregory'idocuments'work'asbestos /field forms'acmphonolog.doc 05/12/15	
PHOTO 14 – 5/12/15	5 – SAMPLE 4.2 – HA 4
	NCRETE

**ABUTMENT WALL** 





PHOTO 15 – 5/12/15 – SAMPLE 4.3 – HA 4 CONCRETE ABUTMENT WALL

and the second s	and the second second		
a state to an	the second second second	Man Mes Town	
and the state of the	and the second		
		and the second	
10.5		- Carlotter and the set	
Contraction of the local			a the second
1.1			
	PHOTOGRAPH LOG - ACM SAMPLE		the state of the second
1 C	PROJECT NO. 154 31 L	A CONTRACTOR	A CARE AND A
	CLIENT: FDOT 1		
	BUILDING NAME: SP 780 over Coon key Walking		
Sec. 1	ROOM NO. 170022 WB		
	DATE: 5-12-15	and all the	And the second second
100	HA NO. 5-1 5-2 5-3		
	HA NO. 5-1 5-2 5-3 HA DESCRIPTION: alr. Iment Mater		20 million and a state
1.1		Enter	The second second
WH.	HA CONDITION: fair		
1	COMMENTS:	(A) Sold (A)	
× /	FRIABLE - YES K NO	TENE STATE	and the second second
	FRIABLE YESK NO CAT I: CAT II: RACM:		and the second
C			
		and the second	
Cont .			
1	explorate (ex. 65/72/15		
ĮÅ⊊ <sup>†</sup> ia	ers (homas gropps) alsoament overkassempylield femnannel folder, der 65/1233	A CONTRACTOR	
		in a start of a second of	
	and the second se		The second se
	145 and		CALLS IN , TA MUSSI
	PHOTO 16 – 5/12/15 -		5
	MOR	TAR	
	ABUTME	NT WALL	



**ABUTMENT WALL** 

	A Company of the
	and the second states of the
PHOTOGRAPH LOG - ACM SAMPLE PROJECT NO154 316 CLIENT: FDOT 1 PROJECT LOCATION: SAGAGE, EC BUILDING NAME: SP 750 ruta Con Key Lodower ROOM NO. 170072 US DATE: 57/255 INSPECTOR: Cargona	4
INSPECTOR: Gregory HA NO. 6-1 6-2 6-3 6-404 HA DESCRIPTION: 6nd Bent concrets HA CONDITION: good COMMENTS: FRIABLE - YES NO	
CAT I: CAT II: RACM:	
Art: stars those group downers with about 640 mm employing die 881913	

PHOTO 19 – 5/12/15 – SAMPLE 6.1 – HA 6 CONCRETE END BENT PILE CAP

and for	2 2 × 10/1	19/2.30
0		
	PHOTOS	No. Contraction
	PHOTOGRAPH LOG - ACM SAMPLE	10 10 5 90 B
	PROJECT NO. 154 316 CLIENT:FDOT 1	
	PROJECT LOCATION: Serajota, FL	
	BUILDING NAME: SR 700 our Cron key Waltering	
	ROOM NO. 170002 WB	
1 1 1 5 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	DATE: <u>5-12-15</u>	
	INSPECTOR: George 4-2 6-3 6-404	
	HA DESCRIPTION: End Bent - concrete	
	HA DESCRIPTION	
	HA CONDITION: good	
	COMMENTS:	
and the second second		
and a start water	FRIABLEYESNO RACM:	
and a state of the second second	CAT II: CAT II: RACM.	
	1 Martin	
Contraction of the second	a second local and a second seco	
	He wantebaux prest/determine of second	
ALLER DINGE		
the state of the		
	PHOTO 20 – 5/12/15 – SAMPLE 6.2 – H	A 6
	CONCRETE	


END BENT PILE CAP

No.	PHOTOGRAPH LOG - ACM SAMPLE		
	PROJECT NO. 154 316		A ROLL
	CLIENT: FDOT 1		Classes!
1	PROJECT LOCATION: Sarasota FL		See She
1	BUILDING NAME: SR 780 nr Con key Walering		
A 19 11	ROOM NO. 170077 WB		
1. 1. 1.	DATE: 5-12-15		
	INSPECTOR: Gregory 6-404		
11	HANO. AL GAZ 6-3 6-TON		
13.2	HA DESCRIPTION: God Bent - concrete.		
	HA CONDITION: good		
	COMMENTS:		
100 C			
	CAT I: CAT II: RACM:		
	CATI		
		A State of the second second	
	Net users done as prepay decrement work with and to main methods and (0) 311		
	shomas graphy documents work sale led formate provide		
	1V c.metzman		

PHOTO 21 – 5/12/15 – SAMPLE 6.3 – HA 6 CONCRETE END BENT PILE CAP

		1 DY
	226	P A
	PHOTOGRAPH LOG - ACM SAMPLE	1 1 1 1
	PROJECT NO. 154 316 CLIENT:	
200	ELECTION SECTOR	
	BUILDING NAME: SP 7to nut Con Key Libline	
N III K		A STATE AND A STAT
	ROOM NO DATE: <u>5'12-15</u>	COLUMN AND STREET
	INSPECTOR: Great A	
	HA NO WA BUNT CONVERSE HA DESCRIPTION: God Bunt converse	THE REAL PROPERTY AND ADDRESS
	HA NO BESCRIPTION: End Bent Call	
	HAULT	
	HA CONDITION AND	
	INVENTS.	ALL
A COLOR	COMMENTS:YESNO FRIABLEYESNO CAT II:RACM:	
Sec.	FRIABLE	
and the second	COMMERT YES NO FRIABLE CAT II RACM:	THE REAL PROPERTY OF
and a section of		
		CONSISTER OF MARKEN AND

PHOTO 22 – 5/12/15 – SAMPLE 6.4 QA/QC– HA 6 CONCRETE END BENT PILE CAP



DIAPHRAM


20 - 51	and the second s
	and the state of the second state of the second
	and a second in the second
	E Contraction To the second
ACM SAMP	LL Langest And Participation
- ADH LOG - AOM	and all the set of the set of the set of the
DHOTOGRAFT	
PHOTOGRAPH LOG - ACM SAMP	and the second of the second o
-H316	and the second s
PROJECT NO. 154316 FDOT 1	
CLIENT: FUELOCATION: Secarate I	her haloway
CLIEN	Lagent
PROJECT NO. FDOT 1 CLIENT: FDOT 1 PROJECT LOCATION: Secreta FC	
PROCE WIG NAME:	Contraction of the second seco
BUILDING	- Pressed in the second
PROJECT NO	
Rot cizo	1.3
ROOM NU. DATE: 5-12-15 DATE: 5-12-15 DATE: 5-12-15	1. La
DECTOR: 0	CROCELASE
DATE: S.IZ.D INSPECTOR: Greatly	
HANO CRIPTION: DIAPhan	
HA SESCRIPTION	
DATE: STEE INSPECTOR: Greens HA NO. THE HA DESCRIPTION: DISPLACE HA DESCRIPTION: DISPLACE	
HA DEL HA CONDITION: gen HA CONDITION: Gen	
IN CONDITION	
HA WENTS:	NO
HA CONDITIST	RACM:
FRIABLE CAT II:	
PIABLE CATIL	
FRIN	A CONTRACT OF A
CATI	A CONTRACT OF A CONTRACT.
	and a state of the
and the second se	
And and a second s	
and the second second	
Action of the second	
Construction of the management	

PHOTO 25 – 5/12/15 – SAMPLE 7.3 – HA 7 CONCRETE DIAPHRAM

1				1 1 1 1 1 1 S
	4212-12	States and the states	B ALANK Cast	1113 23 4
	and the second s	ALC: NOT	SUL LILENS	Cart South
	the state of the	A CONTRACTOR OF A CONTRACTOR OFTA CONTRACTOR O	Stor Mark Link	land the
			1 Call Bar	What Falls
	CO TRANK	· · ·	Black of Carth	10 4 - 10-
1	1.21121		1 Are Are	the 1
	PHUTUGRAPH LOG - ACM SAMPLE		MART MERTI	- 4 - 1
	PHOTOGRAPH LOG - ACM SAMPLE		All Area -	Print 1
	PROJECT NO. 154316		ALL AND ST	and a set
	CLIENT: FDOT 1		ENAL TELE	all a stand of the
	BUILDING NAME: SE 780 and Comp key b	grantetal	NUMBER OF THE	1. 1. 1. 1.
	ROOM NO. 170022 WB	-		
2 AL	ROOM NO. 10000 Mg	-	A Star	1000001/2
	DATE: 5-12-15			Sector 1
	INSPECTOR: Greening 8-2 8-3			
	HANO. 8-1 Sub-airder aspt	alt		
	HA NO. 8-1 8-2 8-3 HA DESCRIPTION: Sub-girder asph prods			
Par I	HA CONDITION: Fait			
	HA CONDITION			
	COMMENTS:	VA		
5	FRIABLE - X YES NO CAT I: CAT II: RACM:			
6.5	FRIABLE - RACM			
	CAT I: CAT II.			
	CAT			
		1		
		-		
	was forms accuptonalog, dos. (25)(2:15			
A CONTRACTOR	The surrabonic proper deciments work above field term surplicing the 1912/1			
	JAC uners thomas a "			
The second second		A CHARTER AND		
	PHOTO 26 – 5/12/15		0 41	
		LT PAPER	IA 0	
	SUBGIRDER	BEARING PAD		

	C Librar	2 2 2 2	195
	Cartania in	a star galler	1 1 2
		CONTRACTOR IN	The states
	icity is		0.0 3
		the state of the second	Section 2
ENGLA			3 1 - A - P
	PHOTOGRAD	Sold Market Contraction	Carlo Carlo
	PHOTOGRAPH LOG - ACM SAMPLE	State of the second state	A Carlor
	PROJECT NO. 154316	and the state of	St. Marke
	PPO INTE FDOT 1	and the start	1 1 1 1
	PROJECT LOCATION: Secarche FL	The second second	
	BOOM :: SR 180 and Ch		Ser in
	ROJECT LOCATION: Seconds for BUILDING NAME: SE TED AND COM Ky Listing ROOM NO. 170022 W. DATE: 5:10:00		NEL DODE
1.3 m Alla	DATE: 5-12-15	All the shares	3-1-1
Carlos A	HA NO. 221 HA DESCRIPTION: C / 8-3		1919
Sel all	HANO. 81 0 0	1 Designed	and and
2019192 ·	HA DESCRIPTION: Sub-girder asphalt	A A A A A A A A A A A A A A A A A A A	
A HAR AR	pads gillour asphalt		
111111	HA CONDITION: Fait		
a and a set	COMMENTS:	A DESCRIPTION OF STREET	
1-9-344			
13 11 10	FRIABLE - X YES NO	A CONTRACTOR OF	the first of the second
and the second	CAT I: CAT II: RACM:		
Carl Maria			
State Land			and the second second
		Market Market States	Contraction of the second
1. 1. 1. 1	i.	The August and the second s	
S. R.	IAC supervisions, preprint documents work arbitrate fails from companying for 16/12/13		Restaura Pile
and the second se	100.000		
12 25			
18			
S. C. M.			
A.		12/1 - All All All All All All All All All A	
-	A State State		

PHOTO 27 – 5/12/15 – SAMPLE 8.2 – HA 8 ASPHALT PAPER SUBGIRDER BEARING PAD



	PHOTOGRAPH LOG - ACM SAMPLE
	ICUINO, ICUILI
	PROJECT LOCATION: Splace C
	BUILDING NAME: SP 780 ALC Convey (Datum) ROOM NO. 170022WB
	DATE: 5-12-15 INSPECTOR: George
•	HA NO. 9.1 9.2 9.3 HA DESCRIPTION: GODING CONNEC
	HA CONDITION: good
	COMMENTS:
	FRIABLE - YES KNO RAGN: CAT II: RAGN:
	Constant Constant

PHOTO 29 – 5/12/15 – SAMPLE 9.1 – HA 9 CONCRETE GIRDER



N:\Clients\FDOT FILES\FDOT 1 (BDV 75)\PROJECTS\154316 (LOA 47) - SE 789 (Little Ringling Bridge) asbestos survey\5.0 Reports\Bridge 170022\154316 - Br 170022\_AsbSurv, Paint Survey\_070815 FINAL.docx

GIRDER



PHOTO 32 - 5/12/15 - SAMPLE 10.1 - HA 10 MORTAR GIRDER

BUILDING NAME: SR 780 over Coon by Waturay

CAT II: \_\_\_\_\_ RACM: \_

ROOM NO. 170022 WB DATE: 5-1215

INSPECTOR: Greener HA NO. 10-1

HA CONDITION: Coro COMMENTS:\_\_\_\_

CAT I:


HA DESCRIPTION: Grobers- Mortan

FRIABLE - YES K NO

	Sacola ,	A Start
	WAR TRANSPORT	
	PRO ISON	
the state	NOJECT NO. ICURY	
	FDOT 4	at the state
	PROJECT LOCATION: Social Co	and the second
	- TEDING NAME: JOD DURG ( OF 11 12 F.	x.
	ROOM NO. 170022 WB	
	DATE: 5-1215	
	INSPECTOR: Great	
	INSPECTOR: Gregory HA NO. 10:1 10:2 10:3	
29-1	HA DESCRIPTION: Grobers- Mortan	ALL AND AL
		1999年1975日
	HA CONDITION: <u>Comp</u>	and the second
4	COMMENTS:	2 1 2 5 6
	NO	and the second
	FRIABLE - YES RACM:	A Start Start
	FRIABLEYESKNO         CAT I: CAT II: RACM:	11 . 1
	,	
	1770 - 1770 - 1770 - 1770 - 1770 - 1770 - 1770 - 1770 - 1770 - 1770 - 1770 - 1770 - 1770 - 1770 - 1770 - 1770 -	
	relevants prepary decembers work adversion data forms announding an 40/2/3	
	shows greeny documents and	

PHOTO 33 – 5/12/15 – SAMPLE 10.2 – HA 10 MORTAR GIRDER

Test allan	and a lot	A DESCRIPTION OF		Stor State of
0 3	a con a man and an			
15.12 - all -	The state	AR 43 193		
5.1. 22.00	1 - 1 - 1 - 1			c'an '
1-70 - 1 - John	+/: 22 ·		and the second s	1
67 2013		- 福田市市市市 1	ALL IN	2000-00
	i i i i i i i i i i i i i i i i i i i		the second	an rise
and the second second second	Line A	17	Parts In T	The state
- ACM	A SAMPLE	A State I		1 2 2
	Btor	N. March & I		at Part and
PROJECT NO. 154316			the second	
EDOT 1	- Stind		12.	
CLIENT: FUT	a, FC In Junan Vi		Sta .	
PROJECT LOCATION	Coon key warmen to -	in the second		
CLIENT: PROJECT LOCATION: Sacason BUILDING NAME: SR BUILDING NAME: SR DOOM NO:WB	14	7-2		Cart -
ROOM NO. 170077 WB	134	S S. Marker		
	10.2	A REAL OF	N.S.	
DATE: 5-TOT	103			
HA NO. LOST HA NO. LOST	105-tac		AND -	· For
INSPECTOR: DECEMONING			AR .	
HA DESCH				TX X
unition.		CARE AND LEVE	and the second second	Literat -
HA COND. COMMENTS:	NO	L. STORE	Allesia	
FRIABLE CATIL	RACM	<ul> <li>A second difference</li> </ul>	一位"说"	and the second second
NABLE CATIN	-	<b>人名</b> 人的法国法国	1949	
FRIABLE CATIN			CONTRACT OF	A state of the
CAL				
			143	ALC: NO.
	1 Andrews	1 58 58 68	and the second second	-
	A STREET, STREET, ST			
	and make the second	A SOL	and a star with	
	A COMPANY AND A COMPANY		No.	Caller and the second
ΡΗΟΤΟ	34 – 5/12/15 – SA	MPLE 10.3 – HA	10	
	MORTA	\R \R		
	GIRDE			
	GIRDE	Γ.		






PHOTO 36 – 5/12/15 – SAMPLE 11.2 – HA 11 ASPHALT PAPER SUBDECK BEARING PAD

Que Sanda e	
WANTPLE	
PROJECT NO. 154316	
EDOT 1	
BUILDING NAME: SR TAC OUT CON LEWEDDING	All all and and
ROOMING	A P
HA NO.	
HA DESCRIPTION.	
HA DESCRIT	
FRIABLE CAT II: RACM	
CATI	
	1 - Ar . Share
A LAN	1

PHOTO 37 – 5/12/15 – SAMPLE 11.3 – HA 11 ASPHALT PAPER SUBDECK BEARING PAD

and a fair fair and		ALCONE GRADE	
Contraction of the			Sec. 19
			Start.
	PHOTOGRAPH LOG - ACM SAMPLE		
	PROJECT NO. 154316		
1.000	CLIENT: FDOT 1		
	PROJECT LOCATION: Some		Sec. 1
ALCONT	BUILDING NAME: 52 780 Duras las how		
State of the	PROJECT LOCATION: Sorasota, El BUILDING NAME: S2 780 Over Look Key Waterway ROOM NO. 170022 - WB		
	INSPECTOR: Q all	14 1 1 1 1	2.5
	HA NO. 12 - 1 2 3 YOA/QC	P-R 2 - P	
all to the	HA DESCRIPTION: Expansion Joint		
3			
	HA CONDITION:	**************************************	
	COMMENTS:	. 1962	
	FRIABLE - YES VO		
	CAT I: CAT II: RACM:		100
			100
LIL CALL MALT MALE			
1 North Contraction	1		193.00
	JAc users thomas propsy documents work unbertout field from documenting date (6):233		
			1
	PHOTO 38 – 5/12/15 – SAMPLE 12.1 – HA 12		
	RUBBER SEALER		

**EXPANSION JOINTS** 

	PHOTOGRAPH LOG – ACM SAMPLE	
		A CONTRACTOR
	PROJECT NO54 \$16	
	CLIENT: FDOT 1	
	PROJECT LOCATION: <u>Sarasota, El</u> BUILDING NAME: 52. 780 over Loon Key Waterway	
	ROOM NO. 170022 - WB	
	DATE: 5/12/15	a at a said
	INSPECTOR: Roebke	C.S. Carlos
an and the second second	HA NO. 12 - 12 3 4 DA/QC	N. J. M
	HA DESCRIPTION: Expansion Joint	. with the second
	HA CONDITION:	· ·
	COMMENTS:	A Contraction
1501		
	FRIABLE - YES VO	
	CAT I: CAT II: RACM:	
- - F	PHOTOGRAPH LOG - ACM SAMPLE   PROJECT NO	
	PHOTO 40 – 5/12/15 – SAMPLE 12.3 – HA 12 RUBBER SEALER EXPANSION JOINTS	and the second

	and the second sec
PHOTOGRAPH LOG - ACM SAMPLE	
LOGRAPH LOG - ACM DA	
PROJECT NO. 154316	
PROJECT LOCATION: Sarasota, El BUILDING NAME (2) 280	
BUILDING NAME CO 2000 ALL	
BUILDING NAME SR. 780 Over Look Key Waterwar ROOM NO. 170022 - WB	ay a state of the
DATE: 5/12/15	
INSPECTOR: Roebke	
HA NO. 12 - 1/ 1/ 4 404/90	
HA DESCRIPTION: Expansion Joint	and the second
HA CONDITION: 900	
COMMENTS:	and the second second second second
COMMENTS	
FRIABLE - YES NO	
FRIABLE YES         RACM:           CAT I: CAT II: RACM:         RACM:	
CAT 1: CAT	
	and the second
	THE PERSON NEW YORK
1	Contraction of the second
PHOTO 41 – 5/12/15 – SAMPLE 1	2.4 QA/QC – HA 12
RUBBER SEALE	
EXPANSION JOIN	NTS
	PHOTOGRAPH LOG - ACM SAMPLE
	PROJECT NO. 154316
	CLIENT:FDOT 1
and the second	PROJECT LOCATION: Sara sota , 51
	BUILDING NAME SR. 700 OVER (COR KAY Water
	DATE: 5/12/15
A REAL PROPERTY OF AN A REAL PROPERTY OF A REAL PRO	INSPECTOR: Rochie
	HA NO. 13 . 1 2 3
And the second	HA DESCRIPTION: Roilings
and the second sec	HA CONDITION:
	COMMENTS:
	FRIABLE - YES NO
	CAT I: CAT II: RACM:
	Ave institutions graphy day.
	and the second second
PHOTO 42 – 5/12/15 – SAMPI	LE 13.1 – HA 13

 PHOTO 43 – 5/12/15 – SAMPLE 13.2 – HA CONCRETE RAILING	A 13
PHOTOGRAPH LOG - ACM SAMPLE         PROJECT NO.       15 4 3/6         CLIENT:       EDOT 1         PROJECT LOCATION:       Sara Sorta	
CONCRETE RAILING	-

PHOTOGRAPH LOG - ACM SAMPLE	
PROJECT NO. 154316	
CLIENT: FDOT 1	
PROJECT LOCATION: Sarasota, 81	
BUILDING NAME: SR 790 aug Com Kault	1 Alexandre and a second
TIDLE WK	
DATE: 5/12/15	and the second second
INSPECTOR: Roebke	
HANO. 14-1 2 3	
HA DESCRIPTION: END (49	
	Contraction and the
HA CONDITION: gand	
COMMENTS:	
COMMENTS	
YES NO	-
FRIABLE RACM:	1 de 1
COMMENTO:       YES       NO         FRIABLE -       YES       NO         CAT I:       CAT II:       RACM:	1000
PHOTO 45 – 5/12/15 - SAMPLE 14.1	

PHOTO 45 – 5/12/15 - SAMPLE 14.1 – HA 14 CONCRETE END CAP

PHOTOGRAPH LOG -	ACM SAMPLE	
PROJECT NO. 154316		
CLIENT: FDOT 1		
PROJECT LOCATION: Sara	into RI	
BUILDING NAME: SR 780 0	ue Com Kay Wake -	
ROOM NO. 170022 - 4	IR REAL REAL REAL	
DATE: 5/12/15		
INSPECTOR: Roebke		
HA NO. 14 - 4 2	3	4
HA DESCRIPTION: END	49	
	**	
HA CONDITION: 2000		
COMMENTS:		
FRIABLE - YES		
CAT I: CAT II:	RACM:	
РНОТО 46 –	5/12/15 – SAMPLE 14.2 – HA 14 CONCRETE END CAP	

	to the second second	Constant - R. X
		1 - A Been
CHARLES CO.		
	PHOTOGRAPH LOG – ACM SAMPLE	
	PROJECT NO. 154316	
	CLIENT: FDOT 1	the former to the
	DINIC NAME: SP 790 OVER COOL NEY SCO.	way
	ROOM NO. 170012 000	
	DATE: 5/12/15	
	INSPECTOR: Roebke 3 HA NO. 14 - 4 3	
Contraction of the second	HA DESCRIPTION: END 74P	
	HA CONDITION:	
	COMMENTS:	
	NO	
	FRIABLE - YES NO	
	CAT I: CAT II	
100		
	PHOTO 47 – 5/12/15 – SAMPLE 14.3 –	HA 14
	END CAP	
The second		
A CONTRACT OF	PHOTOGRAPH LOG - ACM SAMPLE	
	TRO IECT NO. 154316	
	OUTENT. LOC.	
	BUILDING NAME: <u>SK 700-07</u> ROOM NO. <u>170022 - WB</u> DATE: <u>S1/21-5</u>	
	INSPECTOR: Coches HA NO. 15 - \$1 \$ 9 3	
· 2 100	HA NO. 19 HA DESCRIPTION: Curb	A State of the second sec
100	HA CONDITION: _ 3000	and the
200	COMMENTS:	and the second second
	FRIABLE - YES NO RACM:	
	CAT I: CAT II: RACM:	
Market C		
	PHOTO 48 – 5/12/15 – SAMPLE 15.1 – CONCRETE	HA 15
	CURB	

PROJECT NO.   SPROJECT NO.   SPROJECT NO.   SPROJECT NO.   SPROJECT NO.   SPROJECT LOCATION:   SOLICT LOCATION:   MADESCRIPTION:   LILL   HA DESCRIPTION:   CUILL   HA CONDITION:   SOLICT   COMMENTS:   FIRIABLE -   YES   NO   CAT I:   CAT II:   RACM:		
PHOTO 49 – 5/12/15 – SAMPL CONCRETE CURB	E 15.2 – HA 15	

PHOTOGRAPH LOG - ACM SAMPLE

BUILDING NAME: SR 780 over Coon Key Waterway

PROJECT LOCATION: SAVA Sota , FI

PROJECT NO. 154316 CLIENT: FDOT 1

ROOM NO. 170022 - WB

HA NO. 15 - 40 400 3

DATE: S/12/15 INSPECTOR: Roeble

HA DESCRIPTION: Curb

HA CONDITION: good

FRIABLE - YES YES NO CAT I: \_\_\_\_\_ CAT II: \_\_\_\_\_ RACM: \_\_\_

COMMENTS:

PHOTO 50 - 5/12/15 - SAMPLE 15.3 - HA 15 CONCRETE CURB

<form>         Particle of the second of</form>
PHOTO 51 – 5/12/15 – SAMPLE 16.1 – HA 16 CONCRETE DECK

PHOTOGRAPH LOG - ACM SAME         PROJECT NO.       151316         CLIENT:       FDOT 1         PROJECT LOCATION:       SAFASSATA ST         BUILDING NAMES & 780 over (conket         ROOM NO.       1702 22 - WB         DATE:       \$1/2/15         INSPECTOR:       Soebka         HA DESCRIPTION:       Sridge Deck         HA CONDITION:       good         COMMENTS:       NO         FRIABLE -       YES       NO         CAT I:       CAT II:       RACM:	Ap Materway
	15 – SAMPLE 16.2 – HA 16 DNCRETE DECK

BRIDGE 170022 ASBESTOS SURVEY PHOTO LOG
PHOTOGRAPH LOG - ACM SAMPLE   PROJECT NOYABIG   CLIENT:FDOT 1   PROJECT LOCATION: _SATASOTA, CT   BUILDING NAME SL 280 over ( Cook kee Nakruw   ROOM NOOO 22 - WB   DATE:S_12/15   INSPECTOR:AB   MA DESCRIPTION: Bridge Deck   HA CONDITION:ROM   CMMENTS:   FRIABLEYESNO   CAT !: CAT II: RACM:
PHOTO 53 – 5/12/15 – SAMPLE 16.3 – HA 16 CONCRETE DECK
PHOTOGRAPH LOG - ACM SAMPLE

PHOTOGRAPH LOG - ACM SAMPLE         PROJECT NO.       /SU316/         CLIENT:       FDOT 1         PROJECT LOCATION:       Sarassota, (1)         BUILDING NAME:       S2 760 over Coon Kay Uberney         ROOM NO.       170222 - WB         DATE:          MSPECTOR:       Cooblea         HA DESCRIPTION:       Lailing Post         HA CONDITION:       Post         COMMENTS:	
PHOTO 54 – 5/12/15 – SAMPLE 17.1 – HA CONCRETE	17
RAILING POST	

	PROJECT NO.       /SY3/6         PROJECT NO.       /SY3/6         CLIENT:       FDOT 1         PROJECT LOCATION:       Saras ota, f1         BUILDING NAME:       Saras ota, f1         BUILDING NAME:       Saras ota, f1         BUILDING NAME:       Saras ota, f2         DATE:       _//L//S         INSPECTOR:       Cooble         HA CONDITION:       Saras         COMMENTS:	
-	Proventione programment in the state of the	E 17.2 – HA 17
	CONCRETE RAILING POST	
		a 1. 41.
P C P	PHOTOGRAPH LOG - ACM SAMPLE ROJECT NO. /54316 ELIENT: FOOT 1 ROJECT LOCATION: Sarasota, 61 EUILDING NAME: 52 760 over Capa Kay Ubierway 12(702 2 - WB	
R D IN	IULDING NAME: <u>SL. J WB</u> OOM NO. <u>17022 - WB</u> ATE: <u>C/12/15</u> ISPECTOR: <u>Roebke</u> A NO. <u>17 - K 3</u> A DESCRIPTION: <u>Railing Post</u>	
нл сс	A CONDITION: DMMENTS: IABLE YES NO T I: CAT II: RACM:	
CA		
	PHOTO 56 – 5/12/15 – SAMPL CONCRETE	E 17.3 - HA 17

**RAILING POST** 

- Carlos Barton			1- Jan 1- 2
		VIII A	1-1-
		- Alexandre	- X X
and the second second	A Contraction of the second	X X T = CAN	
The second second		New House and the second	A SIZA
		1 Comment	the states
			A Short -
- Alexandre	PHOTOGRAPH LOG - ACM SAME		
		PLE	0-0
States and the	PROJECT NO. 154316	and the state	North Contraction
Sec. 2.	CLIENT: FDOT 1		
Street 1	PROJECT LOCATION: Sara Jota, 51		
	BUILDING NAME: 52 20 over Loon	Car Abteriance	
	10011 NO. 110022 - WB		
	DATE: 5/12/15		
	INSPECTOR: Roebke		and the second
	HANO. 18 - 1 2 3 4 4	ha	The second
and the second second	HA DESCRIPTION: DECK CENENT		
	TA DESCRIPTION: DEC CENEDT		
		1. S	
and the second	COMMENTS:		
			· · · · · ·
	FRIABLE YES _ MO	and the second s	
ing a	FRIABLE TES HO		
	CAT I: CAT II: RACM:		
			Estant Anti-
	PHOTO 57 – 5/12/15 – SAMPLE	- 18 1 – HΔ 18	
	MORTAR		
	BRIDGE DECK		
		https://www.com/analysis.com/analysis	3710 Bringer
			11 11
and the second s			
			34 Station
			A GUNLANS
P	HOTOGRAPH LOG - ACM SAMPLE	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	A REAL PROPERTY AND IN THE REAL PROPERTY AND INTERPORT
		the second s	
P	ROJECT NO. 154316		and the set of
	LIENT: FDOT 1		195 20
F	PROJECT LOCATION: Sara Jota, FI		
	BUILDING NAME: SR 200 over loon Key Waterway		
	ROOM NO. 170022 - WB		The second
2.98	DATE: 5/12/15		
	HODECTOR: Rochke	and the second	and the second
	18-2 2 9 ayor		
	HA DESCRIPTION: DELL CENELT		and them
	HA CONDITION:		Martin Martin
12	COMMENTS:		Contraction of the
			A CARLES
	TRIABLE - YES - RACM		
Section 1	CAT I: CAT II: RACIN		
		and the second s	
No.			Star Adams
- Alexandre	1		STATIS STATE
Contraction of the second	1		No. 200
	PHOTO 58 – 5/12/15 – SAMPLE	- 18.2 – HA 18	
	MORTAR		
	BRIDGE DECK		

		West and the second
	PHOTOGRAPH LOG – ACM SAMPLE	
	PROJECT NO. 154316	SACE 1
	CLIENT: FDOT 1	the second second
	PROJECT LOCATION: Sara sota, 51	
2.11	BUILDING NAME: 52 20 over 600 key Harring ROOM NO. 170022 - WB	
	DATE: 5/12/15	
	INCRECTOR: Dachke	
	HANO. 18-6 4 9 4 MAC	the second second
	HA DESCRIPTION: DECK CENELT	
	HA CONDITION:	
	COMMENTS:	
	FRIABLE - YES NO RACM:	
A REAL OF	FRIABLE - YES NO CAT II: RACM:	
X		
- And	T	
1100	- Anothernational indexed field freesivereglander are distant	×
	a propio	and the second sec
	PHOTO 59 – 5/12/15 – SAMPLE 18.	3 – HA 18
	MORTAR BRIDGE DECK	
10000		
		Call State State
		Margare _ etc.
	PHOTOGRAPHICO	147 - 147 L
	PHOTOGRAPH LOG – ACM SAMPLE	
2	PROJECT NO. 154316	The second la
18	CLIENT: FDOT 1	
	PROJECT LOCATION: Sara Jota, 41 BUILDING NAME: SE 720 over Loon Key Haterway	
	ROOM NO. 170022 - WB	
	DATE: 5/12/15	
	INSPECTOR: Roebice	
	HA NO. 18 - 2 4 4 4462	
	HA CONDITION:	
	COMMENTS:	
	FRIABLEYESNO	
	FRIABLE FE3           CAT I: CAT II: RACM:	
		All
	PHOTO 60 – 5/12/15 – SAMPLE 18.4 Q. MORTAR	AVQU - HA 18

**BRIDGE DECK** 

PHOTOGRAPH LOG - ACM SAMPLE	PT BUILD	A.E	
O OGRAPH LOG	or other and the later of		
PROJECT NO	Constraint and the	_	A Distances of
CLIENT.	The second se	Contraction of the	
PROJECT LOS	NOTICE STATE	1	and and and the second
PROJECT LOCATION: Sarasbta, F1 BUILDING NAME: S2 780 ever Const Key Waterway ROOM NO. 170922 - WB	Construction of the	A DESCRIPTION OF THE OWNER OWNER OF THE OWNER	THE OWNER OF THE OWNER OF
ROOM NO. 170020		And a subsection of the subsec	
DATE: 5/12/15	my l		
INSPECTOR: Roelle	· ·		
11A NO. 19 - 1			
HA DESCRIPTION: Reflector Mastic	00	-	
HA CONDITION: good			
COMMENTS:			Street St.
FRIABLE - YES V NO			
CAT I: CAT II: RACM:	the second se		
	The second second		10000
	The second second	No. Contraction	
		and the second second	
-sony documentational automation from form form photology doc 10/12/15	A CONTRACTOR		
Sony documents work and that a new source of		11 A12 212	
	m and a second	States - States - States	Contra 1
	the second	they have	West of a state
	State of the local division of the local div	Married Married Married	

BLACK ADHESIVE MASTIC UNDER REFLECTORS ON DECK

	A CONTRACTOR OF THE OWNER	
PHOTOGRAPH LOG – ACM SAMPLE		1
PROJECT NO. 154316		
CLIENT: FDOT 1 PROJECT LOCATION: Sarasota, FI	A REAL PROPERTY AND ADDRESS OF	
BUILDING NAME: 5/2 780 ever Coon Key Waterway ROOM NO. 170922 - WB	<b>y</b>	
DATE: 5/12/15 INSPECTOR: Roebke		
HA NO. 19 - 1 5 3		
HA DESCRIPTION: <u>Reflector Mostic</u>	and the local sectors of	
HA CONDITION: good		
FRIARIE YES V NO		
CAT I: CAT II: RACM:		
		R

PHOTO 63 – 5/12/15 – SAMPLE 19.3 – HA 19 BLACK ADHESIVE MASTIC UNDER REFLECTORS ON DECK

0			
	The state of the s	1	·;
PHOTOGRAPH LOG - ACM SAMPLE			
PROJECT NO. 194316 CLIENT: FOOT 1 PROJECT LOCATION: Satespice for BUILDING NAME: SR TBD OWN (SW BUILDING NAME: SR TBD OWN (SW)	Key walky		
ROUM	1	Colle-	1 2 **
HA NO. HA DESCRIPTION: Some			
HA CONDITIONS	ACON.	€.	
	1.		
2- //			
PHOTO 64	- 5/12/15 - SAMPLE 20.1	– HA 20	
	CLASS 5 COATING		

N:\Clients\FDOT FILES\FDOT 1 (BDV 75)\PROJECTS\154316 (LOA 47) - SE 789 (Little Ringling Bridge) asbestos survey\5.0 Reports\Bridge 170022\154316 - Br 170022\_AsbSurv, Paint Survey\_070815 FINAL.docx

VARIOUS LOCATIONS ON GIRDERS

PHOTOGRAPH LOG - ACM SAMPLE		
126		
BUILDING MOST	and the second	
INSPECTOR: Class 2 cours		
HA CONDITIST AND NO RACM		
COMME YES		Alter a start
1		ter an a

PHOTO 65 – 5/12/15 – SAMPLE 20.2 – HA 20 CLASS 5 COATING VARIOUS LOCATIONS ON GIRDERS

a change	Charles and the second se	1000 00 00 00 00 00 00 00 00 00 00 00 00	1
ALC: NO	A MARCON	A TO	The second
SICH	PHOTOGRAPH LOG - ACM SAMPLE	a.s.t.t.	al and
1	PRO - ACM SAMPLE	Orpel'	Contraction of the second
1000	CLIENT SY316		*****
	PROJECTION	THE B	14.
	PROJECT LOCATION: STERSOL PL	FT.	
	ROOM NO. Day 201 100 over Loon Kay Walden		The same
100 m	DATE: 512.15	E SEA	
and the second	INSPECTOR: 60000	are to	P. Start
and the second second	HANO. DO 142 20.3	f.	
	HA DESCRIPTION: Class 5 costing	1	Â
- X3	HA CONDITION:	Ren C	in the set
2.00-	COMMENTS:		4.
and the second			
and the	FRIABLE - YES K NO	Stranger .	101 15
22	CAT I: CAT II: RACM:	. 15	
a total		the	
			enter land
		1	· Jan Hart
			~ 3 1 4 4 4 ×
		1	A REAL PROPERTY
	PHOTO 66 – 5/12/15 – SAMPLE 20.	3 – HA 20	
	CLASS 5 COATING		


VARIOUS LOCATIONS ON GIRDERS

. \_UG - AUM. 154316 Call Very water JECT NO. PROJECT LOCATION: Sacaseta P BUILDING NAME: 52 130 ROOM NO. MOULZ 21.4 4A DATE: 5-131 2:3 INSPECTOR: Great GLASS HA DESCRIPTION: FIBEA HA NO. 21-1 HA CONDITION: GOD CONMENTS:-NO RACM: YES FRIABLE -CATI CATI

PHOTO 67 – 5/13/15 – SAMPLE 21.1 – HA 21 FIBERGLASS PILE JACKET

OJECI NO. 154316
LIENT: FDOT 1
PROJECT LOCATION: Sarasota, PL
THU DING NAME: SR 780 OVER CON ROLLING
POOM NO. 170000
WORECTOR: DIPAN OLS ZING
HA NO. 2 KI FIBERGIASI
HA DESCRIPTION:
HA CONDITION: GOOD
HACONDIT
ABLE TH
FRIADE CAT II.
and the second sec
Newsman and the second se
PHOTO 68 – 5/13/15 – SAMPLE 21.2 – HA 21 FIBERGLASS

**PILE JACKET** 



.. IT LOG - ACM SAMPLE PROJECT NO.\_ FDOT 1 - Ceal KON WATERN ROJECT LOCATION: LIENT: Arasota, t BUILDING NAME: Se ROOM NO. TOULE WE DATE: 5-131 INSPECTOR: G HA NO. 241 HA DESCRIPTION: HA CONDITION: G COMMENTS: FRIABLE -CATI CATI

PHOTO 70 – 5/13/15 – SAMPLE 21.4 QA/QC – HA 21 FIBERGLASS PILE JACKET

BRIDGE 170022 ASBESTOS SURVEY PHOTO LOG
Image: State of the state
SEALANT (IN THE SPACE BETWEEN PILE AND PILE JACKET)         PILE JACKETS         PROJECT NO.         SCIENT:         POIDIT:         PROJECT LOCATION:         SCIENT:         BUILDING NAME:         SCIENT:
SEALANT (IN THE SPACE BETWEEN PILE AND PILE JACKET) PILE JACKETS

N:\Clients\FDOT FILES\FDOT 1 (BDV 75)\PROJECTS\154316 (LOA 47) - SE 789 (Little Ringling Bridge) asbestos survey\5.0 Reports\Bridge 170022\154316 - Br 170022\_AsbSurv, Paint Survey\_070815 FINAL.docx

## **SECTION 4**

## LABORATORY ANALYTICAL DATA AND CHAIN OF CUSTODY FORM(S)



**EMSL** Analytical, Inc. 5125 Adanson Street, Suite 900, Orlando, FL 32804 Phone/Fax: (407) 599-5887 / (407) 599-9063 orla

EMSL Order: 341504828 CustomerID: SHAW77C CustomerPO: DroigotID

				)
Attn:	Shawn Flynn	Phone:	(407) 287-3200	
	Shaw/CB&I	Fax:		
	1228 Winter Garden Vineland Rd	Received:	05/18/15 11:00 AM	
		Analysis Date:	5/19/2015	
	Winter Garden, FL 34787	Collected:	E/12/201E	

5/13/2015

Collected:

Project: 154316/Bridge 1700022

# Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using **Polarized Light Microscopy**

			Non-Asi	<u>Asbestos</u>	
Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Type
1-1	Support Piles -	Gray/White		45% Quartz	None Detected
341504828-0001	Concrete	Non-Fibrous		10% Ca Carbonate	
		Heterogeneous		45% Non-fibrous (other)	
1-2	Support Piles -	Gray/Tan/White	<1% Cellulose	45% Quartz	None Detected
341504828-0002	Concrete	Fibrous	<1% Synthetic	10% Ca Carbonate	
		Heterogeneous		45% Non-fibrous (other)	
1-3	Support Piles -	Gray/White		40% Quartz	None Detected
341504828-0003	Concrete	Non-Fibrous		20% Ca Carbonate	
		Heterogeneous		40% Non-fibrous (other)	
2-1	Bent Caps -	Gray/Tan		40% Quartz	None Detected
341504828-0004	Concrete	Non-Fibrous		5% Ca Carbonate	
		Heterogeneous		55% Non-fibrous (other)	
2-2	Bent Caps -	Gray	<1% Cellulose	55% Quartz	None Detected
341504828-0005	Concrete	Non-Fibrous		10% Ca Carbonate	
		Heterogeneous		35% Non-fibrous (other)	
2-3	Bent Caps -	Gray		55% Quartz	None Detected
341504828-0006	Concrete	Non-Fibrous		10% Ca Carbonate	
		Heterogeneous		35% Non-fibrous (other)	
3-1	Sea Wall -	Gray/Tan		50% Quartz	None Detected
341504828-0007	Concrete	Non-Fibrous		10% Ca Carbonate	
		Heterogeneous		40% Non-fibrous (other)	

Analyst(s)

Lindsay Karashay (22) Manolo Hernandez (44)

Jonathan Teda, Asbestos Lab Manager or other approved signatory

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by N/LAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. Reporting limit is 1% Samples analyzed by EMSL Analytical, Inc. Orlando, FL NVLAP Lab Code 101151-0



Project: 154316/Bridge 1700022

EMSL Analytical, Inc. 5125 Adanson Street, Suite 900, Orlando, FL 32804 Phone/Fax: (407) 599-5887 / (407) 599-9063 http://www.EMSL.com orlandolab@emsl.com EMSL Order: 341504828 CustomerID: SHAW77C CustomerPO: ProjectID:

Attn:	Shawn Flynn	Phone:	(407) 287-3200
	Shaw/CB&I	Fax:	
	1228 Winter Garden Vineland Rd	Received:	05/18/15 11:00 AM
	Winter Garden, FL 34787	Analysis Date:	5/19/2015
	winter Garden, FL 34/6/	Collected:	5/13/2015

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

			Non-Ast	estos	<u>Asbestos</u>
Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Type
3-2	Sea Wall -	Gray/Tan/White	<1% Synthetic	55% Quartz	None Detected
341504828-0008	Concrete	Fibrous		10% Ca Carbonate	
		Heterogeneous		35% Non-fibrous (other)	
3-3	Sea Wall -	Gray/White		50% Quartz	None Detected
341504828-0009	Concrete	Non-Fibrous		25% Ca Carbonate	
		Heterogeneous		25% Non-fibrous (other)	
4-1	Abutment Wall -	Gray		50% Quartz	None Detected
341504828-0010	Concrete	Non-Fibrous		10% Ca Carbonate	
		Heterogeneous		40% Non-fibrous (other)	
4-2	Abutment Wall -	Gray		55% Quartz	None Detected
341504828-0011	Concrete	Non-Fibrous		10% Ca Carbonate	
		Heterogeneous		35% Non-fibrous (other)	
4-3	Abutment Wall -	Gray/Tan		60% Quartz	None Detected
341504828-0012	Concrete	Norr ibroad	10% Ca Carbonate		
		Heterogeneous		30% Non-fibrous (other)	
5-1	Abutment Wall -	Gray		50% Quartz	None Detected
341504828-0013	Mortar	Non-Fibrous		10% Ca Carbonate	
		Heterogeneous		40% Non-fibrous (other)	
5-2	Abutment Wall -	Gray	<1% Cellulose	55% Quartz	None Detected
341504828-0014	Mortar	Non-Fibrous		10% Ca Carbonate	
		Heterogeneous		35% Non-fibrous (other)	

Analyst(s)

Lindsay Karashay (22) Manolo Hernandez (44)

Jonathan Teda, Asbestos Lab Manager or other approved signatory

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. Reporting limit is 1% Samples analyzed by EMSL Analytical, Inc. Orlando, FL NVLAP Lab Code 101151-0



EMSL Analytical, Inc. 5125 Adanson Street, Suite 900, Orlando, FL 32804 Phone/Fax: (407) 599-5887 / (407) 599-9063 http://www.EMSL.com orlandolab@emsl.com EMSL Order: 34150 CustomerID: SHAV CustomerPO: ProjectID:

341504828
SHAW77C

Attn:	Shawn Flynn Shaw/CB&I 1228 Winter Garden Vineland Rd Winter Garden, FL 34787	Phone: Fax: Received: Analysis Date: Collected:	(407) 287-3200 05/18/15 11:00 AM 5/19/2015 5/13/2015
-------	---	---	---

Project: 154316/Bridge 1700022

# Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

			Non-As	bestos	<u>Asbestos</u>
ample	Description	Appearance	% Fibrous	% Non-Fibrous	% Type
5-3	Abutment Wall -	Gray		50% Quartz	None Detected
341504828-0015	Mortar	Non-Fibrous		10% Ca Carbonate	
		Heterogeneous		40% Non-fibrous (other)	
6-1	End Bent -	Gray		50% Quartz	None Detected
341504828-0016	Concrete	Non-Fibrous		10% Ca Carbonate	
		Heterogeneous		40% Non-fibrous (other)	
6-2	End Bent -	Gray		50% Quartz	None Detected
341504828-0017	Concrete	Non-Fibrous		10% Ca Carbonate	
		Heterogeneous		40% Non-fibrous (other)	
6-3	End Bent -	Gray/White		50% Quartz	None Detected
341504828-0018	Concrete	Non-Fibrous		15% Ca Carbonate	
		Heterogeneous		35% Non-fibrous (other)	
7-1	Diaphram -	Gray/Tan	<1% Cellulose	55% Quartz	None Detected
341504828-0019	Concrete		Non-Fibrous	10% Ca Carbonate	
		Heterogeneous		35% Non-fibrous (other)	
7-2	Diaphram -	Gray/Tan/White	<1% Cellulose	50% Quartz	None Detected
341504828-0020	Concrete	Fibrous		10% Ca Carbonate	
		Heterogeneous		40% Non-fibrous (other)	
7-3	Diaphram -	Gray/White		40% Quartz	None Detected
341504828-0021	Concrete	Non-Fibrous		30% Ca Carbonate	
		Heterogeneous		30% Non-fibrous (other)	

Analyst(s)

Lindsay Karashay (22) Manolo Hernandez (44)

1

Jonathan Teda, Asbestos Lab Manager or other approved signatory

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. Reporting limit is 1% Samples analyzed by EMSL Analytical, Inc. Orlando, FL NVLAP Lab Code 101151-0



EMSL Analytical, Inc. 5125 Adanson Street, Suite 900, Orlando, FL 32804 Phone/Fax: (407) 599-5887 / (407) 599-9063 http://www.EMSL.com orlandolab@emsl.com EMSL Order: 341504828 CustomerID: SHAW77C CustomerPO: ProjectID:

Attn:	Shawn Flynn	Phone: Fax:	(407) 287-3200	
	Shaw/CB&I 1228 Winter Garden Vineland Rd	Received:	05/18/15 11:00 AM	
-	Winter Garden, FL 34787	Analysis Date:	5/19/2015	
	Winter Garden, i E 54767	Collected:	5/13/2015	

Project: 154316/Bridge 1700022

# Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

				Non-Ast	<u>bestos</u>	<u>Asbestos</u>
Sample	Description	Appearance	%	Fibrous	% Non-Fibrous	% Type
8-1	Bearing Pads-	Black	5%	Cellulose	95% Non-fibrous (other)	None Detected
341504828-0022	Subgliders - Asphalt Paper	Fibrous Homogeneous				
8-2	Bearing Pads-	Black	5%	Cellulose	95% Non-fibrous (other)	None Detected
341504828-0023	Subgliders - Asphalt Paper	Fibrous Homogeneous				
8-3	Bearing Pads-	Brown/Black	5%	Cellulose	95% Non-fibrous (other)	None Detected
341504828-0024	Subgliders -	Fibrous Homogeneous				
9-1	Gliders - Concrete	Gray/Tan	<1%	Cellulose	50% Quartz	None Detected
341504828-0025		Non-Fibrous			10% Ca Carbonate	
		Heterogeneous			40% Non-fibrous (other)	
9-2	Gliders - Concrete	Gray/Tan	<1%	Cellulose	50% Quartz	None Detected
341504828-0026		Non-Fibrous			10% Ca Carbonate	
		Heterogeneous			40% Non-fibrous (other)	
9-3	Gliders - Concrete	Gray/W hite			50% Quartz	None Detected
341504828-0027		Non-Fibrous			15% Ca Carbonate	
		Heterogeneous			35% Non-fibrous (other)	
10-1	Gliders - Mortar	Gray/W hite			45% Quartz	None Detected
341504828-0028		Non-Fibrous			15% Ca Carbonate	
		Heterogeneous			40% Non-fibrous (other)	

Analyst(s)

Lindsay Karashay (22) Manolo Hernandez (44)

Jonathan Teda, Asbestos Lab Manager or other approved signatory

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. Reporting limit is 1% Samples analyzed by EMSL Analytical, Inc. Orlando, FL NVLAP Lab Code 101151-0



Attn: Shawn Flyn Shaw/CB&I

**EMSL** Analytical, Inc. 5125 Adanson Street, Suite 900, Orlando, FL 32804 (407) 599-5887 / (407) 599-9063 Phone/Fax:

EMSL Order: 341504828 CustomerID: SHAW77C CustomerPO:

	http://www.EMSL.com	orlandolab@emsl.com	ProjectID:	)
Shawn F	lynn	Phone:	(407) 287-3200	
Shaw/CE	•	Fax:		
1228 Wir	nter Garden Vineland	Rd Received:	05/18/15 11:00 AM	

5/19/2015

5/13/2015

Analysis Date:

Collected:

Project: 154316/Bridge 1700022

Winter Garden, FL 34787

# Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using **Polarized Light Microscopy**

			Non-Ast	pestos	<u>Asbestos</u>
Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Type
10-2	Gliders - Mortar	Gray		55% Quartz	None Detected
341504828-0029		Non-Fibrous		10% Ca Carbonate	
		Heterogeneous		35% Non-fibrous (other)	
10-3	Gliders - Mortar	Gray		50% Quartz	None Detected
341504828-0030		Non-Fibrous		10% Ca Carbonate	
		Homogeneous		40% Non-fibrous (other)	
11-1	Bearing Pads-	Black	30% Cellulose	70% Non-fibrous (other)	None Detected
341504828-0031	Subdeck - Asphalt Paper	Fibrous Homogeneous			
11-2	Bearing Pads- Subdeck - Asphalt Paper	Black	30% Cellulose	70% Non-fibrous (other)	None Detected
341504828-0032		Fibrous Homogeneous			
11-3	Bearing Pads-	Brown/Black	40% Cellulose	60% Non-fibrous (other)	None Detected
341504828-0033	Subdeck - Asphalt Paper	Fibrous Homogeneous			
12-1	Expansion Joints -	Gray/Black		100% Non-fibrous (other)	None Detected
341504828-0034	Black Rubber	Non-Fibrous Homogeneous			
12-2	Expansion Joints -	Gray/Black		100% Non-fibrous (other)	None Detected
341504828-0035	Black Rubber	Non-Fibrous Homogeneous			
12-3	Expansion Joints -	Gray/Black		100% Non-fibrous (other)	None Detected
341504828-0036	Black Rubber	Non-Fibrous Heterogeneous			

Analyst(s)

Lindsay Karashay (22) Manolo Hernandez (44)

Jonathan Teda, Asbestos Lab Manager or other approved signatory

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by N/LAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. Reporting limit is 1% Samples analyzed by EMSL Analytical, Inc. Orlando, FL NVLAP Lab Code 101151-0



Attn:

EMSL Analytical, Inc. 5125 Adanson Street, Suite 900, Orlando, FL 32804 Phone/Fax: (407) 599-5887 / (407) 599-9063 http://www.EMSL.com orlandolab@emsl.com EMSL Order: 341504828 CustomerID: SHAW77C CustomerPO: ProjectID:

Shawn Flynn	Phone: Fax:	(407) 287-3200
Shaw/CB&I 1228 Winter Garden Vineland Rd	Received: Analysis Date:	05/18/15 11:00 AM 5/19/2015
Winter Garden, FL 34787	Collected:	5/13/2015

Project: 154316/Bridge 1700022

#### Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

			Non-As	bestos	Asbestos	
Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Type	
13-1	Railing-Rail -	Gray/Tan		55% Quartz	None Detected	
341504828-0037	Concrete	Non-Fibrous		10% Ca Carbonate		
Ηε	Heterogeneous		35% Non-fibrous (other)			
13-2	Railing-Rail -	Gray/Tan		55% Quartz	None Detected	
341504828-0038	Concrete	Non-Fibrous		10% Ca Carbonate		
		Heterogeneous		35% Non-fibrous (other)		
13-3	Railing-Rail -	Gray/White		50% Quartz	None Detected	
341504828-0039	Concrete	Non-Fibrous		25% Ca Carbonate		
		Heterogeneous		25% Non-fibrous (other)		
14-1	End Cap -	Gray/Tan		50% Quartz	None Detected	
341504828-0040	Concrete	Non-Fibrous Heterogeneous		10% Ca Carbonate		
				40% Non-fibrous (other)		
14-2	End Cap -	Gray/Tan		50% Quartz	None Detected	
341504828-0041	Concrete	Non-Fibrous		10% Ca Carbonate		
		Heterogeneous		40% Non-fibrous (other)		
14-3	End Cap -	Gray/White		50% Quartz	None Detected	
341504828-0042	Concrete	Non-Fibrous		20% Ca Carbonate		
		Heterogeneous		30% Non-fibrous (other)		
15-1	Curb - Concrete	Gray/Tan	<1% Cellulose	50% Quartz	None Detected	
341504828-0043		Non-Fibrous		10% Ca Carbonate		
		Heterogeneous		40% Non-fibrous (other)		

Analyst(s)

Lindsay Karashay (22) Manolo Hernandez (44)

Jonathan Teda, Asbestos Lab Manager or other approved signatory

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. Reporting limit is 1% Samples analyzed by EMSL Analytical, Inc. Orlando, FL NVLAP Lab Code 101151-0



At

EMSL Analytical, Inc. 5125 Adanson Street, Suite 900, Orlando, FL 32804 Phone/Fax: (407) 599-5887 / (407) 599-9063 http://www.EMSL.com orlandolab@emsl.com EMSL Order: 341504828 CustomerID: SHAW77C CustomerPO: ProjectID:

tn:	Shawn Flynn	Phone:	(407) 287-3200
	Shaw/CB&I	Fax:	
	1228 Winter Garden Vineland Rd	Received:	05/18/15 11:00 AM
	Winter Garden, FL 34787	Analysis Date:	5/19/2015
Winter Garden, FL 54/6/	Winter Garden, FL 34707	Collected:	5/13/2015

Project: 154316/Bridge 1700022

#### Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

		Non-Ast	<u>Asbestos</u>		
Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Type
15-2	Curb - Concrete	Gray/Tan	<1% Cellulose	50% Quartz	None Detected
341504828-0044		Non-Fibrous		10% Ca Carbonate	
		Heterogeneous		40% Non-fibrous (other)	
15-3	Curb - Concrete	Gray		45% Quartz	None Detected
341504828-0045		Non-Fibrous		25% Ca Carbonate	
		Homogeneous		30% Non-fibrous (other)	
16-1	Deck - Concrete	Gray/Tan/White		50% Quartz	None Detected
341504828-0046		Non-Fibrous		15% Ca Carbonate	
		Heterogeneous		35% Non-fibrous (other)	
16-2	Deck - Concrete	Gray/Tan	<1% Cellulose	40% Quartz	None Detected
341504828-0047		Non-Fibrous		15% Ca Carbonate	
		Heterogeneous		45% Non-fibrous (other)	
16-3	Deck - Concrete	Gray/White		55% Quartz	None Detected
341504828-0048		Non-Fibrous		10% Ca Carbonate	
		Heterogeneous		35% Non-fibrous (other)	
17-1	Railing Post -	Gray/Tan/White		45% Quartz	None Detected
341504828-0049	Concrete	Non-Fibrous		15% Ca Carbonate	
		Heterogeneous		40% Non-fibrous (other)	
17-2	Railing Post -	Gray/Tan/White		45% Quartz	None Detected
341504828-0050	Concrete	Non-Fibrous		15% Ca Carbonate	
		Heterogeneous		40% Non-fibrous (other)	

Analyst(s)

Lindsay Karashay (22) Manolo Hernandez (44)

Jonathan Teda, Asbestos Lab Manager or other approved signatory

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. Reporting limit is 1% Samples analyzed by EMSL Analytical, Inc. Orlando, FL NVLAP Lab Code 101151-0



EMSL Analytical, Inc. 5125 Adanson Street, Suite 900, Orlando, FL 32804 Phone/Fax: (407) 599-5887 / (407) 599-9063 http://www.EMSL.com orlandolab@emsl.com EMSL Order: 34150 CustomerID: SHAV CustomerPO: ProjectID:

341504828 SHAW77C

Attn:	Shawn Flynn Shaw/CB&I 1228 Winter Garden Vineland Rd Winter Garden, FL 34787	Phone: Fax: Received: Analysis Date: Collected:	(407) 287-3200 05/18/15 11:00 AM 5/19/2015 5/13/2015
-------	---	---	---

Project: 154316/Bridge 1700022

#### Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

			Non-As	<u>Asbestos</u>	
Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Type
17-3	Railing Post -	Gray/W hite		45% Quartz	None Detected
341504828-0051	Concrete	Non-Fibrous		15% Ca Carbonate	
		Heterogeneous		40% Non-fibrous (other)	
18-1	Deck - Mortar	Gray		45% Quartz	None Detected
341504828-0052		Non-Fibrous		10% Ca Carbonate	
		Heterogeneous		45% Non-fibrous (other)	
			Inseparable paint / coating lay	er included in analysis	
18-2	Deck - Mortar	Gray		55% Quartz	None Detected
341504828-0053		Non-Fibrous		10% Ca Carbonate	
		Heterogeneous		35% Non-fibrous (other)	
18-3	Deck - Mortar	Gray		45% Quartz	None Detected
341504828-0054		Non-Fibrous		15% Ca Carbonate	
		Homogeneous		40% Non-fibrous (other)	
19-1	Reflector - Black	Black		100% Non-fibrous (other)	None Detected
341504828-0055	Adhesive Mastic	Non-Fibrous Homogeneous			
19-2	Reflector - Black	Black		100% Non-fibrous (other)	None Detected
341504828-0056	Adhesive Mastic	Non-Fibrous Homogeneous			
19-3	Reflector - Black	Black		100% Non-fibrous (other)	None Detected
341504828-0057	Adhesive Mastic	Non-Fibrous Homogeneous			

Analyst(s)

Lindsay Karashay (22) Manolo Hernandez (44)

Jonathan Teda, Asbestos Lab Manager or other approved signatory

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. Reporting limit is 1% Samples analyzed by EMSL Analytical, Inc. Orlando, FL NVLAP Lab Code 101151-0



**EMSL** Analytical, Inc. 5125 Adanson Street, Suite 900, Orlando, FL 32804 (407) 599-5887 / (407) 599-9063 Phone/Fax: http://www.EMSL.com orlandolab@emsl.com EMSL Order: CustomerID: CustomerPO: ProjectID:

341504828
SHAW77C

Attn:	Shawn Flynn Shaw/CB&I	Phone: Fax:	(407) 287-3200
	1228 Winter Garden Vineland Rd Winter Garden, FL 34787	Received: Analysis Date: Collected:	05/18/15 11:00 AM 5/19/2015 5/13/2015

Project: 154316/Bridge 1700022

#### Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using **Polarized Light Microscopy**

				Non-As	bestos	Asbestos
Sample	Description	Appearance	% Fi	brous	% Non-Fibrous	% Type
20-1	Class 5 Coating -	White			100% Non-fibrous (other)	None Detected
341504828-0058	Class 5 Coating	Non-Fibrous Homogeneous				
20-2	Class 5 Coating -	White			100% Non-fibrous (other)	None Detected
341504828-0059	Class 5 Coating	Non-Fibrous Homogeneous				
20-3	Class 5 Coating -	White			100% Non-fibrous (other)	None Detected
341504828-0060	Class 5 Coating	Non-Fibrous Homogeneous				
21-1	Support Pile Protective Casing - Fiberglass	Gray	25% (	Glass	25% Quartz	None Detected
341504828-0061		Fibrous Heterogeneous			50% Non-fibrous (other)	
21-2	Support Pile	Gray/White	35% (	Glass	65% Non-fibrous (other)	None Detected
341504828-0062	Protective Casing - Fiberglass	Fibrous Homogeneous				
			Inseparable p	aint / coating lay	er included in analysis	
21-3	Support Pile	White/Yellow	30% (	Glass	70% Non-fibrous (other)	None Detected
341504828-0063	Protective Casing - Fiberglass	Fibrous Heterogeneous				
			Inseparable p	aint / coating lay	er included in analysis	
22-1	Support Pile	Gray			40% Quartz	None Detected
341504828-0064	Protective Casing - Sealant				5% Ca Carbonate	
	Sealant	Heterogeneous			55% Non-fibrous (other)	

Analyst(s)

Lindsay Karashay (22) Manolo Hernandez (44)

Jonathan Teda, Asbestos Lab Manager or other approved signatory

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. Reporting limit is 1% Samples analyzed by EMSL Analytical, Inc. Orlando, FL NVLAP Lab Code 101151-0



EMSL Analytical, Inc. 5125 Adanson Street, Suite 900, Orlando, FL 32804 Phone/Fax: (407) 599-5887 / (407) 599-9063 http://www.EMSL.com orlandolab@emsl.com EMSL Order: 341504828 CustomerID: SHAW77C CustomerPO: ProjectID:

Attn:	Shawn Flynn Shaw/CB&I 1228 Winter Garden Vineland Rd Winter Garden, FL 34787	Phone: Fax: Received: Analysis Date: Collected:	(407) 287-3200 05/18/15 11:00 AM 5/19/2015 5/13/2015	
-------	---	---	---	--

Project: 154316/Bridge 1700022

#### Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

			Non-Asbestos			Asbestos	
Sample	Description	Appearance	%	Fibrous	% Non-Fibrous	% Type	
22-2	Support Pile	Gray			40% Quartz	None Detected	
341504828-0065	Protective Casing -				5% Ca Carbonate		
0110010200000	Sealant	Heterogeneous			55% Non-fibrous (other)		
22-3	Support Pile	Gray			35% Quartz	None Detected	
341504828-0066	Protective Casing -				5% Ca Carbonate		
	Sealant	Homogeneous			60% Non-fibrous (other)		

Analyst(s)

Lindsay Karashay (22) Manolo Hernandez (44)

Jonathan Teda, Asbestos Lab Manager or other approved signatory

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. Reporting limit is 1% Samples analyzed by EMSL Analytical, Inc. Orlando, FL NVLAP Lab Code 101151-0

EN	15L	Asbestos Bulk I Chain of	Building Mat Custody	terial	EMSL ANALYTICAL, INC. 200 ROUTE 130 NORTH CINNAMINSON, NJ 08077
EMSL ANAL			mber (Lab Use O	n/y):	PHONE: (800) 220-3675 FAX. (856) 786-5974
		391304	828		
Company :	: ((	39-1		EMSL-Bill to: Sal Bill to is Different note instri	
		In ter Garden Vineland Rd			authorization from third party
	-, ,	Garden State/Province: FL Sharyn FLYNN	Zip/Postal Code Telephone #:	<u>: 34787 0</u> 407-217.3200	Country: US &
		Shawn, Flynnechi, com	Fax #: 407~7		Purchase Order:
Project Na U.S. State	me/Num	ber: 1543161 Bridge 17000 252	Please Provide	Results: 🔲 Fax	Email Ne 🛄 Residential/Tax Exempt
0.5. State	Samples	Turnaround Time (T	AT) Options* - Ple		
3 Hour     *For TEM An		6 Hour 24 Hour 48 Hour gh 6 hr, please call ahead to schedule. *There is a pr		IT BE AND A STATE IN THE AND A STATE AND A	1 Week     2 Week     evel II TAT You will be asked to sign
	uthorizatioi	form for this service. Analysis completed in accord A - Bulk (reporting limit)			d in the Analytical Price Guide.
PLM EP		93/116 (<1%)		- EPA 600/R-93/116	<b></b>
		<1%) <b>{&lt;</b> 0.25%) 🔲 1000 (<0.1%)	NY ELAP Meth		
L		metric 🔲 400 (<0.25%) 🛄 1000 (<0.1%)		col (semi-quantitative s – EPA 600/R-93/11	•
	9002 (<*	%)	······································	via Filtration Prep T	
		d 198.1 (friable in NY) d 198.6 NOB (non-friable-NY)	TEM Qualitative	via Drop Mount Pre Other	p Technique
	ID-191 M	······································			
🔲 Standa	rd Additio	on Method			
🗌 Check i	For Posi	tive Stop – Clearly Identify Homogenous	Group Date Sam	pled: 5/13+14/	2015
Samplers	Name:	Thomas Gragory/Daniel Roeb	Samplers Sig	inature: ) V >	<u> </u>
Sample #	HA #	Sample Location		Mate	/ erial Description
1-1	1	support piles	<u> </u>	convete	<u></u>
1-2	<u> </u>	puppert oily		concrete.	
1-3	1	suppor piles		concrete	
2-1	2	Bent caps		Convert	
2-2	2	Bent caps	I	concrete	
2-3	2	Bent caps.		concrete	
3-1	3	aluson sea wall		convite	
3-2	3	about there wall		convete	
3-3	3	alvertrageotsea wall		convete	
4-1	4	abutment wall		concrite	· · · · · · · · · · · · · · · · · · ·
Client Sam	nple # (s)	: III - 1.1 -	22.3		Samples: 66
Relinquish	ned (Clie	nt): Dat	e:		Time:
Received (		ass Elek Dat	e: <u>5-18-</u>	15	Time: 11am
Comments	s/Specia	Instructions			

Controlled Document - Asbestos COC - R6 - 11/29/2012

Page 1 of \_\_\_\_ pages



#### Asbestos Bulk Building Material Chain of Custody

EMSL Order Number (Lab Use Only):

EMSL ANALYTICAL, INC. 200 ROUTE 130 NORTH CINNAMINSON, NJ 08077 PHONE. (800) 220-3675 FAX. (856) 786-5974

341504828

Additional Pages of the Chain of Custody are only necessary if needed for additional sample information

Sample #	HA #	Sample Location	Material Description
42	4	abutment wall	concrete
4.3	4	abutment well	concrite
5-1	5	abutment wall	morter
5.2	S	abritment wall	month
5.3	5	abutment wall	motel
6-1	6	End bent	concrete
6.2	6	End bint	Concette
63	6	End bint	concrete
7-1	7	Disphram	concrete
7.2	1	Disphran	concette
7.3	1	Disphan	concrete
8-1	8		apphalt paper
8-Z	8	Bearing pads-subgirder Bearing pads-subgirder	asphalt paper
8-3	8	Bearing pado-Sulgide	asphalt paper
9-1	9	gudes	condicte
9-2	9	girders	concrete
9-3	9	girdes	concrete
10-1	10	anders	mater
10.2	10	girden	morter
10-3	lo	kindus	montel
11-1	11	Bearing pads - subdeck	asphalt paper
[1-2	$\mathbf{N}$	Bearine pads-subdeck	apphalt paper
(1-3	η	-Rearing pado-suldick	apphalt paper
(2-1	12	Certranson jane	black rulber
"Commen	ts/Speci	al Instructions: ()	•

Page \_\_\_\_\_ of \_\_\_\_\_ pages



#### Asbestos Bulk Building Material Chain of Custody

EMSL Order Number (Lab Use Only):

EMSL ANALYTICAL, INC. 200 ROUTE 130 NORTH CINNAMINSON, NJ 08077 PHONE: (800) 220-3675

FAX. (856) 786-5974

341504828

Additional Pages of the Chain of Custody are only necessary if needed for additional sample information

Sample #	<u>HA #</u>	Sample Location	Material Description
12.2	12	Expansion joint	black rubber
12:3	p	Expansion joint	black rubber black rubber
13-1	13	Railing - Mail	concrete
13-2	B	Railing - Nail	conorete
13.3	13	Railing-nail	concrete
14.1	М	Gid cap	converte
14.2	М	End cap	condite
14.3	14	End cap	concrete,
15.1	15	curb	Consiste
15.2	15	curb	concrete
15.3	15	curt	concrete
16.1	16	Back	Concrete
16.2	N	Dich	concrete
16.3	4	Dech	womerete
17.1	17	Railing-prot	Concrete
17.2	17	Railing post	convett
17.3	רי	Rauling post	concrete
18.1	18	Duck	morter
11-2	18	Deck	morter
18-3	18	Dech	mater
19.1	19	reflector	Black adhesive mastic
19.2	19	reflector	Black adhesive martic Black adhesive Mart
19.3	19	refireto	Black adhesive Maste
20-1	20	Less 5 wating	class 5 cotting
*Commer	nts/Spec	ial Instructions:	

Page \_\_\_\_\_ of \_\_\_\_ pages



#### Asbestos Bulk Building Material Chain of Custody

EMSL ANALYTICAL, INC. 200 ROUTE 130 NORTH CINNAMINSON, NJ 08077

EMSL Order Number (Lab Use Only):

PHONE: (800) 220-3675 FAX: (856) 786-5974

34	1504828

Additional Pages of the Chain of Custody are only necessary if needed for additional sample information

Sample #	HA #	Sample Location	Material Description
20.2	20	Class & Conting	chass 5 contra
20.3	20	closs 5. coaling	class 5 coating
21.1	11	support pile protective casine	Libralas
21.2	2	support pile parolective castrig support pileprotective castrig	filinglad
21-3	21	support alterprotective cashing	file glass
22.1	22	support pile protective casing	sealant
22.2	22	support sile protective casing	pialant
22.3	22	support pile protective casing	sealant
!			
*Commer	nts/Spec	ial Instructions:	

Page \_\_\_\_\_ of \_\_\_\_ pages

#### QUALITY ASSURANCE SAMPLING

QA/QC sampling was performed in accordance with the State of Florida Asbestos Survey Procedure Manual. Two QA/QC samples (sample No. 6.4 QA/QC, No. 12.4 QA/QC, No. 18.4 QA/AC and No. 21.4 QA/QC) were collected next to sample No. 6.3 and No. 12.3, No. 18.3 and No. 21.3 respectively. Laboratory analyses indicated that these QA/QC samples did not contain asbestos.



## **CERTIFICATE OF ANALYSIS**

**Client:** Shaw Environmental Inc(CBI Co) 1228 Winter Garden Vineland Rd

> Winter Garden FL 34787

<b>Report Date:</b>	5/23/2015
Report No.:	363772
Project:	Bridge 170022
Project No.:	154316

#### **BULK SAMPLE ANALYSIS SUMMARY**

Lab No.: Client No.:	5629285 6-4QA/QC	Description / Location:	White/Grey Cementitious End Bent	
<u>% Asbestos</u>	Type	% Non-Asbestos Fibrous	Material Type	% Non-Fibrous Material
None Detected	None Detected	None Detected	None Detected	100
Lab No.:	5629286	Description / Location:	Grey Rubber	
Client No.:	12-4QA/QC		Expansion Joint	
<u>% Asbestos</u>	Type	% Non-Asbestos Fibrous	Material Type	% Non-Fibrous Material
None Detected	None Detected	None Detected	None Detected	100
Lab No.:	5629287	Description / Location:	Grey Cementitious	
Client No.:	18-4QA/QC		Deck	
<u>% Asbestos</u>	Type	% Non-Asbestos Fibrous	Material Type	% Non-Fibrous Material
None Detected	None Detected	None Detected	None Detected	100
Lab No.:	5629288	Description / Location:	White Fibrous	
Client No.:	21-4QA/QC	<b>r</b>	Support Pile Protective Case	
<u>% Asbestos</u>	Type	% Non-Asbestos Fibrous	Material Type	% Non-Fibrous Material
None Detected	None Detected	90	Fibrous Glass	10
Accreditations:	NIST-NVLA	P No. 101165-0 NY	7-DOH No. 11021	AIHA-LAP, LLC No. 100188

	This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP, AIHA or any agency of the U.S. government This report shall not be reproduced except in full, without written approval of the laboratory.					
Analytical Method: US EPA 600/R-93/116 by Polarized Light Microscopy, (ELAP 198.1 where applicable)						
Comments:	quantifiable under the present or the client h of the optical microsc	at <0.25% by volume is possible with this method. (PC) Indicates Stratified Point Count Method performed. (PC-Trace) means that asbestos was detected but is not der the Point Counting regimen. Analysis includes all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not lient has specifically requested that it not be analyzed (ex. analyze until positive instructions). Small asbestos fibers may be missed by PLM due to resolution limitations nicroscope. Therefore, PLM is not consistently reliable in detecting asbestos in non-friable organically bound (NOB) materials. Quantitative transmission electron EM) is currently the only method that can pronounce materials as non-asbestos containing.				
Analysis P	erformed By:	D. Jao	Approved By:	Fre English		
Date:	5/23/2015		Page 1 of 1	Frank E. Ehrenfeld, III Laboratory Director		



9000 Commerce Parkway, Suite B • Mount Laurel, NJ 08054 Phone: 877-428-4285/856-231-9449 • Fax: 856-231-9818

.

# **Chain of Custody**

-Bulk Asbestos -

Contact Informa	ation				
Client Company:	CB&I	<b>Project Number:</b>	154316		
Office Address:	1228 Winter Garden Vineland Rd	<b>Project Name:</b>	Bridge MOOZZ		
City, State, Zip:	Orlando, FL 34787	<b>Primary Contact:</b>	Shawn Flynn		
Fax Number:	407-287-3201	<b>Office Phone:</b>	407-287-3200		
Email Address:	shawn.flynn@cbi.com	Cell Phone:	407-832-3072		
PLM Instructions:       CCH FIGHT. [07 COL 2071]         PLM: Bulk Asbestos Building Materials EPA 600 R-93/116, 1993       PLM: Bulk Asbestos Building Materials EPA 600 M-4/82-020, 1982         PLM: Bulk Asbestos Building Materials NIOSH 9002, 1985       PLM: Bulk Asbestos Building Materials NYSDOH-ELAP 198.1, 2002         PLM: Bulk Asbestos Building Materials NYSDOH-ELAP 198.6, 2010       PLM: Bulk Asbestos Building Materials NYSDOH-ELAP 198.4, 2009         PLM: Point Counting       PLM: Analyze Until Positive (Positive Stop)         PC: via ELAP 198.1       AUP: by Homogenous Area as Noted         PC: via ELAP 198.1       AUP: by Material Type as Noted         PC: 800 Points *       PLM: NOB via 198.6         PC: 1600 Points *       PLM: Friable via EPA 600 2.3         PLM: Instructions for Multi-Layered Samples       If <1% by PLM, to TEM via 198.4 *         PLM: Instructions for Multi-Layered Samples       Soil or Vermiculite Analysis         Conly Analyze and Report All Separable Layers per EPA 600       Soil or Vermiculite Analysis         Conly Analyze and Report Specifically Noted Layer       Soil or Vermiculite Analysis         Special Instructions:       CARB 435					
* Additional cha	arge and turnaround may be required <b>**</b> Alte	rnative Method (ex: EPA 600/R-04/	/004) may be recommended by Laboratory		
Turnaround Time         Preliminary Results Requested Date:					
Chain of Custod Relinguished (Name/O		Deter for long	Time: 1100		
Received (Name / iAT			Time:		
Sample Login (Name	/ iATL):	Date:	Time:		
Analysis(Name(s) / iA QA/QC Review (Nam			Time:		
Archived / Released: _			Time: Time:		
MA	· · · · ·				



## Sample Log -Bulk Asbestos -

Client: CB&I

Project: 154316/ Bridge, 170022 \_\_\_

Sampling Date/Time: MAY 12 +13 2015

Bulk Asbestos Sample Log				
Client Sample #	iATL #	Location/Description	Notes	
6.4 QA/QC		End bent - concrete		
12-4 QA/QC 18-4 QA/QC 21-4 QA/QC		Expansion joints - black cu	ubber	
18.4 QA/QC		Deck-morter		
21.4 QA/QC		End bent - concrete Expansion joints - blackru Deck - morter Support pilling protective (	asing	
			5	

IATL - 2 -Submit Form

#### **SECTION 5**

#### CREDENTIALS FOR CONSULTANT, INSPECTOR, AND LABORATORY

License Ty	pe Name		Name Type	License Number/ Rank	Status/Expires
Asbestos Business	CB&I ENVIRONMENTAL INFRASTRUCTUR INC.		Primary	ZA317 Asbsts Business	Current 11/30/2015
Address*:	License Location	9143 7460		GHWAY JACKSO	NVILLE, FL 32256-
	Main Address*:	ain Address*: 4171 f		71 ESSEN LANE BATON ROUGE, LA 70809	
Asbestos Business	DAVID WARNER MOSHER	2	DBA	ZA317 Asbsts Business	Current 11/30/2015
Address*:	License Location	9143 7460		SHWAY JACKSO	NVILLE, FL 32256-
			171 ESSEN LANE BATON ROUGE, LA 70809		

 RICK SCOTT, GOVERNOR
 STATE OF FLORIDA DEPARTMENTORISINESS AND PROFIDE DEPARTMENTORISING OF DEPARTMENT


 DEPARTMENTORISING
 DEPARTMENT

 DEPARTMENTORISING
 DEPARTMENT

 DEPARTMENTORISING
 DEPARTMENT







.



#### National Voluntary Laboratory Accreditation Program



#### SCOPE OF ACCREDITATION TO ISO/IEC 17025:2005

EMSL Analytical, Inc. 5125 Adanson Street, Suite 900 Orlando, FL 32804 Dr. Blanca Cortes Phone: 407-599-5887 Fax: 407-599-9063 E-Mail: bcortes@emsl.com URL: http://www.emsl.com

#### BULK ASBESTOS FIBER ANALYSIS (PLM)

#### NVLAP LAB CODE 101151-0

 NVLAP Code
 Designation / Description

 18/A01
 EPA 600/M4-82-020; Interim Method for the Determination of Asbestos in Bulk Insulation Samples

 18/A03
 EPA 600/R-93/116; Method for the Determination of Asbestos in Bulk Building Materials


2014-07-01 through 2015-06-30

Effective dates

Main R. Mal

For the National Institute of Standards and Technology NVLAP-01S (REV. 2005-05-19)

Page 1 of 1





-211

For the National Institute of Standards and Technology

NVLAP-01C (REV. 2009-01-28)

2014-07-01 through 2015-06-30

Effective dates

N:\Clients\FDOT FILES\FDOT 1 (BDV 75)\PROJECTS\154316 (LOA 47) - SE 789 (Little Ringling Bridge) asbestos survey\5.0 Reports\Bridge 170022\154316 - Br 170022\_AsbSurv, Paint Survey\_070815 FINAL.docx



#### National Voluntary Laboratory Accreditation Program



#### SCOPE OF ACCREDITATION TO ISO/IEC 17025:2005

International Asbestos Testing Laboratories 9000 Commerce Parkway Suite B Mt. Laurel, NJ 08054 Mr. Frank E. Ehrenfeld, III Phone: 856-231-9449 Fax: 856-231-9818 E-Mail: frankehrenfeld@iatl.com URL: http://www.iatl.com

#### BULK ASBESTOS FIBER ANALYSIS (PLM)

#### NVLAP LAB CODE 101165-0

- NVLAP Code Designation / Description
- 18/A01 EPA 600/M4-82-020: Interim Method for the Determination of Asbestos in Bulk Insulation Samples
   18/A03 EPA 600/R-93/116: Method for the Determination of Asbestos in Bulk Building Materials

2014-07-01 through 2015-06-30

Effective dates

Page 1 of 1

Mprin R. Mlal

For the National Institute of Standards and Technology NVLAP-01S (REV. 2005-05-19)

#### **SECTION 6**

#### ASBESTOS OPERATIONS AND MAINTENANCE (O&M) PLAN AND RESPONSE ACTION

N:\Clients\FDOT FILES\FDOT 1 (BDV 75)\PROJECTS\154316 (LOA 47) - SE 789 (Little Ringling Bridge) asbestos survey\5.0 Reports\Bridge 170022\154316 - Br 170022\_AsbSurv, Paint Survey\_070815 FINAL.docx

#### O&M PLAN AND RESPONSE ACTION FOR BRIDGE 170022 (LITTLE RINGLING BRIDGE, WESTBOUND) SR 789 OVER THE COON KEY WATERWAY SARASOTA, SARASOTA COUNTY, FLORIDA DURING CONSTRUCTION ACTIVITIES

Any regulated asbestos-containing material (RACM) must be abated in accordance with 40 CFR, Subpart M, Part 61.145, as stated in abatement specifications required by Chapter 255, FS and OSHA Standard 1926.58 for the construction industry, prior to demolition or renovation. RACM is identified as follows:

- Friable ACM
- Category I nonfriable ACM that has become friable
- Category I nonfriable ACM that will be or has been subject to sanding, grinding, cutting, or abrading
- Category II nonfriable ACM that has a high probability of becoming, or has become, crumbled, pulverized, or reduced to powder by the forces expected to act on such material

No regulated asbestos-containing materials were found at Bridge 170022 located on SR 789 over the Coon Key Waterway within the materials tested. Renovation or demolition can proceed without any asbestos containment engineering controls, and no O&M or response actions are required. However, the use of wet demolition methods is recommended.

#### End of Work Plan

#### DISCLAIMER

The services described in this report were performed consistent with generally accepted professional consulting principles and practices. No other warranty, expressed or implied, is made. These services were performed consistent with our agreement with our client. This report is solely for the use and information of our client unless otherwise noted. Any reliance on this report by a third party is at such party's sole risk.

This report is the result of a limited investigation of the referenced bridge, and every attempt has been made to discover and inventory all asbestos-containing building materials (ACBM) in the structure. However, due to the limited and nondestructive nature of the inspection, it is possible that other concealed and inaccessible suspect materials may exist. Should any additional suspect ACMs be uncovered during renovation or demolition that are not listed in this report, then those materials should be sampled and submitted for analysis.

Opinions and recommendations contained in this report apply to conditions existing when services were performed and are intended only for the client, purposes, locations, time frames, and project parameters indicated. We are not responsible for the impacts of any changes in environmental standards, practices, or regulations subsequent to performance of services. We do not warrant the accuracy of information supplied by others, nor the use of segregated portions of this report.

#### **SECTION 8**

#### METALS-BASED PAINT SURVEY REPORT

 Facility Name:
 Bridge 170022 (Little Ringling Bridge, Westbound)

 Along SR 789 over Coon Key Waterway

Address/Location: 1.4 miles west of US 41

City, County, State: Sarasota, Sarasota County, Florida

 Owner Agency:
 Florida Department of Transportation, District 1

Date of Survey: <u>May 13, 2015</u>

Consultant: CB&I Environmental & Infrastructure, Inc.

Consultant Address: 1228 Winter Garden Vineland Road

City, State, Zip Code: \_\_\_\_\_\_ Winter Garden, Florida 34787

**Telephone Number:** 407-287-3210

Ju<u>ly 9, 2015</u>

\_\_\_\_\_

Shawn D. Flynn, P.G. Contract Manager

#### METALS-BASED PAINT COATING SAMPLING REPORT

CB&I Environmental & Infrastructure, Inc., (CB&I) was retained by the Florida Department of Transportation (FDOT), District 1, to collect representative samples of the paint coating system from Bridge No. 170022, located on SR 789 (Westbound) over the Coon Key Waterway in Sarasota, Sarasota County, Florida.

#### Introduction

CB&I collected <u>one sample</u> of the paint coatings system from the bridge, in general accordance with the sampling procedures developed by the State Materials Office, Florida Method of Test for Sampling of Structural Steel Existing Coating Systems Designation 5-564. The samples were obtained by Thomas Gregory of CB&I on May 13, 2015, and were labeled, packaged, manifested, and transported to Xenco Laboratories in Tampa, Florida. Sample <u>Pile Cover</u> <u>Composite</u> was collected from a white paint located on the fiberglass pile jackets (**Figure 1** in **Section 8**). Photographic documentation is provided in **Attachment A**, **Section 8**. Paint samples were laboratory analyzed for total heavy metals cadmium, chromium, lead, and the metal zinc by United States Environmental Protection Agency (EPA) Method 6010B and by the toxicity characteristic leaching procedure (TCLP) (EPA Method 6010C) for the same for metals. A copy of the laboratory analytical report is provided **Section 4**.

#### **Sample Results**

The following is a list of the paint samples collected for total metals analysis and the reported metals concentration.

		Sample ID: Pile Cover Composite
Metals	EPA Test Method	Concentration (mg/kg)
Cadmium	6010C	0.0645 U
Chromium	6010C	4.74
Lead	6010C	19.4
Zinc	6010C	330

mg/kg – milligrams per kilogram

U - Compound was analyzed for but not detected at the MDL level

The composite sample above was also laboratory analyzed by the Toxicity Characteristic Leachate Procedure (TCLP) to determine whether the painted surfaces would exceed the Environmental Protection Agency (EPA) leachability limits established in 40 CFR 261.24. Exceedance of the limits established under 40 CFR 261.24 would (upon removal) classify the material as hazardous.

		Sample ID: Pile Cover Composite	Hazardous Waste Regulatory Level per CFR 261-24	
Metals	EPA Test Method	Concentration (mg/L)	(mg/L)	
Cadmium	6010C	0.0006 U	1	
Chromium	6010C	0.0522 I	5	
Lead	6010C	0.0862	5	
Zinc	6010C	15.5	NS	

mg/L – milligrams per liter

*U* - Compound was analyzed for but not detected at the MDL level

I – Reported value is between the laboratory MDL and the laboratory PQL

NS – No Standard

#### **Recommendations for Personnel Health and Safety**

Due to the presence of metals in the paint coating identified on the pile jackets, the contractor selected to perform the renovation or demolition of the bridge should be familiar with and comply with all parts of the Occupational Safety and Health Administration (OSHA) Construction Standard contained in 29 CFR 1926.

Since sample analysis indicates that the paint coatings present on the tested components contain metals above detectable levels, there is potential for exposure to workers. Contractors should perform renovation or demolition activities in such a way as to continue to ensure that workers on the project are not exposed to levels above the OSHA permissible exposure limits in accordance with 29 CFR Subpart Z, and to ensure that any regulated metals are not spread to uncontrolled areas.

# Recommendations for Material/Waste Handling, Transportation, and Disposal


Based on the TCLP analytical results for the sampled areas, the paint waste generated from renovation or demolition of the metal span is not required to be handled as hazardous waste. However, any paint removed during construction will need to be re-analyzed as part of the waste profiling acceptance process prior to disposal.

During the removal and handling activities, the work area should be sufficiently protected from loose or falling paint chips and residue. All paint-related waste should be containerized in United States Department of Transportation (DOT) approved containers, labeled, and properly stored.

If blast media or chemicals are used during the paint removal operations, additional testing may be required. This could change the waste classification and disposal options.

In addition to the above requirements, all personnel who handle paint chips that have been removed from the metal span shall comply with all of the requirements in 40 CFR Parts 260 through 370. This includes, but is not limited to, waste handling, container labeling, transportation, and disposal.

#### FIGURE



#### ATTACHMENT A

#### PHOTOGRAPHIC LOG

N:\Clients\FDOT FILES\FDOT 1 (BDV 75)\PROJECTS\154316 (LOA 47) - SE 789 (Little Ringling Bridge) asbestos survey\5.0 Reports\Bridge 170022\154316 - Br 170022\_AsbSurv, Paint Survey\_070815 FINAL.docx

#### BRIDGE 170022 METALS-BASED PAINT SURVEY PHOTO LOG




PHOTO 1 – 5/13/15 – VIEW OF PILE COVER COMPOSITE PAINT SAMPLE LOCATED ON PILE JACKETS OVER CONCRETE SUPPORT PILES



PHOTO 2 – 5/12/15 – VIEW OF SUPPORT PILES WITH PILE JACKETS

#### ATTACHMENT B

#### LABORATORY ANALYTICAL REPORT AND CHAIN OF CUSTODY RECORD

N:\Clients\FDOT FILES\FDOT 1 (BDV 75)\PROJECTS\154316 (LOA 47) - SE 789 (Little Ringling Bridge) asbestos survey\5.0 Reports\Bridge 170022\154316 - Br 170022\_AsbSurv, Paint Survey\_070815 FINAL.docx

#### DISCLAIMER

The services described in this report were performed consistent with generally accepted professional consulting principles and practices. No other warranty, expressed or implied, is made. These services were performed consistent with our agreement with our client. This report is solely for the use and information of our client unless otherwise noted. Any reliance on this report by a third party is at such party's sole risk.

Opinions and recommendations contained in this report apply to conditions existing when services were performed and are intended only for the client, purposes, locations, time frames, and project parameters indicated. We are not responsible for the impacts of any changes in environmental standards, practices, or regulations subsequent to performance of services. We do not warrant the accuracy of information supplied by others, or the use of segregated portions of this report.

## Asbestos Survey and Metals-Based Paint Coatings Sampling Report

### Bridge Number 170951 (Eastbound) SR 789 (Little Ringling Bridge) over Coon Key Waterway Sarasota, Sarasota County, Florida

Prepared for: Florida Department of Transportation District 1 801 North Broadway Avenue Bartow, Florida 33830

Prepared by: CB&I Environmental & Infrastructure, Inc. 1228 Winter Garden Vineland Road Winter Garden, Florida 34787

FDOT Contract BDV75 FDOT FPID 436545-1-C2-32, LOA 47 CB&I Project 154316 July 2015

# **ASBESTOS SURVEY TITLE SHEET**

Facility Name:	Bridge 170951
	SR 789 (Little Ringling Bridge) Over Coon Key Waterway
Address/Location:	1.4 miles West of US 41
City, County, State:	Sarasota, Sarasota County, Florida
Owner Agency:	Florida Department of Transportation, District 1
Date of Survey:	May 12 and 13, 2015
Consultant:	CB&I Environmental & Infrastructure, Inc.
Consultant Address: _	1228 Winter Garden Vineland Road
City, State, Zip Code:	Winter Garden, Florida 34787
Telephone Number:	407-287-3210 (Shawn Flynn, PG; Contract Manager)

(T July 9, 2015

David W. Mosher, PE, LAC Licensed Asbestos Consultant, EA-0000078

### **TABLE OF CONTENTS**

#### **ACRONYMS AND ABBREVIATIONS**

- SECTION 1 SURVEY SUMMARY FORMS SURVEY OVERVIEW ASBESTOS SURVEY REPORT – FORM 1 ASBESTOS SURVEY AND ASSESSMENT – FORM 2 PERSONNEL SUMMARY – FORM 3
- SECTION 2 BRIDGE DIAGRAM(S)
- SECTION 3 PHOTOGRAPHS
- SECTION 4 LABORATORY ANALYTICAL DATA AND CHAIN OF CUSTODY FORM(S)
- SECTION 5 CREDENTIALS FOR CONSULTANT, INSPECTOR, AND LABORATORY
- SECTION 6 ASBESTOS OPERATIONS AND MAINTENANCE (O&M) PLAN AND RESPONSE ACTION
- SECTION 7 DISCLAIMER

#### METALS-BASED PAINT COATINGS SAMPLING REPORT

SECTION 8 INTRODUCTION

SAMPLE RESULTS

RECOMMENDATIONS FOR PERSONNEL HEALTH AND SAFETY

**RECOMMENDATIONS FOR MATERIAL/WASTE HANDLING, TRANSPORTATION, AND DISPOSAL** 

- FIGURES PAINT COATING SAMPLE LOCATION MAP
- ATTACHMENT A PHOTOGRAPHS
- ATTACHMENT B LABORATORY ANALYTICAL DATA AND CHAIN OF CUSTODY FORMS

### ACRONYMS AND ABBREVIATIONS

#### **Surfacing Materials**

- SAS acoustical/sprayed surfacing material
- SAT acoustical/troweled surfacing material
- SFP fireproofing/structural

#### **Thermal Materials**

- TPI pipe insulation
- TPC pipe cover
- TPE pipe elbow/joint
- TPM pipe mastic

#### **Miscellaneous Materials**

- MAS mastic/adhesive
- MBB vinyl baseboard
- MBP bearing pad
- MCA carpet adhesive
- MCC concrete
- MCK caulk/sealant
- MCM cementitious material/patch
- MCT ceiling tile
- MDI duct insulation
- MDM duct mastic
- MEJ expansion joint
- MFD fire door
- MFT floor tile
- MGS gasket
- MJC joint compound
- MMB moisture barrier (felt)
- MPC "popcorn" textured ceiling finish
- MPL plaster
- MRM reflector mastic
- MRP railing pads
- MSI sink insulation
- MST stucco
- MSV sheet vinyl/flooring
- MTC cementitious/Transite-type conduit/pipe
- MTP cementitious/Transite-type panel
- MVD vibration damper
- MVP vibration pads
- MWB wallboard
- MWG window glazing
- MWP wallpaper/covering

#### **Roofing Materials**

- RBU built-up roofing
- RAS asphalt shingle
- RFT tarpaper and felt
- RRM rolled membrane
- RFM flashing mastic
- RTP Transite-type panel/shingle

# **SECTION 1**

# SURVEY SUMMARY FORMS

N:\Clients\FDOT FILES\FDOT 1 (BDV 75)\PROJECTS\154316 (LOA 47) - SE 789 (Little Ringling Bridge) asbestos survey\5.0 Reports\Bridge 170951\154316 - Br 170951\_AsbSurv, Paint Survey\_070815 FINAL.docx

## ASBESTOS SURVEY OVERVIEW

As part of transportation improvement activities, the Florida Department of Transportation (FDOT), District 1, will be performing renovations to Bridge Number 170951 (or Little Ringling Bridge), eastbound along SR 789 over the Coon Key Waterway in Sarasota, Sarasota County, Florida, and has requested that an asbestos survey be performed to determine the presence, if any, of asbestos-containing materials (ACM). CB&I Environmental & Infrastructure Inc. (CB&I) has provided a map (**Figure 1**) illustrating the location of the subject bridge. Sampling locations are provided on **Figure 2**. Provided on **FORM 1** is detailed information regarding the bridge and the asbestos survey.

In addition to the asbestos survey, the FDOT requested sampling of the bridge paint coatings with laboratory analysis for heavy metals. The metals-based paint coatings survey was performed on May 13, 2015, and the results have been incorporated in this submittal (**Section 8**) immediately following the asbestos survey.

Survey activities described below were performed in accordance with the Asbestos Hazard Emergency Response Act (AHERA) sampling protocol and comply with the National Emission Standards for Hazardous Air Pollutants (NESHAP).

The FDOT provided CB&I with the following information:

- Bridge Plans, dated 1955
- Bridge Rehabilitation Final Plans, prepared by the FDOT, dated 1986
- Bridge Rehabilitation Final Plans, prepared by the FDOT, dated 1993
- Bridge Repair Plans (60% Submittal), prepared by T.Y. Lin International, dated February 10,2015

Thomas Gregory and Daniel Roebke of CB&I performed the asbestos survey on May 12 and 13, 2015, to determine the location, extent, and condition of suspect ACM.

During the asbestos survey, random samples of the following materials were collected to determine asbestos content: concrete, mortar, asphalt paper, caulking, mastic, Class 5 coating, fiberglass, and sealant (**FORM 2**). No suspect drains were identified on the bridge structure.

Under the AHERA definitions and sampling protocol, 22 homogenous areas (HA) were identified during this survey as miscellaneous materials (see **FORM 2**). A homogeneous area is an application of surfacing material, thermal system insulation material, or miscellaneous materials that is uniform in color, texture, and vintage of application. Miscellaneous material is defined by the United States Environmental Protection Agency (US EPA) as interior building

material on structural components, structural members, or fixtures (such as floor tiles, adhesives, and mastics) and does not include surfacing material or thermal system insulation (40 CFR Part 763.83).

Also, during the survey, the quantification and extent of each HA was estimated and the friability of the material was determined. A material is considered friable that, when dry, can be crumbled, pulverized, or reduced to a powder by hand pressure as defined by the US EPA. At a minimum, three samples of each HA were collected for analysis, as recommended by the US EPA (*100 Commonly Asked Questions About the New AHERA Asbestos-in-Schools Rule*, US EPA, May 1988) and required by CB&I protocol. Three additional samples were collected randomly for quality assurance/quality control (QA/QC) purposes. The total number of samples collected from this bridge was 70 (66 from 22 HAs and 4 QA/QC). Provided on **FORM 3** is a list of survey team (personnel and laboratories) and their appropriate license or certificate numbers.

Samples of suspect materials were submitted for asbestos analysis to an independent laboratory certified by the National Voluntary Laboratory Accreditation Program (NVLAP). Additionally, as per FDOT requirements, QA/QC samples were collected and submitted for analysis to a second NVLAP-certified laboratory. All samples were analyzed for asbestos of bulk materials by EPA Method 600/R-93/116 using Polarized Light Microscopy.

Laboratory analysis of the collected suspect samples indicated that the sampled materials did not contain asbestos. Renovation or demolition can proceed without any engineering controls. However, the use of wet demolition methods is recommended during renovation or demolition of these sampled materials.

Estimates related to the cost of abatement (including disposal) and on-site air monitoring are provided on **FORM 2** for each HA that contains asbestos. These estimates are based on our previous experience for similar abatement projects in similar locations and do not include the costs for replacement materials or labor following the abatement work. However, because no asbestos was identified, no abatement costs are noted.

# **ASBESTOS SURVEY REPORT – FORM 1**

#### **BRIDGE IDENTIFICATION**

County:	Sarasota
Agency:	Florida Department of Transportation District 1
Bridge Names:	Little Ringling Bridge (Eastbound) over Coon Key Waterway
Bridge Numbers:	170951
Address and/or Geogra	ohic Location: <u>Along SR 789, 1.4 Miles West of US 41</u>
Asbestos Contact Perso	n: Jeffrey W. James Telephone Number: <u>863-519-2625</u>
FDOT Contact: Jeffre	James         Telephone Number: 863-519-2625

# SURVEY IDENTIFICATION

Date of Survey:	May 12 and 13, 2015 Date of Report: July 9, 2015
Contract No.:	BDV75
FM No.:	436545-1-C2-32
Consultant's Name:	David W. Mosher, PE, LAC License No.: <u>EA-0000078</u>
Name of Firm:	CB&I Environmental & Infrastructure, Inc.
Address:	1228 Winter Garden Vineland Road, Winter Garden, Florida 34787
Telephone Number:	407-287-3210 (Shawn Flynn, PG, Contract Manager)

# **BRIDGE INFORMATION**

Year of Construction: _	1958		
Renovation Dates:	Unknown		
Bridge Documents/Drav	wings Available/Con	nsulted:	
Types: Plans	⊠Yes □No	Location	Several pages from 1955, 1986, 1993
			and 2015 bridge plan set
Specifications	□Yes ⊠No	Location	
Other	□Yes ⊠No	Location	
Asbestos Docur	nents □Yes ⊠No	Location	
	⊠Yes □No	Location	uglybridges.com
	□Yes □No	Location	

## STRUCTURAL DATA

Vertical Support:	Prestressed concrete piles Horizontal: Prestressed concrete
Decking:	Concrete, Cast-In-Place
Span:	21 Spans, Longest 47.9', Total Length 1,010.2' Gaskets: NA
Bearing Pads:	Noted as "Bearing Plates" Railings: Concrete
If applicable:	
Roof:	NA
Floors:	NA Ceilings: NA
Exterior Walls:	NA Partition Walls: NA
HVAC System:	$\Box$ Yes $\boxtimes$ No Type: <u>NA</u>

	170951 (Little Ringling Bi May 12 and 13, 2015	ridge, East	bound) – SR 789 over Coon Key Agency:	Waterway Florid	/ da Depa	urtment of	Contract N Transport	No.: <u>BDV</u> ation, Dist	75 trict 1
ıltant:	CB&I Environmental & Ir	nfrastructu	re, Inc. FDOT Contact Perso	n: Jeffre	ey W. Ja	ames	*		
Sample No. or Assumed	Material Description	Homo- geneous Area No.	Area Description	Quantity (Total for HA)	Friable Y/N	Asbestos Type & % or Assumed	Response Cost	Air Monitoring Cost	Replace Cost
1.1	CONCRETE	1	BENT COLUMNS	5600 CF	N	NAD	0	0	0
1.2	CONCRETE	1	BENT COLUMNS	5600 CF	Ν	NAD	0	0	0
1.3	CONCRETE	1	BENT COLUMNS	5600 CF	Ν	NAD	0	0	0
2.1	CONCRETE	2	BENT CAPS	4662 CF	Ν	NAD	0	0	0
2.2	CONCRETE	2	BENT CAPS	4662 CF	Ν	NAD	0	0	0
2.3	CONCRETE	2	BENT CAPS	4662 CF	N	NAD	0	0	0
3.1	CONCRETE	3	SEA WALL	1540 CF	N	NAD	0	0	0
3.2	CONCRETE	3	SEA WALL	1540 CF	N	NAD	0	0	0
3.3	CONCRETE	3	SEA WALL	1540 CF	Ν	NAD	0	0	0
4.1	CONCRETE	4	ABUTMENT WALL	1036 CF	N	NAD	0	0	0
4.2	CONCRETE	4	ABUTMENT WALL	1036 CF	Ν	NAD	0	0	0
4.3	CONCRETE	4	ABUTMENT WALL	1036 CF	N	NAD	0	0	0
5.1	MORTAR	5	ABUTMENT WALL	11520 CF	Ν	NAD	0	0	0
5.2	MORTAR	5	ABUTMENT WALL	11520 CF	Ν	NAD	0	0	0
5.3	MORTAR	5	ABUTMENT WALL	11520 CF	N	NAD	0	0	0
COMMENTS/N Y – Yes N – No NA – Not Appli	Subtot	als for thi	s page	0	0	0			
NAD - No Asbestos Detected LF - Linear feetPC - Point Count Analysiscro crocidoliteSF - Square feetPC - Less than 1%				Consultant Fees					
<ol> <li>All quantities</li> <li>All costs prov</li> </ol>	O & M Costs								
	bold text indicates Asbestos-Co	ntaining Mat	erial (ACM) or assumed ACM.		TOTAL				

Survey: <u>N</u> tant: <u>C</u>	May 12 and 13, 2015 CB&I Environmental & Int	frastructu	Agency: re, Inc. FDOT Contact Per	Flor son: Jeff	<u>ida Der</u> rey W	bartment ( James	of Transpor	rtation, Dis	strict 1
Sample No. or Assumed	Material Description	Homo- geneous Area No.	Area Description	Quantity (Total for HA)	Friable Y/N	Asbestos Type & % or Assumed	Response Cost	Air Monitoring Cost	Replace Cost
6.1	CONCRETE	6	END BENT	1230 CF	N	NAD	0	0	0
6.2	CONCRETE	6	END BENT	1230 CF	N	NAD	0	0	0
6.3	CONCRETE	6	END BENT	1230 CF	N	NAD	0	0	0
6.4 QA/QC	CONCRETE	6	END BENT	1230 CF	N	NAD	0	0	0
7.1	CONCRETE	7	DIAPHRAM	2220 CF	N	NAD	0	0	0
7.2	CONCRETE	7	DIAPHRAM	2220 CF	N	NAD	0	0	0
7.3	CONCRETE	7	DIAPHRAM	2220 CF	N	NAD	0	0	0
8.1	ASPHALT IMPREGNATED PAPER	8	SUBGIRDER BEARING PAD	400 SF	N	NAD	0	0	0
8.2	ASPHALT IMPREGNATED PAPER	8	SUBGIRDER BEARING PAD	400 SF	N	NAD	0	0	0
8.3	ASPHALT IMPREGNATED PAPER	8	SUBGIRDER BEARING PAD	400 SF	N	NAD	0	0	0
9.1	CONCRETE	9	GIRDERS	22725 CF	N	NAD	0	0	0
9.2	CONCRETE	9	GIRDERS	22725 CF	N	NAD	0	0	0
9.3	CONCRETE	9	GIRDERS	22725 CF	N	NAD	0	0	0
10.1	MORTAR	10	GIRDERS	10100 SF	N	NAD	0	0	0
10.2	MORTAR	10	GIRDERS	10100 SF	N	NAD	0	0	0
COMMENTS/ Y – Yes N – No NA – Not App	Subtotals for this page		0	0	0				
LF – Linear fe	NAD - Not ApplicablePC - Point Count Analysiscro crocidoliteNAD - No Asbestos DetectedPC - Point Count Analysiscro crocidoliteLF - Linear feetPS - Analyzed to first positive stopTrace - Less than 1%				Consultant Fees				
<ol> <li>All quantities given in square feet unless otherwise indicated.</li> <li>All costs provided assume one mobilization.</li> </ol>									
					& M Cost	S			
3. Shaded an	d bold text indicates Asbestos-Co	ontaining Ma	aterial (ACM) or assumed ACM.		TOTAL				

	70951 (Little Ringling Bridge, Eas	stbound)		-	-			t No.: <u>BD</u>	
	May 12 and 13, 2015		Agency:				of Transpo	ortation, Di	strict 1
iltant: <u>C</u>	CB&I Environmental & Infrastruct	ure, Inc.	FDOT Contact Pers	on: Jeff	rey W.	James			
Sample No. or Assumed	Material Description	Homo- geneous Area No.	Area Description	Quantity (Total for HA)	Friabl e Y/N	Asbestos Type & % or Assumed	Response Cost	Air Monitoring Cost	Replace Cost
10.3	MORTAR	10	GIRDER	10100 SF	N	NAD	0	0	0
11.1	ASPHALT IMPREGNATED PAPER	11	SUBDECK BEARING PADS	5050 SF	Ν	NAD	0	0	0
11.2	ASPHALT IMPREGNATED PAPER	11	SUBDECK BEARING PADS	5050 SF	Ν	NAD	0	0	0
11.3	ASPHALT IMPREGNATED PAPER	11	SUBDECK BEARING PADS	5050 SF	Ν	NAD	0	0	0
12.1	BLACK RUBBER CAULKING	12	EXPANSION JOINTS	814 LF	Ν	NAD	0	0	0
12.2	BLACK RUBBER CAULKING	12	EXPANSION JOINTS	814 LF	N	NAD	0	0	0
12.3	BLACK RUBBER CAULKING	12	EXPANSION JOINTS	814 LF	Ν	NAD	0	0	0
12.4 QA/QC	BLACK RUBBER CAULKING	12	EXPANSION JOINTS	814 LF	Ν	NAD	0	0	0
13.1	CONCRETE	13	RAILING – RAIL	2273 CF	N	NAD	0	0	0
13.2	CONCRETE	13	RAILING – RAIL	2273 CF	N	NAD	0	0	0
13.3	CONCRETE	13	RAILING – RAIL	2273 CF	N	NAD	0	0	0
14.1	CONCRETE	14	END CAP	144 CF	Ν	NAD	0	0	0
14.2	CONCRETE	14	END CAP	144 CF	Ν	NAD	0	0	0
14.3	CONCRETE	14	END CAP	144 CF	Ν	NAD	0	0	0
15.1	CONCRETE	15	CURB	1616 CF	Ν	NAD	0	0	0
N – No N – No CAT I – Category I CAT II – Category II th			chry chrysotile amo amosite trem tremolite cro crocidolite	Subtota	als for th	is page	0	0	0
				Con	Consultant Fees				
<ol> <li>All quantities given in square feet unless otherwise indicated.</li> <li>All costs provided assume one mobilization.</li> </ol>					O & M Costs				
3. Shaded an	d bold text indicates Asbestos-Containing N	laterial (AC	M) or assumed ACM.		TOTAL				

			bound) – SR 789 over Coon Key Agency:					No.: <u>BDV</u>	
ltant: <u>C</u>				Transport	tation, Dist				
Sample No.	Material	Homo- geneous	Area	Quantity (Total for	Friable	Asbestos Type & %	Response	Air Monitoring	Replace
or Assumed	Description	Area No.	Description	HA)	Y/N	or Assumed	Cost	Cost	Cost
15.2	CONCRETE	15	CURB	1616 CF	N	NAD	0	0	0
15.3	CONCRETE	15	CURB	1616 CF	Ν	NAD	0	0	0
16.1	CONCRETE	16	DECK	37370 CF	Ν	NAD	0	0	0
16.2	CONCRETE	16	DECK	37370 CF	Ν	NAD	0	0	0
16.3	CONCRETE	16	DECK	37370 CF	Ν	NAD	0	0	0
17.1	CONCRETE	17	RAILING – POST	13635 CF	Ν	NAD	0	0	0
17.2	CONCRETE	17	RAILING – POST	13635 CF	Ν	NAD	0	0	0
17.3	CONCRETE	17	RAILING – POST	13635 CF	N	NAD	0	0	0
18.1	MORTAR	18	DECK	681 SF	N	NAD	0	0	0
18.2	MORTAR	18	DECK	681 SF	N	NAD	0	0	0
18.3	MORTAR	18	DECK	681 SF	N	NAD	0	0	0
18.4 QA/QC	MORTAR	18	DECK	681 SF	N	NAD	0	0	0
19.1	BLACK ADHESIVE MASTIC	19	DECK REFLECTORS	70 SF	N	NAD	0	0	0
19.2	BLACK ADHESIVE MASTIC	19	DECK REFLECTORS	70 SF	N	NAD	0	0	0
19.3	BLACK ADHESIVE MASTIC	19	DECK REFLECTORS	70 SF	N	NAD	0	0	0
COMMENTS/NOTES:     CF - Cubic Feet     chry chrysotile       Y - Yes     CAT I - Category I     amo amosite       N - No     CAT II - Category II     trem tremolite       NA - Not Applicable     PC - Point Count Analysis     cro crocidolite       NAD - No Asbestos Detected     PS - Analyzed to first positive stop					Subtotals for this page		0	0	0
LF – Linear feet SF – Square fee	t Trace – Less	than 1%	ve stop	Cor	sultant F	ees			
	given in square feet unless otherw ded assume one mobilization.	ise indicated.		0	& M Cos	ts			
3. Shaded and k	oold text indicates Asbestos-Co	ntaining Mat	erial (ACM) or assumed ACM.		TOTAL				

f Survey: <u>May 12 and 13, 2015</u> Agency: Itant: CB&I Environmental & Infrastructure, Inc. FDOT Con			Agency: FDOT Contact Pe							
Sample No. or Assumed	Material Description	Homo- geneous Area No.		Area Description	Quantity (Total for HA)	Friable Y/N	Asbestos Type & % or Assumed	Response Cost	Air Monitoring Cost	Replace Cost
20.1	CLASS 5 COATING	20	RAILINGS		250 SF	N	NAD	0	0	0
20.2	CLASS 5 COATING	20	RAILINGS		250 SF	N	NAD	0	0	0
20.3	CLASS 5 COATING	20	RAILINGS		250 SF	N	NAD	0	0	C
21.1	FIBERGLASS	21	PILE JACKETS	3	3200 SF	N	NAD	0	0	0
21.2	FIBERGLASS	21	PILE JACKETS	3	3200 SF	N	NAD	0	0	0
21.3	FIBERGLASS	21	PILE JACKETS	3	3200 SF	N	NAD	0	0	0
21.4 QA/QC	FIBERGLASS	21	PILE JACKETS	3	3200 SF	N	NAD	0	0	0
22.1	SEALANT (WITHIN THE SPACE BETWEEN PILE AND PILE JACKET)	22	PILE JACKETS	3	1600 SF	N	NAD	0	0	0
22.2	SEALANT (WITHIN THE SPACE BETWEEN PILE AND PILE JACKET)	22	PILE JACKETS	3	1600 SF	N	NAD	0	0	0
22.3	SEALANT (WITHIN THE SPACE BETWEEN PILE AND PILE JACKET)	22	PILE JACKETS	3	1600 SF	N	NAD	0	0	0
COMMENTS/NOTES:       CF – Cubic Feet       chry chrys         Y – Yes       CAT I – Category I       amo amo         N – No       CAT II – Category II       trem trem         NA – Not Applicable       DP Deist Court Applicable       chry chrys					Subtota	als for this	s page	0	0	0
NA = Not ApplicablePC = Point Count Analysiscro.NAD = No Asbestos DetectedPC = Point Count Analysiscro.LF = Linear feetPS = Analyzed to first positive stopSF = Square feetTrace = Less than 1%			cro crocidolite	Con	Consultant Fees					
1. All quantities given in square feet unless otherwise indicated.										
2. All costs provided assume one mobilization.						& M Cos	ts			
3. Shaded and bold text indicates Asbestos-Containing Material (ACM) or assumed ACM.						TOTAL				


# ASBESTOS SURVEY REPORT – FORM 3 PERSONNEL SUMMARY


Facility/Bridge Name:	SR 789 (Little Ringling Bridge) over Coon Key Waterway
Bridge No.:	170951
Date of Survey:	May 12 and 13, 2015

Name and Address	Task Performed	License or Certificate
David W. Mosher, PE, LAC	Asbestos Consultant	EA-0000078
CB&I Environmental & Infrastructure, Inc. 9143 Philips Highway, Suite 400 Jacksonville, FL 32256	Asbestos Business	ZA-317
Thomas Gregory CB&I Environmental & Infrastructure, Inc. 1228 Winter Garden Vineland Road Winter Garden, Florida 34787	Asbestos Inspector	161984
Daniel Roebke CB&I Environmental & Infrastructure, Inc. 1228 Winter Garden Vineland Road Winter Garden, Florida 34787	Asbestos Inspector	140627-4599
EMSL Analytical, Inc. (EMSL) 5125 Adanson Street, Suite 900 Orlando, FL 32804	Bulk Analysis	NVLP No. 101151-0
International Asbestos Testing Laboratory (IATL) 9000 Commerce Parkway, Suite B Mt. Laurel, New Jersey 08054	Quality Assurance	NVLAP No. 101165-0

# **SECTION 2**

# **BRIDGE DIAGRAM(S)**





# **SECTION 3**

# PHOTOGRAPHS

N:\Clients\FDOT FILES\FDOT 1 (BDV 75)\PROJECTS\154316 (LOA 47) - SE 789 (Little Ringling Bridge) asbestos survey\5.0 Reports\Bridge 170951\154316 - Br 170951\_AsbSurv, Paint Survey\_070815 FINAL.docx



PHOTO 1 – 5/12/15 BRIDGE NO. 170951 – SR 789 OVER COON KEY WATERWAY – VIEW TOWARDS SOUTHEAST SARASOTA, SARASOTA COUNTY, FL



PHOTO 2 – 5/12/15 BRIDGE NO. 170951 – SR 789 OVER COON KEY WATERWAY – VIEW TOWARDS NORTHEAST SARASOTA, SARASOTA COUNTY, FL




PHOTO 3 – 5/12/15 BRIDGE NO. 170951 – SR 789 OVER COON KEY WATERWAY – VIEW TOWARDS NORTHEAST SARASOTA, SARASOTA COUNTY, FL

PHOTOGRAPH LOG - ACM SAMPLE PROJECT NO. 15431 PROJECT LOCATION: Jacobsty Li Coor key Water BUILDING NAME: SE 280 Del CLIENT:\_\_\_ ROOM NO. 1285 DATE: 5-13-15 INSPECTOR: 61494 A DESCRIPTION --IA NO --HA CONDITION 90 NO RACM COMMENTS:-YES FRIABLE CAT CATI PHOTO 4 - 5/13/15 - SAMPLE 1.1 - HA 1 CONCRETE

N:\Clients\FDOT FILES\FDOT 1 (BDV 75)\PROJECTS\154316 (LOA 47) - SE 789 (Little Ringling Bridge) asbestos survey\5.0 Reports\Bridge 170951\154316 - Br 170951\_AsbSurv, Paint Survey\_070815 FINAL.docx

**BENT COLUMNS** 

	_	E <b>170951</b> RVEY PHOTO LOG	
PROJE CLIEN PRO BUII RO DA IN H/	DGRAPH LOG - ACM SAMPLE CT NO. 154316 T: FDOT 1 DECT LOCATION: Seresta, FL DING NAME: SR 180 over Contraction DM NO. 120351 EB TE: S-13-15 SPECTOR: Gregory 13 A DESCRIPTION: PHONS - MORENTES COMMENTS: NO COMMENTS: CAT II: CAT		
8	PHOTO 5 – 5/13/15 CON BENT C PHOTOGRAPH LOG – ACM PROJECT NO154316	- SAMPLE 1.2 - HA 1 CRETE COLUMNS	
	HA NO HA DESCRIPTION: HA CONDITION: grad	n key Watersusy	
	FRIABLE - YES - RACM: CAT II: CAT II: RACM: PHOTO 6 - 5/13/15 - CON	– SAMPLE 1.3 – HA 1 CRETE COLUMNS	

ACM SAMPLE
OJECT NO. 154316
IENT: FDOT 1
UILDING NAME: SE TED OVER COON Key Waterway
ANNO 1/Clean
INSPECTOR: Grand 22 INSPECTOR: 22 Inspector
INSPECTOR:
HA DESCRIT
IN CONDITION: BOA
HA COMMENTS: NO NO RACM:
FRIABLE CATI
FRIAT CATE
A State Base
PHOTO 7 – 5/13/15 – SAMPLE 2.1 – HA 2 CONCRETE
BENT CAPS
154315
ACM SAMPLE
PROJECT NO. 154316
CLIENT: FDOT 1
PROJECT LOCATION: Sacasoto FL
BUILDING NAME: SR 780 over Coon Key Waterway
ROOM NO. TOPSI ER
DATE: 5-13-15
INSPECTOR: Granger 12
HA NO. N 22 HA DESCRIPTION: Cross Sume-Length
HA DESCRIPTION:
HA CONDITION:
MEN D
VES
FRIABLE
CATE
PHOTO 8 – 5/13/15 – SAMPLE 2.2 – HA 2

**BENT CAPS** 

State of the state	150		1.23	r m the state	1. Company and the A
		LUG - ACM SAN	NPLE	11 - 1 - 1 - 1 - 1 - 1 - 1 - 1 - 1 - 1	
	PROJECT NO CLIENT: PROJECT LOCA BUILDING NAMI ROOM NO DATE: INSPECTOR: HA NO HA DESCRIP HA CONDITI COMMENTS	H314 DOT 1 FION: <u>Sqraseta, Ft</u> Steps) EB 5-15 <u>Sceney</u> TION: <u>Cross Brems</u> ON: <u>good</u>	on key waterway		
	PHO		CAPS	- ACM SAMPLE	


FRIABLE - YES K NO CAT I: CAT II: RACM:

N:\Clients\FDOT FILES\FDOT 1 (BDV 75)\PROJECTS\154316 (LOA 47) - SE 789 (Little Ringling Bridge) asbestos survey\5.0 Reports\Bridge 170951\154316 - Br 170951\_AsbSurv, Paint Survey\_070815 FINAL.docx

PHOTO 10 – 5/12/15 – SAMPLE 3.1 – HA 3 CONCRETE SEAWALL



PHOTO 11 – 5/12/15 – SAMPLE 3.2 – HA 3 CONCRETE SEAWALL



SEAWALL




PHOTO 13 – 5/12/15 – SAMPLE 4.1 – HA 4 CONCRETE END BENT OR ABUTMENT




PHOTO 14 – 5/12/15 – SAMPLE 4.2 – HA 4 CONCRETE END BENT OR ABUTMENT




PHOTO 15 – 5/12/15 – SAMPLE 4.3 – HA 4 CONCRETE END BENT OR ABUTMENT

NUNI SAMPLE 154 31 BUILDING NAME: SR 780 OUL COOD RELEVATIONS PROJECT NO.\_\_ PROJECT LOCATION: Socosota CLIENT:\_\_\_ ROOM NO. 170951 - EB DATE: 5-1 INSPECTOR: Georges HA NO. 5.12.15 HA DESCRIPTION: <u>Algutiment</u> molta HA CONDITION: COMMENTS:\_\_ YES \_X NO RACM: FRIABLE -CAT II: CAT I: \_

PHOTO 16 – 5/12/15 – SAMPLE 5.1 – HA 5 MORTAR END BENT OR ABUTMENT

TONG WE THEN I		S. B. C. L.
		1. 1. 1.
121		1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
TARAPH LOG - ACM SAMPLE		ALC: SALES
PROJECT NO. 154 316		and the second
CLIENT: FDOT		
PROJECT LOCATION: La use way wat	ruby	
BUILDING NAME: DR. HO		
ROOM NO. 170951 0 00 5.3	and Brooks	
DATE:	The Aller and Aller	No.
INSPECTOR: Gregory	1. S. C. S.	Sec. 8 3.
HANO. 5.12-15 + mostal		
HA DESCRIPTION: automore in the		and the second
- and fait	and an interest of the	13 C 23
HA CONDITION: Sector - Court		
COMMENTS:	e test	ALL'S ALL
FRIABLE - YES NO		A Carlos
<form></form>		
work advention field formal acceptotolog data 05/12/15	1.1	
MOF	TAR	
MOF END BENT O	TAR R ABUTMENT	
MOF END BENT O	TAR R ABUTMENT	
MOF END BENT O	TAR R ABUTMENT	
MOF END BENT O	TAR R ABUTMENT	
MOF END BENT O	TAR R ABUTMENT	
MOF END BENT O		
PHOTOGRAPH LOG - ACM SAME		
PROJECT NO 154 316	A ABUTMENT	
PHOTOGRAPH LOG - ACM SAME PROJECT NOSU		
PHOTOGRAPH LOG - ACM SAMP		
PHOTOGRAPH LOG - ACM SAME PHOTOGRAPH LOG - ACM SAME PROJECT NO154 316 CLIENT: FDOT 1 PROJECT LOCATION: Sacasota _EL BUILDING NAME: _SP_770_0741_CEPT ROOM NO170751 - EB		
PHOTOGRAPH LOG - ACM SAME PROJECT NOS4_316 CLIENT:FDOT 1 PROJECT LOCATION: Sarcasota (FL BUILDING NAME:S7_700 OVAL CAST ROOM NOCOSTE8 DATE:S7		
PHOTOGRAPH LOG - ACM SAMP PROJECT NOSU CLIENT:FDOT 1 PROJECT LOCATION: Sarasota EL BUILDING NAME: SP. 7K0 - 9KL CAP ROOM NOCAST DATE:SMSX2 INSPECTOR: Garges		
PHOTOGRAPH LOG - ACM SAMP PROJECT NOSU CLIENT:FOOT 1 PROJECT LOCATION: Sacasda BUILDING NAME:SP OM NOSP INSPECTOR: Gacasda HA NOSP HA NOSP		
PHOTOGRAPH LOG - ACM SAMP PROJECT NO ISU 316 CLIENT: _ FDOT 1 PROJECT LOCATION: <u>Socaseta FL</u> BUILDING NAME: <u>SP. 700 9M. CROP</u> ROOM NO. <u>17051 - E8</u> DATE: <u>SM.</u> INSPECTOR: <u>Googed</u> HA NO <u>S-12-15</u> HA DESCRIPTION: <u>AUtoment</u>		
PHOTOGRAPH LOG - ACM SAME PHOTOGRAPH LOG - ACM SAME PROJECT NOSCH SILL CLIENT:FDOT 1 PROJECT LOCATION: Sacasots FL BUILDING NAME: SPL 730 OPUL COP ROOM NOTCASI _ EB DATE: SX1SX2 INSPECTOR: Garges HA NOS.12.15 HA DESCRIPTION: Albutment HA CONDITION: Automat		
PHOTOGRAPH LOG - ACM SAMP		
PROJECT NO SCASOLS FL BUILDING NAME: SP TRO ONL CON ROOM NO 150 - 314 CLIENT: FDOT 1 PROJECT LOCATION: <u>Socasols FL</u> BUILDING NAME: <u>SP TRO ONL CON</u> ROOM NO 12051 - 58 DATE: <u>SM</u> SX2 INSPECTOR: <u>Googe</u> HA NO S-12-15 HA DESCRIPTION: <u>AlutEment</u> HA CONDITION: <u>AlutEment</u> HA CONDITION: <u>AlutEment</u>	TAR ABUTMENT	
PROJECT NOSUM PROJECT NOSUM CLIENT:FDOT 1 PROJECT LOCATION: Socrasots ft BUILDING NAME: SPTSOOWCOT ROOM NOTCQS1 - E8 DATE: SMST INSPECTOR: Go.gog HA NOS.12.15 HA DESCRIPTION: duritment HA CONDITION: duritment HA CONDITION: duritment	TAR ABUTMENT	
PROJECT NO SUBJECT NOSUBJECT NO.	TAR ABUTMENT	
PROJECT NO SUBJECT NOSUBJECT NO.	TAR ABUTMENT	
PROJECT NO SUBJECT	TAR ABUTMENT	
PHOTOGRAPH LOG - ACM SAME         PROJECT NO.         PROJECT NO.         PROJECT LOGATION:         PROJECT REGENCE	TAR ABUTMENT	
PROTECT NO.       MARGE         PROTECT NO.       Server         PROJECT NO.       Server         PROJECT NO.       Server         PROJECT NO.       Server         PROJECT LOCATION:       Server         PROJECT COMMENTS:       Server         PROJECT Server       Server	TAR ABUTMENT	
Photograph Log - Act Magnetic         Project No.         States         Project Location:         Building Name:         States         Building Name:         Building Name:         Buil	TAR ABUTMENT	
PROFERENCE	TAR ABUTMENT	
PHOTOGRAPH LOG - ACM SAME         PROJECT NO.         PROJECT NO.         PROJECT LOGATION:         PROJECT REGENCE	TAR ABUTMENT	
PHOTOGRAPH LOG - ACM SAME         PROJECT NO.         PROJECT NO.         PROJECT LOGATION:	TAR ABUTMENT	
Photocraph log - active   PROJECT NO.   States   PROJECT NO.   States   CLENT:   PROJECT LOCATION:   States   BUILDING NAME:   BUILDING N	TAR ABUTMENT	

END BENT OR ABUTMENT

1. Participant		
PHOTOGRAPH LOG - ACM SAMPLE		
PROJECT NO. 154 316 CLIENT: FDOT 1 PROJECT LOCATION: SECOND. CON Key Waldway BUILDING NAME: SE 750 and Con Key Waldway		• • •
ROOM NO. 120351 - EB DATE: 5:12-15 INSPECTOR: <u>Geograp</u> HA NO. 6-1 6-2 6-3 6-4 6A HA DESCRIPTION: <u>GAJ Burt</u>		
HA CONDITION: good		
FRIABLE YES NO           CAT I: CAT II: RACM:		
The contribution prepty documents where the line completive due 2012/1	-	

PHOTO 19 – 5/12/15 – SAMPLE 6.1 – HA 6 CONCRETE END BENT PILE CAP

	PHOTOGRAPH LOG - ACM SAMPLE PROJECT NOLCH SLC	
-	CLIENT:FDOT 1	And the
	PROJECT LOCATION: Sergardia R	
	BUILDING NAME: Se 720 ave. (on key lind Juney ROOM NO. 170351 - 6 6	23
- 162 C		24
	INSPECTOR: Greagery	a partie
	HANO. 61 6-2 6-2 6-4 CA	Part Parts
	HA DESCRIPTION: God Ban	
	HA CONDITION: 3000	
	COMMENTS:	AT ALL OF ALL OF
	FRIABLE - YES NO RACM:	. State 1
	FRIABLE RACM: CAT II: RACM:	-
	CATI	
1		
	and increased and in 19110	
	Strending over some state	
	PHOTO 20 – 5/12/15 – SAMPLE 6.2 – HA 6	
	CONCRETE	
	END BENT PILE CAP	


			A DE ALTHE REAL OF A
			N. N.O. S. North
10 M	ALL ALL ALL	A Promotive	A MARTIN AND AND AND AND AND AND AND AND AND AN
	and the second		1 M THERE AND A 199 1 1 14
	A State of the second s	Contraction of the second second	
All Contract of		AND A DOM	
			Simon All
			States 101 111 (Second
		State State	A LANGER
		South State State	A A AN AND ADDRESS
		12	and the state of the second
	C.L.		
		A PA	
	PHOTOCOL		
	PHOTOGRAPH LOG - ACM SAMPLE		
100	PROJECT NO. 154 316		
125	CLIENT: FDOT 1		
	PROJECT LOCATION: Saraabla ft		
1	BUILDING NAME: 54 780 our Con key White	au BERENE STORE	
	ROOM NO. 170951 - EB	-0	
	DATE: 5-12-15	and the second second	
	DATE: <u>51015</u>		
	INSPECTOR: Greening HANO. AL 62 6.3 6.	YGA	
	HANO. KI ONL		
	HA DESCRIPTION: Grd Bent		
	HA CONDITION: good		
WE S	COMMENTS:		
	COMMENT		
1118	FRIABLE - YES NO CAT I: CAT II: RACM: - RACM: - GAT II: - GAT III: - RACM: - GIGLEO		
	FRIABLE RACIN.		
	CAT I: CAT		
STE/ 12	, ides		
Contra la	4911000	No.	
			And a second sec
State The			
and the second second	shows promitive and shows find the series and provide the GAUS		
	an documents work subcours field hereit		
Contraction of the local data and the	domas gregos		Sector Se

PHOTO 21 – 5/12/15 – SAMPLE 6.3 – HA 6 CONCRETE END BENT PILE CAP

	AND INCOMENT		Press and
			ALLAND CALL
	g di Carto and	-25	
			AN ASSA ASY
a later and a later and a later	and the first		All Start / /
			Stat 19 18
		and the second	1 1 M 10 10
	A CONTRACTOR	And the second second	A MARIA
			S MEA LESS
PHOTOGRAPH L	OG - ACM SAMPLE	A PART OF	a fait
PROJECT NO. 154	316		A CARLON MARINE
CLIENT: FDC	0T1		
PROJECT LOCATIO	N: Sarazota A		
ROOM NO. 17095	R 780 over Coon key Waterway		
DATE: 5-12-15		Martin Martin	
INSPECTOR: GO	eaging 6x 6-40A		
HANO.	0/10		
HA DESCRIPTION	: Ond Bar		
HA CONDITION:	good		
	VES NO		
FRIABLE -	RACM:		
CAT I:			
U	_YES NO CAT II: RACM: GI(140		
		and the second s	
	interming for 251215		
analosian bernen	work when what to an a set		
We surrow			
			100
РНОТО		PLE 6.4 QA/QC- HA 6	
	CONCRE		
	END BENT P	LE CAP	


411 31 PHOTOGRAPH LOG - ACM SAMPLE PROJECT NO. 154316 PROJECT LOCATION: Seleste CLIENT:\_\_\_ wa BUILDING NAME: SE 750 ROOM NO. 170951 DATE: 5.12.15 INSPECTOR: Geogra HA DESCRIPTION: PLACEMENT HA NO. 1-1 HA CONDITION: 20 NO COMMENTS: RACM: YES -FRIABLE ---CATI CAT I: -

PHOTO 23 – 5/12/15 – SAMPLE 7.1 – HA 7 CONCRETE DIAPHRAM



DIAPHRAM

en E		
WORAPH LOG - ACM SAMPLE		
PROJECT NO. 154316 CLIENT: FDOT 1 PROJECT LOCATION: Sacasets, FL BUILDING NAME: SR 760 Con Key Walking HT09514 Eb		
BUILDING NAME: JE ROOM NO. 10951 E6 DATE: 5:12:15 INSPECTOR: Greagery 7:5 HA NO. 121 HA DESCRIPTION: PLAPHEAD Greatery HA DESCRIPTION: PLAPHEAD GREAT		
HA CONDITION		A Part
FRIABLE - CATIL: RATE		
	5 – SAMPLE 7.3 – HA 7 ICRETE	



N:\Clients\FDOT FILES\FDOT 1 (BDV 75)\PROJECTS\154316 (LOA 47) - SE 789 (Little Ringling Bridge) asbestos survey\5.0 Reports\Bridge 170951\154316 - Br 170951\_AsbSurv, Paint Survey\_070815 FINAL.docx

PHOTOGRAPH LOG - ACM SAMPLE PROJECT NO. CLIENT: PROJECT LOCATION: BUILDING NAME: SR 100 ROOM NO. 17055 sot. DATE: F INSPECTOR: 5.12.1 KCA HA NO. PH HA DESCRIPTION: SUL- gider asplast HA CONDITION: COMMENTS: FRIABLE - K YES CAT I: NO \_\_\_ CAT II: \_\_ \_ RACM:

PHOTO 27 – 5/12/15 – SAMPLE 8.2 – HA 8 ASPHALT IMPREGNATED PAPER SUBGIRDER BEARING PAD

State Car	and the second s	
		and the start of
		and the set
	2007 AL	The start of the
		WY PLANIES
		al the second
	PHOTOGRAPH LOG - ACM SAMPLE	1 30 10 -
	PROJECT NO. 154316	ALL ST
MA SEL	CLIENT: FOOT 1 PROJECT LOCATION: Salagets FL	19 30 200
	BUILDING NAME: SR 780 mm, CODY and Some	1.1
	BOOM NO. 170951- Et	APR SOL
C Jackson	DATE: 5-12-15	
	HANO. PIL REPORT	
9-1	HA DESCRIPTION: SUB- grave aspect	NACE SPACE
	HA CONDITION: frir	
	COMMENTS:	
Argent a	COMMENTSNO	
	FRIABLE - K YES RACM:	
and a tolda	FRIABLE - K YES NO CAT I: RACM:	
Bart		
	the second se	
· All Standing	1	
All a start of the	to present and automatical language matching day \$1111	
	A custiana provaciant	
CAL SER		
All All All All		
and shaft		
	PHOTO 28 – 5/12/15 – SAMPLE 8.3 – HA 8	
	ASPHALT IMPREGNATED PAPER	

SUBGIRDER BEARING PAD






PHOTO 29 – 5/12/15 – SAMPLE 9.1 – HA 9 CONCRETE GIRDER



CONCRETE GIRDER

A State State of the		· Million	1. 18 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
	The second se	And the	
		State State	The Arman was the law of
STATE OF		The Market	4
	La and a state of the second	A The All And	and the second and
	Duone		1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
	PHOTOGRAPH LOG - ACM SAMPLE	The Part of	1 2 3
	PROJECT NO. 154 316	125 manual 1	Contraction of the second
	CLIENT: FDOT 1		1.3
	PROJECT LOCATION: Sarassta G		
Sec. 1	BUILDING NAME: SR 780 over Coon key Waterway	1 A .	in the second
	ROOM NO. 170951- EB	a . Reide	Billings
	DATE: 5.12.15		
	INSPECTOR: Gregorid		AL
100 C	HANO.		
A DESCRIPTION OF THE OWNER	HA DESCRIPTION: Gurders- conclute	A MARCH AND	and the second
100 C	HA CONDITION: Good		All the second
	COMMENTS:	ALL MATTING TO THE	
100	FRIABLE YES K NO		The Print of the second
	FRIABLE TE3         RACM:           CAT I: CAT II: RACM:	The And I service	the ship of
		and the second	and and a second second
		the stand of the	
	5×	E SA	
	Net considerate priors' determine weak subsected at the propagation by the 10/10/1		· /
and the second	Incloantheau ment and		
	and the second s		
	a strange the second		A
the second second		d and	

PHOTO 31 – 5/12/15 – SAMPLE 9.3 – HA 9 CONCRETE GIRDER



GIRDER

Surasole, C		1
120 31		1
PHOTOGRAPH LOG - ACM SAMPLE		- And
PROJECT NO. 154 au	· La State : 2	
CLIENT:FDOT1		
PROJECT LOCATION: Scant G	The second second	2 4
BUILDING NAME: SK 780 Ox1 Coon Key Waterman	and a second	X
ROOM NO. 170591 - EB		
DATE: 5-12-15		
INSPECTOR: Gregory HA NO. 102 10-3		
HANO. 10-2 10-3		
HA DESCRIPTION: Graders - Martin		
HA CONDITION: Good		
COMMENTS:		
TRIABLE - YES K NO		
CAT II:		
CATI		- 3-0
		* 1.
1		
and an an an and a set of the set		
numer damas prepari da una a su da su d	The state of the s	
JAC.		

PHOTO 33 – 5/12/15 – SAMPLE 10.2 – HA 10 MORTAR GIRDER

ONDER	
iense internet	
PHOTOGRAPH LOG - ACM SAMPLE PROJECT NO 154 3L CLIENT:	
PHOTO 34 – 5/12/15 – SAMPLE 10.3 – HA 10	
MORTAR GIRDER	

120 MP	
PHOTOGRAPH LOG - ACM SAMPLE	NICE NO.
CLIENT: <u>Too</u> PROJECT LOCATION: <u>Serasota, PC</u> BUILDING NAME: <u>SR 780 OUL Coon Kur</u> Wildum BUILDING NAME: <u>SR 780 OUL Coon Kur</u> Wildum ROOM NO. <u>170951-EB</u>	
HA NO. III HA DESCRIPTION: Sub-dick applant HA DESCRIPTION: Au	
HA CONDENTS: COMMENTS: FRIABLE - X YES RACM: FRIABLE - CAT II: CAT I:	
and the second sec	

PHOTO 35 – 5/12/15 – SAMPLE 11.1 – HA 11 ASPHALT IMPREGNATE PAPER SUBDECK BEARING PAD

2-15-12- 5-16 and the series are and the series are and the series are series	
ACM SAMPLE	
PROJECT NOGYJL LIENT:	
PHOTO 36 – 5/12/15 – SAMPLE 11.2 – HA 11 ASPHALT IMPREGNATE PAPER	

SUBDECK BEARING PAD

and	
the second as a los	
and the set of the set	
Contraction and the second	
ACM SAMPLE	
Acmora	
malle	
PROJECT NO. 59 316 FDOT 1 FOOT SCALE FULLY FROM FOOT	the second se
BUILDING NAME: SR TRO OKL Gen kullingant	and the second se
PROJECT LOCATE SR TRO CLAS	
BUILDING NAME: SK ALE BUILDING NAME: SK ALE ROOM NO. 170351: ED ROOM NO. 170351: ED	
DATE: 5: 12: 12: 12: 12: 12: 12: 12: 12: 12: 12	
HA NO. AL ALLAND ALLAND	
HA DESCRIPTION AND	
HA DESCRIT HA CONDITION:	對國際自由國外 医下颌的
HA CONDITIS	
COM YEL	
HA CONDITIE	
CATI	
PHOTO 37 – 5/12/15 – SAMI ASPHALT IMPREGNA	
ASPHALT IMPREGNA	ATE PAPER
	ATE PAPER
ASPHALT IMPREGNA	ATE PAPER
ASPHALT IMPREGNA SUBDECK BEARIN	ATE PAPER
ASPHALT IMPREGNA SUBDECK BEARIN	ATE PAPER
ASPHALT IMPREGNA SUBDECK BEARIN PHOTOGRAPH LOG – ACM SAMPLE	ATE PAPER
ASPHALT IMPREGNA SUBDECK BEARIN PHOTOGRAPH LOG – ACM SAMPLE PROJECT NO. /SV314	ATE PAPER
ASPHALT IMPREGNA SUBDECK BEARIN PHOTOGRAPH LOG – ACM SAMPLE PROJECT NO. /54316 CLIENT: FDOT 1	ATE PAPER
ASPHALT IMPREGNA SUBDECK BEARIN PHOTOGRAPH LOG – ACM SAMPLE PROJECT NO. /5¥316 CLIENT: FDOT 1 PROJECT LOCATION: Service 51	ATE PAPER
ASPHALT IMPREGNA SUBDECK BEARIN PHOTOGRAPH LOG – ACM SAMPLE PROJECT NO. /54316 CLIENT: FDOT 1 PROJECT LOCATION: Saca (Dia, 51 BUILDING NAME: \$2,766 area (on Key Independent)	ATE PAPER
ASPHALT IMPREGNA SUBDECK BEARIN PHOTOGRAPH LOG - ACM SAMPLE PROJECT NO. /54316 CLIENT: FDOT 1 PROJECT LOCATION: Seres Dia, 51 BUILDING NAME: 92 780 over (conc Key Waterway ROOM NO. 170 951 - 63	ATE PAPER
ASPHALT IMPREGNA SUBDECK BEARING PHOTOGRAPH LOG - ACM SAMPLE PROJECT NO/5Y316 CLIENT:FDOT 1 PROJECT LOCATION: Saras Dita, 51 BUILDING NAME: 52 786 over (ook Key Waterway ROOM NO172 951 - 63 DATE:	ATE PAPER
ASPHALT IMPREGNA SUBDECK BEARING PHOTOGRAPH LOG - ACM SAMPLE PROJECT NO. <u>ISV316</u> CLIENT: <u>FDOT 1</u> PROJECT LOCATION: <u>Saras Ota</u> , <u>F1</u> BUILDING NAME: <u>SP 766 over (one Key Wederway</u> ROOM NO. <u>176 951 - 63</u> DATE: <u>S112/15</u> INSPECTOR: <u>Rochus</u>	ATE PAPER
ASPHALT IMPREGNA SUBDECK BEARING PHOTOGRAPH LOG - ACM SAMPLE PROJECT NO. /54316 CLIENT: FDOT 1 PROJECT LOCATION: Seras Dia, F1 BUILDING NAME: 92 700 over (ook Key Worksrowy ROOM NO. 172951-63 DATE: 5/12/15 INSPECTOR: Rocha HA NO. 12 · 1 2 3 4 GMGK	ATE PAPER
ASPHALT IMPREGNA SUBDECK BEARING PHOTOGRAPH LOG - ACM SAMPLE PROJECT NO. <u>ISV316</u> CLIENT: <u>FDOT 1</u> PROJECT LOCATION: <u>Saras Ota</u> , <u>F1</u> BUILDING NAME: <u>SP 766 over (one Key Wederway</u> ROOM NO. <u>176 951 - 63</u> DATE: <u>S112/15</u> INSPECTOR: <u>Rochus</u>	ATE PAPER
ASPHALT IMPREGNA SUBDECK BEARING PHOTOGRAPH LOG - ACM SAMPLE PROJECT NO	ATE PAPER
ASPHALT IMPREGNA SUBDECK BEARING PHOTOGRAPH LOG - ACM SAMPLE PROJECT NO	ATE PAPER
ASPHALT IMPREGNA SUBDECK BEARING PHOTOGRAPH LOG - ACM SAMPLE PROJECT NO	ATE PAPER
ASPHALT IMPREGNA SUBDECK BEARING         PHOTOGRAPH LOG - ACM SAMPLE         PROJECT NO.       /5Y316         CLIENT:       FDOT 1         PROJECT LOCATION:       Saras Sala, FI         BUILDING NAME:       \$200 over (over Key Wederway)         ROOM NO.       172 951 - 63         DATE:       5/12/-5         INSPECTOR:       Beable         HA NO.       12 - 1 - 2 - 3 - 4 0 M/SC         HA DESCRIPTION:       Expansion Joint         HA CONDITION:       gcol         COMMENTS:	ATE PAPER
ASPHALT IMPREGNA SUBDECK BEARING         PHOTOGRAPH LOG - ACM SAMPLE         PROJECT NO.       /5Y316         CLIENT:       FDOT 1         PROJECT LOCATION:       Saras Sala, FI         BUILDING NAME:       \$200 over (over Key Wederway)         ROOM NO.       172 951 - 63         DATE:       5/12/-5         INSPECTOR:       Beable         HA NO.       12 - 1 - 2 - 3 - 4 0 M/SC         HA DESCRIPTION:       Expansion Joint         HA CONDITION:       gcol         COMMENTS:	ATE PAPER
ASPHALT IMPREGNA SUBDECK BEARING PHOTOGRAPH LOG - ACM SAMPLE PROJECT NO. /SY316 CLIENT: FDOT 1 PROJECT LOCATION: Serestoria, F1 BUILDING NAME: & 760 ever (see Key Waterway ROOM NO. 170951-63 DATE: S/12/15 INSPECTOR: Rochae HA NO. 12 - 1 2 3 4 GM/SC HA DESCRIPTION: Expansion Joint HA CONDITION: good	ATE PAPER
ASPHALT IMPREGNA SUBDECK BEARING         PHOTOGRAPH LOG - ACM SAMPLE         PROJECT NO.       /5Y316         CLIENT:       FDOT 1         PROJECT LOCATION:       Saras Sala, FI         BUILDING NAME:       \$200 over (over Key Wederway)         ROOM NO.       172 951 - 63         DATE:       5/12/-5         INSPECTOR:       Beable         HA NO.       12 - 1 - 2 - 3 - 4 0 M/SC         HA DESCRIPTION:       Expansion Joint         HA CONDITION:       gcol         COMMENTS:	ATE PAPER
ASPHALT IMPREGNA SUBDECK BEARING         PHOTOGRAPH LOG - ACM SAMPLE         PROJECT NO.       /5Y316         CLIENT:       FDOT 1         PROJECT LOCATION:       Saras Sala, FI         BUILDING NAME:       \$200 over (over Key Wederway)         ROOM NO.       172 951 - 63         DATE:       5/12/-5         INSPECTOR:       Beable         HA NO.       12 - 1 - 2 - 3 - 4 0 M/SC         HA DESCRIPTION:       Expansion Joint         HA CONDITION:       gcol         COMMENTS:	ATE PAPER
ASPHALT IMPREGNA SUBDECK BEARING         PHOTOGRAPH LOG - ACM SAMPLE         PROJECT NO.       /5Y316         CLIENT:       FDOT 1         PROJECT LOCATION:       Saras Sala, FI         BUILDING NAME:       \$200 over (over Key Wederway)         ROOM NO.       172 951 - 63         DATE:       5/12/-5         INSPECTOR:       Beable         HA NO.       12 - 1 - 2 - 3 - 4 0 M/SC         HA DESCRIPTION:       Expansion Joint         HA CONDITION:       gcol         COMMENTS:	ATE PAPER
ASPALTIMPREAMENTS	ATE PAPER
ASPHALT IMPREGNA SUBDECK BEARING         PHOTOGRAPH LOG - ACM SAMPLE         PROJECT NO.       /5Y316         CLIENT:       FDOT 1         PROJECT LOCATION:       Saras Sala, FI         BUILDING NAME:       \$200 over (over Key Wederway)         ROOM NO.       172 951 - 63         DATE:       5/12/-5         INSPECTOR:       Beable         HA NO.       12 - 1 - 2 - 3 - 4 0 M/SC         HA DESCRIPTION:       Expansion Joint         HA CONDITION:       gcol         COMMENTS:	ATE PAPER

**EXPANSION JOINT** 

and the second s
and the second sec
and the second
and the second

	in the	
PHOTOGRAPH LOG - ACM SAMPLE	A REAL PROPERTY	
PROJECT NO. 154316	and the second	
CLIENT: FDOT 1 PROJECT LOCATION: Same Soite, SI		
BUILDING NAME: SR 780 over (oon key Waterway		
ROOM NO. 170951-63 DATE: 5/12/15		1
INSPECTOR Realize	the share of	- and
HA NO. 12 . 7		-
HA DESCRIPTION: Expansion Joint		
HA CONDITION: good	F. 2.2	a sugar the
COMMENTS:	5.445	
FRIABLE - YES NO	- "	
CAT I: CAT II: RACM:	A PARTY COMPANY	and the second
	1.3.200	18 8 A . O

PHOTO 41 – 5/12/15 – SAMPLE 12.4 QA/QC – HA 12 RUBBER CAULKING EXPANSION JOINT

PHOTOGRAPH LOG - ACM SAMPLE         PROJECT NO	
PHOTO 42 – 5/12/15 – SAMPLE 13 CONCRETE RAILING - RAIL	3.1 – HA 13

PHOTOGRAPH LOG - ACM SAMPLE	
PROJECT NO. 154316 CLIENT: FDOT 1 PROJECT LOCATION: Serester f 1 BUILDING NAME: SR 780 over Coon Ley Underway	
BUILDING NAME	
HANO. 13 Pailings	
HA DESCRIPTION	and the second sec
FRIABLE - YES NU CAT I: CAT II: RACM:	

PHOTO 43 – 5/12/15 – SAMPLE 13.2 – HA 13 CONCRETE RAILING - RAIL

PROJECT NO	
Proversione providence and the state of a state of the st	TE
PHOTOGRAPH LOG - ACM SAMPLE PROJECT NO. 1543/6 CLIENT: FDOT 1 PROJECT LOCATION: Sarasota, S1 BUILDING NAME: 52 708 over Coon Key Work	

 PHOTOGRAPH LOG - ACM SAMPLE

 PROJECT NO. \_ PUBL

 PROJECT LOCATION: Sectoria, S.I.

 PROJECT LOCATION: Sectoria, Sectoria, S.J.

 PROJECT LOCATION: Sectoria, Sectoria, S.J.

 PROJECT LOCATION: Sectoria, Sectoria, S.J.

 PROJECT LOCATION: Sectoria, Sector

a state of the		
		A State of the second s
	PHOTOGRAPH LOG - ACM SAMPLE	
	PROJECT NO. 154316	A State of the second sec
	CLIENT: FDOT 1 PROJECT LOCATION: Sarasota, 51	A March and A
A. S. S. S. S.	BUILDING NAME: SR 708 over Coon Key Work	inwey a state of the state of t
1 Acres	ROOM NO. 170951 - EB DATE: 5/12/15	
	INSPECTOR: Roebke Bregory	- A
	HA NO. <u>14</u> <del>3</del> HA DESCRIPTION: <u>END</u> CAP	
621	COMMENTS:	_
its of for	FRIABLE - YES NO	
a for the second	CAT I: CAT II: RACM:	
1 and 1		
	Ave uservånnan projety documentelentelabelen field forma amplensig der 45/12/5	
	PHOTO 47 – 5/12/15 – SAMP	LE 14.3 – HA 14
	CONCRETE END CAP	
	PHOTOGRAPH	
	PHOTOGRAPH LOG - ACM SAMPLE	
	PROJECT NO. /543/6 CLIENT: FDOT 1	The state and the second
	RUJECT LOCATE	- Harden and the Charten and the
R	DOM NO. 1709-1	
DA		CONTRACTOR DE LA CONTRA
НА	PECTOR: <u>Roebke / Gregory</u> No. 15 · 1 2 3	- Aller and a second se
_	LOCRIPTION: Corb	
HA C	ONDITION: 200)	
	MENTS:	Contraction and the second
CAT I:	LE - YES VNO	
	TES NO CAT II: RACM:	
Air: Userstillerum		
- 4 × (10) (40	interest work and exact field three sempleming day (\$1215	A STATE AND A STATE
		A CONTRACT OF A CONTRACT
	PHOTO 48 – 5/12/15 – SAMP	E 15 1 - HA 15
	CONCRETE	LE 13.1 - HA 13
	CURB	

A CONTRACTOR OF A CONTRACTOR O	
PHOTOGRAPH LOG – ACM SAMPLE	and the second s
A HOTOGRAFH LOG - ACM SAMPLE	
PROJECT NO. 154316	
CLIENT: FDOT 1	
PROJECT LOCATION: Sarasota, SI	Carl Carl Carl Carl Carl Carl Carl Carl
BUILDING NAME: 52 780 over to coon Key Waternay ROOM NO. 170951 - EB	
DATE: chalue	
INSPECTOR: Roebke / Gregory	- Alexandre and a second and a se
HA NO. 15	and the second
HA DESCRIPTION: Curle	A CARLER CONTRACTOR
HA CONDITION: 300	
COMMENTS:	
FRIABLE - YES V NO	
CAT I: CAT II: RACM:	
Also sumethouse grapery discusses interview discusses interruption by day (55/2)/5	
1	

PHOTO 49 – 5/12/15 – SAMPLE 15.2 – HA 15 CONCRETE CURB

HU CO FRI CAT	PHOTOGRAPH LOG - ACM SAMPLE  PROJECT NO / SY 3/6 CLIENT: _ FDOT 1 PROJECT LOCATION: Sarascta . S( BUILDING NAME: SE 280 over _ Coos Key Wormen ROOM NO / 70951 - E3 DATE: _ \$/a/15 INSPECTOR: 2006bke / Gregory HA NO 15	
	PHOTO 50 – 5/12/15 – SAMF CONCRETE CURB	

,	
PHOTOCOLOGI	
PHOTOGRAPH LOG – ACM SAMPLE	
PROJECT NO. 154316	
CLIENT:FDOT 1	
PROJECT LOCATION: Sarasota, FI	
	A MARTIN AND A MARTIN AND A MARTIN
DATE: S/12/10	
INSPECTOR: Padda 10	31 And Andrewson and
HA DESCRIPTION: Bridge deck	
HA CONDITION: 9.00k	and a second second second
COMMENTS:	B. Comment
	and a strain of the second strain
FRIABLE - YES V NO	A STATE OF A STATE OF A STATE OF A STATE
CAT I: CAT II: RACM:	
	no l
Are somethinnan grappe) damannanseed andersta field damantampleating date 6512/15	
	B. martha Branches and a string the
	N9
PHOTO 51 – 5/12/15 – S	SAMPLE 16.1 – HA 16
CONCE	
CONCr	RETE
DEC	
DEC	
DEC PHOTOGRAPH LOG - ACM SAMPLE	
DEC PHOTOGRAPH LOG - ACM SAMPLE PROJECT NO. 15/13/6	
DEC PHOTOGRAPH LOG - ACM SAMPLE	
DEC	
PHOTOGRAPH LOG - ACM SAMPLE PROJECT NO. /SV/3/6 CLIENT:	
PHOTOGRAPH LOG - ACM SAMPLE PROJECT NO	
PHOTOGRAPH LOG - ACM SAMPLE PROJECT NO	
PHOTOGRAPH LOG - ACM SAMPLE PROJECT NO	
DEC	
PHOTOGRAPH LOG - ACM SAMPLE  PROJECT NO	
PHOTOGRAPH LOG - ACM SAMPLE  PROJECT NO	
PHOTOGRAPH LOG - ACM SAMPLE  PROJECT NO	
PHOTOGRAPH LOG - ACM SAMPLE  PROJECT NO	

DECK

PHOTOGRAPH LOG - ACM SAMPLE         PROJECT NO.       /54/316         CLIENT:       FDOT 1         PROJECT LOCATION:       Sarasota, \$1         BUILDING NAME:       Sarasota, \$2         BATE:       Sarasota, \$2         BATE:       Sarasota, \$2         HA DESCRIPTION:       Bridge deck         HA CONDITION:       Sarasota, \$2         Sarasota, \$2       Sarasota, \$3         BATE:       Sarasota, \$3         BATE:       Sarasota, \$3         BATE: <th></th>	
FRIABLE - YES NO CAT I: CAT II: RACM: PHOTO 53 – 5/12/15 – SAM CONCRET DECK	
PHOTOGRAPH LOG - ACM SAMP         PROJECT NO.       154316         CLIENT:       FDOT 1         PROJECT LOCATION:       Sarasota, f/         BUILDING NAME:       SP 280 over (and key)         ROOM NO.       170951 - EA         DATE:       \$/12/1s         INSPECTOR:       Roebke/Gregory         HA NO.       17 - 1       2         HA DESCRIPTION:       Roiling Post         HA CONDITION:       good         COMMENTS:	
PHOTO 54 – 5/12/15 – SAM CONCRET RAILING - P	ſE

A State of the second	
PHOTOGRAPH LOG – ACM SAMPLE	
PROJECT NO. 154316 CLIENT: FDOT 1	and and the
PROJECT LOCATION: Sarasota, FI	Stern Mars // K
BUILDING NAME: SR 780 over Coop Key Woterway ROOM NO. 170951 - EB	Service 1/2
DATE: <u>S/12/15</u> INSPECTOR: <u>Roebke/Gregory</u>	C. Carl
12 1 2 3	Constitution of the second
HA DESCRIPTION: Kailing fast	
HA CONDITION:	
COMMENTS:	
FRIABLEYES NO CAT I: CAT II: RACM:	
CAT I: CAT	
A photos field downerspiceling day 1971213	
PHOTO 55 – 5/12/15 – SAMPLE <sup>-</sup> CONCRETE	17.2 – HA 17
PHOTO 55 – 5/12/15 – SAMPLE *	17.2 – HA 17
PHOTO 55 – 5/12/15 – SAMPLE <sup>-</sup> CONCRETE	17.2 – HA 17
PHOTO 55 – 5/12/15 – SAMPLE <sup>-</sup> CONCRETE	17.2 – HA 17
PHOTO 55 – 5/12/15 – SAMPLE CONCRETE RAILING - POST PHOTOGRAPH LOG – ACM SAMPLE	17.2 – HA 17
PHOTO 55 – 5/12/15 – SAMPLE CONCRETE RAILING - POST PHOTOGRAPH LOG – ACM SAMPLE PROJECT NO. <u>1543/6</u> CLIENT: <u>FDOT 1</u>	17.2 – HA 17
PHOTO 55 – 5/12/15 – SAMPLE CONCRETE RAILING - POST PHOTOGRAPH LOG – ACM SAMPLE PROJECT NO. <u>1543/6</u> CLIENT: <u>FDOT 1</u> PROJECT LOCATION: <u>Sarazota, F/</u>	17.2 – HA 17
PHOTO 55 – 5/12/15 – SAMPLE CONCRETE RAILING - POST PHOTOGRAPH LOG – ACM SAMPLE PROJECT NO. <u>1543/6</u> CLIENT: <u>FDOT 1</u>	17.2 – HA 17
PHOTO 55 – 5/12/15 – SAMPLE CONCRETE RAILING - POST PHOTOGRAPH LOG – ACM SAMPLE PROJECT NO. 1543/6 CLIENT: FDOT 1 PROJECT LOCATION: Sarasota, F/ BUILDING NAME: 52 780 over Coos Key Woterlow ROOM NO. 170951 - EB DATE: \$/12/15	17.2 – HA 17
PHOTO 55 – 5/12/15 – SAMPLE CONCRETE RAILING - POST PHOTOGRAPH LOG – ACM SAMPLE PROJECT NO. 1543/6 CLIENT: FDOT 1 PROJECT LOCATION: Sarasota, F/ BUILDING NAME: 52 780 over (son Key Wotersey ROOM NO. 170951 - EB DATE: \$/12/15 INSPECTOR: Loebke/Sregory	17.2 – HA 17
PHOTO 55 - 5/12/15 - SAMPLE CONCRETE RAILING - POST PHOTOGRAPH LOG - ACM SAMPLE PROJECT NO. 154316 CLIENT: FDOT 1 PROJECT LOCATION: Sarasola, F/ BUILDING NAME: SR 780 over Cooa Key Woterway ROOM NO. 170451 - EB DATE: \$/12/15 INSPECTOR: Coebke/Sregary HA NO. 17 - W	17.2 – HA 17
PHOTO 55 - 5/12/15 - SAMPLE CONCRETE RAILING - POST PHOTOGRAPH LOG - ACM SAMPLE PROJECT NO. 1543/6 CLIENT: FDOT 1 PROJECT LOCATION: Sarasota, F/ BUILDING NAME: SR 190 over (oon key Woterway ROOM NO. 170951 - EB DATE: \$/12/15 INSPECTOR: Loebke/Gregory HA NO. 17 - M M 3 HA DESCRIPTION: Loiling Post	17.2 – HA 17
PHOTO 55 - 5/12/15 - SAMPLE CONCRETE RAILING - POST PHOTOGRAPH LOG - ACM SAMPLE PROJECT NO. 154316 CLIENT: FDOT 1 PROJECT LOCATION: Sarasola, F/ BUILDING NAME: SR 780 over Cooa Key Woterway ROOM NO. 170451 - EB DATE: \$/12/15 INSPECTOR: Coebke/Sregary HA NO. 17 - K	
PHOTO 55 - 5/12/15 - SAMPLE CONCRETE RAILING - POST         CONCRETE RAILING - POST         PHOTOGRAPH LOG - ACM SAMPLE         PROJECT NO.       1543/6         CLIENT:       FDOT 1         PROJECT LOCATION:       Sare 30/a, F/         BUILDING NAME:       52 780 over (con key Woterway         ROOM NO.       170451 - EB         DATE:       5/12/15         INSPECTOR:       Coebke/Sregory         HA NO.       17 - M         HA CONDITION:       Sailing         COMMENTS:	
PHOTO 55 - 5/12/15 - SAMPLE CONCRETE RAILING - POST         PHOTOGRAPH LOG - ACM SAMPLE         PROJECT NO.       1543/6         CLIENT:       FDOT 1         PROJECT LOCATION:       Sarasota, f/         BUILDING NAME:       Sarasota, f/         BUATE:       Slobeke         Sarasota, foregory       HA NO. 17 - M         HA DESCRIPTION:       Railing         Builtion:       Good         COMMENTS:       FRIABLEYES	
PHOTO 55 - 5/12/15 - SAMPLE CONCRETE RAILING - POST         CONCRETE RAILING - POST         PHOTOGRAPH LOG - ACM SAMPLE         PROJECT NO.       1543/6         CLIENT:       FDOT 1         PROJECT LOCATION:       Sarasota, F/         BUILDING NAME:       52 780 over (con key Woterway         ROOM NO.       170451 - EB         DATE:       S/12/15         INSPECTOR:       Roebke/Sregory         HA NO.       17 - M         HA CONDITION:       Sailing         Scomments:	<text></text>
PHOTO 55 - 5/12/15 - SAMPLE CONCRETE RAILING - POST         PHOTOGRAPH LOG - ACM SAMPLE         PROJECT NO.       1543/6         CLIENT:       FDOT 1         PROJECT LOCATION:       Sarasola, f/         BUILDING NAME:       Sarasola, f/         BUATE:       Slobeke         Sarasola, f/       Sarasola, f/         HA DESCRIPTION:       Railing Past         HA CONDITION:       Gaod         COMMENTS:	<section-header></section-header>

**RAILING - POST** 

	PHOTOGRAPH LOG – ACM SAMPLE	Margar
		E MA CONT
	PROJECT NO. 1543/6 CLIENT: FDOT 1	A Y LAN
	PROJECT LOCATION: Sarasota, 5 (	A A A A A A A A A A A A A A A A A A A
	BUILDING NAME: SR 780 over Loon Key Waterway	
	ROOM NO. 170957 - EB	
	DATE: S/12/15	
	INSPECTOR: Roebke/ Gragory	
	HANO. 18-01 82 +3 400/00	
	HA DESCRIPTION: Deck Coment	
	HA CONDITION: 5000	
	COMMENTS	
	FRIABLE - YES YES NO	
	CAT I: CAT II: RACM:	
		and the second se
	Ve unser thomas prepary documents work addentor field forms acceptorolog doc. 05(12)15	
	PHOTO 57 – 5/12/15 – SAMPLE 18.1 – I	HA 18
	MORTAR	
	DECK	
1. 1		
-130		
a start		A State of the second
100		A State of the second second
Sec.		
	ACM SAMPLE	
	PHOTOGRAPH LOG – ACM SAMPLE	Sec. Sec.
		A Start
	PROJECT NO. 1543/6	
	PROJECT NO. <u>1543/6</u> CLIENT: <u>FDOT 1</u>	
	PROJECT NO. 1543/6 CLIENT: FDOT 1 PROJECT LOCATION: Sarasota, 5 ( PROJECT LOCATION: Sarasota, 5 ( PROJECT NO. 1543/6	
	PROJECT NO. <u>1543/6</u> CLIENT: <u>FDOT 1</u> PROJECT LOCATION: <u>Sara sota, 5 (</u> BUILDING NAME: <u>52 780 over Loca key Haterway</u> ROOM NO. <u>170 957 - ER</u>	
	PROJECT NO. <u>1543/6</u> CLIENT: <u>FDOT 1</u> PROJECT LOCATION: <u>Sarasota, F(</u> BUILDING NAME: <u>52, 780 over Loca Key Naterway</u> ROOM NO. <u>170 957 - ER</u> NOTE: <u>510/15</u>	
	PROJECT NO. <u>1543/6</u> CLIENT: <u>FDOT 1</u> PROJECT LOCATION: <u>Sarasota, F(</u> BUILDING NAME: <u>52, 780 over Loca Key Naterway</u> ROOM NO. <u>170 957 - ER</u> NOTE: <u>510/15</u>	
	PROJECT NO. <u>1543/6</u> CLIENT: <u>FDOT 1</u> PROJECT LOCATION: <u>Sarasota, F(</u> BUILDING NAME: <u>52, 780 over Loca Key Naterway</u> ROOM NO. <u>170 957 - ER</u> NOTE: <u>510/15</u>	
a de la dela dela dela dela dela dela de	PROJECT NO. <u>1543/6</u> CLIENT: <u>FDOT 1</u> PROJECT LOCATION: <u>Sara sota, 5 (</u> BUILDING NAME: <u>52 700 over (son key histerway</u> ROOM NO. <u>170 957 - ER</u> DATE: <u>SJR/15</u> INSPECTOR: <u>Boeble/Arezory</u> HA NO. <u>18 - 2 2 3 4 on/ac</u> HA DESCRIPTION: <u>Jest Peck (ov</u> er the source)	
6	PROJECT NO. <u>1543/6</u> CLIENT: <u>FDOT 1</u> PROJECT LOCATION: <u>Sara sota, E (</u> BUILDING NAME: <u>52 790 over loca key biterway</u> ROOM NO. <u>170 977 - ER</u> DATE: <u>S/12/15</u> INSPECTOR: <u>Roeble:/foregory</u> HA NO. <u>18 - F &amp; 2 &amp; 3 y on/ac</u> HA DESCRIPTION: <u>Soco</u> Peck Coment	
6	PROJECT NO. <u>1543/6</u> CLIENT: <u>FDOT 1</u> PROJECT LOCATION: <u>Sara sota, E (</u> BUILDING NAME: <u>52 780 over look key hiterway</u> ROOM NO. <u>170 977 - ER</u> DATE: <u>S/12/15</u> INSPECTOR: <u>Roebles/Asteropy</u> HA NO. <u>18 - 4 &amp; 2 &amp; 3 y on/ac</u> HA DESCRIPTION: <u>Soco</u> <u>Peck (enert</u> HA CONDITION: <u>Soco</u>	
	PROJECT NO. <u>1543/6</u> CLIENT: <u>FDOT 1</u> PROJECT LOCATION: <u>Sara sota, E (</u> BUILDING NAME: <u>52 780 over look key hiterway</u> ROOM NO. <u>170 977 - ER</u> DATE: <u>S/12/15</u> INSPECTOR: <u>Roebles/Aregory</u> HA NO. <u>18 - 4 2 3 4 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0</u>	
	PROJECT NO. <u>1543/6</u> CLIENT: <u>FDOT 1</u> PROJECT LOCATION: <u>Sara sota, E (</u> BUILDING NAME: <u>52 780 over look key hiterway</u> ROOM NO. <u>170 977 - ER</u> DATE: <u>S/12/15</u> INSPECTOR: <u>Roebles/Aregory</u> HA NO. <u>18 - 4 2 3 4 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0</u>	
	PROJECT NO. <u>1543/6</u> CLIENT: <u>FDOT 1</u> PROJECT LOCATION: <u>Sara sota, E (</u> BUILDING NAME: <u>52 780 over look key hiterway</u> ROOM NO. <u>170 977 - ER</u> DATE: <u>S/12/15</u> INSPECTOR: <u>Roebles/Asteropy</u> HA NO. <u>18 - 4 &amp; 2 &amp; 3 y on/ac</u> HA DESCRIPTION: <u>Soco</u> <u>Peck (enert</u> HA CONDITION: <u>Soco</u>	
	PROJECT NO. <u>1543/6</u> CLIENT: <u>FDOT 1</u> PROJECT LOCATION: <u>Sara sota, E (</u> BUILDING NAME: <u>52 780 over look key hiterway</u> ROOM NO. <u>170 977 - ER</u> DATE: <u>S/12/15</u> INSPECTOR: <u>Roebles/Aregory</u> HA NO. <u>18 - 4 2 3 4 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0</u>	
	PROJECT NO. <u>1543/6</u> CLIENT: <u>FDOT 1</u> PROJECT LOCATION: <u>Sara sota, E (</u> BUILDING NAME: <u>52 780 over look key hiterway</u> ROOM NO. <u>170 977 - ER</u> DATE: <u>S/12/15</u> INSPECTOR: <u>Roebles/Aregory</u> HA NO. <u>18 - 4 2 3 4 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0</u>	

DECK

35.4		
2		
	PHOTOGRAPH LOG – ACM SAMPLE	
	PROJECT NO. 1543/6	A State of the second
	CLIENT: FDOT 1 PROJECT LOCATION: Sara Sota, 5 (	and the second
	BUILDING NAME: 52 780 over Loon Key Waterway ROOM NO. 170 957 - ER	
	DATE: 5/12/15 INSPECTOR: Boebke/ gregoly	A second s
	HAND 18- 0 \$ 43 404/0C	
	HA NO HA DESCRIPTION: Deck (ement	
	HA CONDITION:	
	FRIABLE YES NO	
	CAT I: CAT II: RACM:	The second second
	isarrihansi prpry decumentiveritabener field frantamplanting der 151215	
JA'c	lauerethonial projot desimilativeer autonovice and	
	DECK	
	PHOTOGRAPH LOG – ACM SAMPLE	
	PROJECT NO. 1543/6	
	CLIENT:FDOT 1	
	PROJECT LOCATION: Sarasota, El BUILDING NAME: SR 780 over Loon Key Literwa	4
	ROOM NO. 170957 - ER	
-	DATE: S/1/15 INSPECTOR: Roebke/Bregory	
	HANO. 18- 0 # ## 4 04/0C	
-	HA DESCRIPTION: Deck Cemen	
	IA CONDITION: 500	
_		
	RIABLE YES NO AT I: CAT II: RACM:	
CA		
		Contraction of the
JAic lasers)	thomais graphy-documents work adverses field forms assuppleating disc 10/12/15	

PHOTOGRAPH LOG - ACM SAMPLE	
PROJECT NO. 154316	
CLIENT:	
	manage and
BUILDING NAME: SR 780 over Cook Key Woterway ROOM NO. 170951 - EB	
ROOM NO. 170951 - Over Coon Key Waterway	Set in some of the set
DATE: 5/12 LC	NAME OF TAXABLE PARTY OF TAXABLE PARTY.
INSPECTOR: Dochka (Gua	and the second sec
INSPECTOR: <u>Doebke/Gregory</u> HA NO. 19 - 1 2 3 HA DESCRIPTION: Reflector Marine	the second second second second
Terrettor Misstic	
HA CONDITION: good	State - State
COMMENTS:	the state of the second
FRIABLE - YES YES NO	Plant Land the Serie and
CAT I: CAT II: RACM:	a description of the second
	- Contraction and Contraction of the
	and the second sec
wints work aubentor field forms acmphotolog doc 05/12/15	
	and the second second second second
	and the second sec
PHOTO 61 – 5/12/15 – S BLACK ADHES	IVE MASTIC
UNDER REFLECT	
and the second second	· · · · ·
	and the second s

	11 A. S.
PHOTOGRAPH LOG - ACM SAMPLE         PROJECT NO.       1549316         CLIENT:       FDOT1         PROJECT LOCATION:       Sara Sotte, S1         BUILDING NAME:       S2 780 over Gene Key Waterover         ROOM NO.       170951 - EB         DATE:       5/2).s         INSPECTOR:       Deable/Gregory         HA NO.       19 - X       2         HA CONDITION:       Good         COMMENTS:       Comments:	
FRIABLE YES NO CAT I: CAT II: RACM:	
JAV: warribuma prpry knowner wakakteur field Inne angloning die 051215	• 2 [ -

UNDER REFLECTORS ON DECK

PHOTOGRAPH LOG - ACM SAMPLE	
LOGRAPH LOG - A CH	
PROJECT NO	The second se
PROJECT NO. 154316 CLIENT:	
CLIENT: FDOT 1	Testing and the second second
BILLI -	Constant of the owner
PROJECT LOCATION: Sera Sota, SI BUILDING NAME: SR 200	
NOOM NO	
DATE: 5/12/15	
INSPECTOR. D. LL	
HANO, 19 North Gregory	-
HA NO. 19 - X A 3 HA DESCRIPTION: Reflecter M	
HA DESCRIPTION: Reflector Mastic	
HA CONDITION	
HA CONDITION: 500	
	The second of the second of the second
FRIABLE .	The second second second second second
FRIABLE - YES Y NO	
CAT I: CAT II: RACM:	
and the car a second second	
	Dh.
	the second s
	State of the state
JA's 'users' thomas gregory' documents work' aslessos field former 6512/15	•
1	A CONTRACT STRUCTURE
	and the second second second second second second
PHOTO 63 – 5/12/15 – SAM	MPLE 19.3 – HA 19
BLACK ADHESIV	
UNDER REFLECTOR	
	and the second
PHOTOGRAPH LOG - ACM SAME	PLE
PHOTOGRAPH LOG - AGIN CHANNEL	and the second sec
PROJECT NO. 154316	
CLIENT: FDOT 1 PROJECT LOCATION: Sure state , FI	
PROJECT LOCATION: Sares to , +T BUILDING NAME: SR 780 DURL COOL	key uburney
BUILDING NAME: SE 750 DAME	
DATE: 5/12/15	- Zeneral State Ball
INSPECTOR: COLORE / GOOD	
HA NO. 20 - 1 2 3	ting
HA NO. 20 - 1 2 HA DESCRIPTION: Class V cco	
In stall	
HA CONDITION: good	
COMMENTS:	
NO	
FRIABLE - YES V NO CAT I: CAT II: RACM	
CAT II:	
CATI	
CATI	
CATI	
CAT II.	

PHOTO 64 – 5/12/15 – SAMPLE 20.1 – HA 20 CLASS 5 COATING RAILINGS

	PHOTOGRAPH LOG – ACM SAMPLE	Street Street Street Street Street
	PROJECT NO. 154316	Section and
- Same	CLIENT: FDOT 1	AT STATISTICS
	PROJECT LOCATION: Saresta , FI	
and the second second	BUILDING NAME: SR 780 over Coon key likering	
The second	ROOM NO. 170951 - 68	
	DATE: 5/12/15	
	INSPECTOR: Roebke / Gregory	
	HA NO. 20 - # 2 3	destina and
	HA DESCRIPTION: Class V coating	
and the second second	HA CONDITION: good	
	COMMENTS:	
Stapper .		
	FRIABLE - YES V NO	
and the second sec	CAT I: CAT II: RACM:	
		and the second s
and the second s		10 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
A B	understendeligt former aansphanking das 15/12/15	
	PHOTO 65 – 5/12/15 – SAMPLE 20.2 – HA 20	
	CLASS 5 COATING	
	RAILINGS	
A A A A A A A A A A A A A A A A A A A		
	and the second se	
and the second		
	PHOTOGRAPH LOG – ACM SAMPLE	
	PROJECT NO. 154316	and the second s
	CLIENT: FDOT 1	
D.	PROJECT LOCATION: Sarestate , 51	
	BUILDING NAME: SR 780 OVER COOR Key Whiteway	
19-0-0-0-0-0-0-0-0-0-0-0-0-0-0-0-0-0-0-0	ROOM NO. 170951 - 58 DATE: 5/12/15	and the second second
	INSPECTOR: Roebke / Gregory	and a second
		and the second
	HA DESCRIPTION: Class V ceating	a hand a hard
	HA CONDITION: good	
	COMMENTS:	State State
THE STREET		
2000	FRIABLE YES _ L_ NO           CAT I: CAT II: RACM:	
197	CAT I: CAT II:	
and the Second		
CALCELED THE	In a statement of a second sec	States and
		A State of the
	PHOTO 66 – 5/12/15 – SAMPLE 20.3 – HA 20	
	CLASS 5 COATING	
	RAILINGS	

AMPLE PROJECT NO. 15931 FDOT 1 CLIENT: PROJECT LOCATION: Sarasota, fu BUILDING NAME: SA 780 Our Car KANCAR ROOM NO. 170951 50 DATE: 5-13.15 21-4 RA INSPECTOR: Greger 11.3 HA DESCRIPTION: Silvages Pla HA NO. 21-1 HA CONDITION: Goo COMMENTS: FRIABLE -CAT CATI PHOTO 67 - 5/13/15 - SAMPLE 21.1 - HA 21 FIBERGLASS

**PILE JACKETS** OUNI SAMPLE PROJECT NO. 15431 PROJECT LOCATION: Selasta CLIENT: BUILDING NAME: SE 280 ROOM NO. DATE: NSPECTOR: 1910 ralass NO. AV TION PHOTO 68 - 5/13/15 - SAMPLE 21.2 - HA 21 FIBERGLASS

-	ACM SAMPLE	Carlo Carlo
	PROJECT NO. 154 316	
	CLIENT: FDOT 1	1 Million
	PROJECT LOCATION: Sarasta, fr	
	BUILDING NAME: SA 780 Our Com KAY CAUGANY	1 Martin L
	ROOM NO. 170951 68	CANES TO THE TAX
	DATE: 5-13-15	
	INSPECTOR: Grego(-)	
	HA NO. 241 21-3 21-9 44	De la
	HA NO. THE HALL HE HAS	A A A
	HA CONDITION: COOP	55.
	COMMENTS:	
	VES A NO	The Y
	FRIABLE RACM	and the second se
	COMMENTS:YESNO FRIABLEYESNO CAT I: CAT II: RACM:	
		1 3 100
	and A	1
	and an and a second sec	To a la l
	History and provident	A

PHOTO 69 – 5/13/15 – SAMPLE 21.3 – HA 21 FIBERGLASS PILE JACKETS

	F IL	L JACKE 13	
À	124314		
	PROJECT NO. ISA 314 CLIENT: FDOT 1 PROJECT LOCATION: Second BUILDING NAME: SA 780 C ROOM NO. 170951 56 DATE: S-13.15 INSPECTOR: Great HA NO. 141 142 HA DESCRIPTION: FILLING HA CONDITION: GOOD COMMENTS: YES A FRIABLE YES A CAT I: YES A	ZH3 21-4 QA	

PHOTO 70 – 5/13/15 – SAMPLE 21.4 QA/QC – HA 22 FIBERGLASS PILE JACKETS

1952 NUM SAMPLE PROJECT NO. 15436 PROJECT LOCATION: SAVASON Coon they writering CLIENT: BUILDING NAME: 100951 ROOM NO. SE TRO OVER DATE: 5.13.15 HA DESCRIPTION: Plastic Coulting INSPECTOR: Creey HA NO. 12-1 HA CONDITION: 09 NO COMMENTS:\_ RACM K YES FRIABLE ---CATI CATI PHOTO 71 - 5/13/15 - SAMPLE 22.1 - HA 22 SEALANT (IN THE SPACE BETWEEN PILE AND PILE JACKET) **PILE JACKETS** - ACM SAMPLE PROJECT NO. 15436 FDOT 1 CLIENT: PROJECT LOCATION: Sarason, fr BUILDING NAME: 1 10951 E ROOM NO. SE TRO DIEL COON LEY WITHIN DATE: 5.13.15 INSPECTOR: Green 27.7 HA DESCRIPTION: Plastic Coultri HA NO. 2261 HA CONDITION:\_ COMMENTS: VES FRIABLE -

PHOTO 72 – 5/13/15 – SAMPLE 22.2 – HA 22 SEALANT (IN THE SPACE BETWEEN PILE AND PILE JACKET) PILE JACKETS

CATI

CALCULATION OF THE OWNER OWNER OF THE OWNER OWNE	
116.00	
ACM SAMPLE	
- HOM SAMPLE	
ROJECT NO. 15436	
CLIENT: FDOT 1	
PROJECT LOCATION: Salasota, FL	
BUILDING NAME: 10 10951 ES	
ROOM NO. SE TRO OVER COON LEY WITCHWY	Die Contraction of the second second
ROOM NO. JC IN	
DATE:	1 1 1 Walter Carlos Aller
DATE Creeking 22	1 SALARDER ST
INSPECTOR: Greening 21.2 22	
10 22 alertic Campy	
DATE: INSPECTOR: <u>Greese</u> HA NO HA DESCRIPTION: <u>Plastic Coulting</u> HA DESCRIPTION: <u>Plastic</u>	
DESCRIPTION	
HADE	
HA CONDITION: 0000 HA CONDITION: 0000	
CONDITION	
HAUTS	
OMMENTO:	
HA CONDUCTOR	Man 1984
/ / /	
ABLE CATIL	
FRIME	
TI	
CA	
	CARACTER AND
007013	120 - 120 - 1 - 1 - 1 - 1 - 1 - 1 - 1 - 1 - 1 -
and the second se	
a field formation	A start second was

PHOTO 73 – 5/13/15 – SAMPLE 22.3 – HA 22 SEALANT (IN THE SPACE BETWEEN PILE AND PILE JACKET) PILE JACKETS

#### **SECTION 4**

#### LABORATORY ANALYTICAL DATA AND CHAIN OF CUSTODY FORM(S)



EMSL Order: 341504827 CustomerID: SHAW77C CustomerPO: ProjectID:

Attn:	Shawn Flynn Shaw/CB&I 1228 Winter Garden Vineland Rd Winter Garden, FL 34787	Phone: Fax: Received: Analysis Date: Collected:	(407) 287-3200 05/18/15 11:00 AM 5/23/2015 5/15/2015

Project: 1543161 Bridge 170951

#### Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

			Non-A	<u>sbestos</u>	<u>Asbestos</u>
Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Type
1-1	Support Piles -	Gray/White		55% Quartz	None Detected
341504827-0001	Concrete	Non-Fibrous		10% Ca Carbonate	
		Heterogeneous		35% Non-fibrous (other)	
1-2	Support Piles -	Gray/White		55% Quartz	None Detected
341504827-0002	Concrete	Non-Fibrous		10% Ca Carbonate	
		Heterogeneous		35% Non-fibrous (other)	
1-3	Support Piles -	Gray/W hite		35% Quartz	None Detected
341504827-0003	Concrete	Non-Fibrous		15% Ca Carbonate	
		Heterogeneous		50% Non-fibrous (other)	
2-1	Bent Caps -	Gray/W hite		55% Quartz	None Detected
341504827-0004	Concrete	Non-Fibrous		10% Ca Carbonate	
		Heterogeneous		35% Non-fibrous (other)	
2-2	Bent Caps -	Gray/White		50% Quartz	None Detected
341504827-0005	Concrete	Non-Fibrous		10% Ca Carbonate	
341304627-0003		Heterogeneous		40% Non-fibrous (other)	
2-3	Bent Caps -	Gray/W hite		35% Quartz	None Detected
	Concrete	Non-Fibrous		15% Ca Carbonate	
341504827-0006		Heterogeneous		50% Non-fibrous (other)	

Analyst(s)

Lindsay Karashay (22) Manolo Hernandez (44)

Jonathan Teda, Asbestos Lab Manager or other approved signatory

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. Reporting limit is 1% Samples analyzed by EMSL Analytical, Inc. Orlando, FL NVLAP Lab Code 101151-0



EMSL Order: 341504827 CustomerID: SHAW77C CustomerPO: ProjectID:

			-	
Attn:	Shawn Flynn	Phone:	(407) 287-3200	
	Shaw/CB&I	Fax:		
	1228 Winter Garden Vineland Rd	Received:	05/18/15 11:00 AM	
		Analysis Date:	5/23/2015	
	Winter Garden, FL 34787	Collected:	5/15/2015	

Project: 1543161 Bridge 170951

#### Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

			Non-As	<u>Asbestos</u> % Type	
Sample	Description	Appearance	% Fibrous % Non-Fibrous		
3-1	Sea Wall -	Gray/W hite		45% Quartz	None Detected
341504827-0007	Concrete	Non-Fibrous		10% Ca Carbonate	
		Heterogeneous		45% Non-fibrous (other)	
3-2	Sea Wall -	Gray/White		45% Quartz	None Detected
341504827-0008	Concrete	Non-Fibrous		10% Ca Carbonate	
		Heterogeneous		45% Non-fibrous (other)	
3-3	Sea Wall -	Gray/White		50% Quartz	None Detected
341504827-0009	Concrete	Non-Fibrous		10% Ca Carbonate	
		Heterogeneous		40% Non-fibrous (other)	
4-1	Abutment Wall - Concrete	Gray/White	3% Cellulose	35% Quartz	None Detected
341504827-0010		Non-Fibrous		10% Ca Carbonate	
		Heterogeneous		52% Non-fibrous (other)	
4-2	Abutment Wall -	Gray		45% Quartz	None Detected
341504827-0011	Concrete	Non-Fibrous		10% Ca Carbonate	
		Heterogeneous		45% Non-fibrous (other)	
4-3	Abutment Wall -	Gray/White		50% Quartz	None Detected
341504827-0012	Concrete	Non-Fibrous		10% Ca Carbonate	
		Heterogeneous		40% Non-fibrous (other)	
5-1	Abutment Wall -	Gray/White	3% Cellulose	45% Quartz	None Detected
341504827-0013	Concrete	Fibrous		10% Ca Carbonate	
		Heterogeneous		42% Non-fibrous (other)	

Analyst(s)

Lindsay Karashay (22) Manolo Hernandez (44)

Jonathan Teda, Asbestos Lab Manager or other approved signatory

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. Reporting limit is 1% Samples analyzed by EMSL Analytical, Inc. Orlando, FL NVLAP Lab Code 101151-0



EMSL Order: 341504827 CustomerID: SHAW77C CustomerPO: PreioetID:

CustomerPO:
ProjectID:

Attn:	Shawn Flynn	Phone:	(407) 287-3200
	Shaw/CB&I	Fax:	
	1228 Winter Garden Vineland Rd	Received:	05/18/15 11:00 AM
		Analysis Date:	5/23/2015
	Winter Garden, FL 34787	Collected:	5/15/2015
Projec	et: 1543161 Bridge 170951		

#### Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

			Non-Ast	<u>bestos</u>	<u>Asbestos</u>
ample	Description	Appearance	% Fibrous	% Non-Fibrous	% Type
5-2	Abutment Wall -	Gray	2% Cellulose	60% Quartz	None Detected
341504827-0014	Concrete	Non-Fibrous		10% Ca Carbonate	
		Heterogeneous		28% Non-fibrous (other)	
5-3	Abutment Wall -	Gray/Tan/White		50% Quartz	None Detected
341504827-0015	Concrete	Non-Fibrous		10% Ca Carbonate	
		Heterogeneous		40% Non-fibrous (other)	
6-1	End Bent -	Gray/White		50% Quartz	None Detected
341504827-0016	Concrete	Non-Fibrous		10% Ca Carbonate	
		Heterogeneous		40% Non-fibrous (other)	
6-2	End Bent -	Gray/White		50% Quartz	None Detected
341504827-0017	Concrete	Non-Fibrous		10% Ca Carbonate	
		Heterogeneous		40% Non-fibrous (other)	
6-3	End Bent -	Gray/White		45% Quartz	None Detected
341504827-0018	Concrete	Non-Fibrous		15% Ca Carbonate	
		Heterogeneous		40% Non-fibrous (other)	
7-1	Diaphram -	Gray/White		55% Quartz	None Detected
341504827-0019	Concrete	Non-Fibrous		10% Ca Carbonate	
		Heterogeneous		35% Non-fibrous (other)	
7-2	Diaphram -	Gray/White		55% Quartz	None Detected
341504827-0020	Concrete	Non-Fibrous		10% Ca Carbonate	
		Heterogeneous		35% Non-fibrous (other)	

Analyst(s)

Lindsay Karashay (22) Manolo Hernandez (44)

Jonathan Teda, Asbestos Lab Manager or other approved signatory

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. Reporting limit is 1% Samples analyzed by EMSL Analytical, Inc. Orlando, FL NVLAP Lab Code 101151-0



EMSL Order: CustomerID: CustomerPO: ProjectID:

341504827 SHAW77C

Attn:	Shawn Flynn Shaw/CB&I 1228 Winter Garden Vineland Rd Winter Garden, FL 34787	Phone: Fax: Received: Analysis Date: Collected:	(407) 287-3200 05/18/15 11:00 AM 5/23/2015 5/15/2015
-------	---	---	---

Project: 1543161 Bridge 170951

#### Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using **Polarized Light Microscopy**

				Non-Ast	<u>bestos</u>	<u>Asbestos</u>
ample	Description	Appearance	% Fib	orous	% Non-Fibrous	% Type
7-3	Diaphram -	Gray/White			55% Quartz	None Detected
341504827-0021	Concrete	Non-Fibrous			15% Ca Carbonate	
		Heterogeneous			30% Non-fibrous (other)	
8-1	Bearing Pads-	Gray/Black	35% C	ellulose	65% Non-fibrous (other)	None Detected
341504827-0022	Subgrader - Asphalt Paper	Fibrous Homogeneous				
8-2	Bearing Pads-	Gray/Black	35% C	ellulose	65% Non-fibrous (other)	None Detected
341504827-0023	Subgrader - Asphalt Paper	Fibrous Homogeneous				
8-3	Bearing Pads-	Red/Black			100% Non-fibrous (other)	None Detected
341504827-0024	Subgrader - Asphalt Paper	Non-Fibrous Heterogeneous				
			Inseparable pa	aint / coating layer	included in analysis	
9-1	Gliders - Concrete	Gray/White			55% Quartz	None Detected
341504827-0025		Non-Fibrous			10% Ca Carbonate	
		Heterogeneous			35% Non-fibrous (other)	
9-2	Gliders - Concrete	Gray/W hite			55% Quartz	None Detected
341504827-0026		Non-Fibrous			10% Ca Carbonate	
· ······		Heterogeneous			35% Non-fibrous (other)	
9-3	Gliders - Concrete	Gray/White			35% Quartz	None Detected
341504827-0027		Non-Fibrous			20% Ca Carbonate	
		Heterogeneous			45% Non-fibrous (other)	

Analyst(s)

Lindsay Karashay (22) Manolo Hernandez (44)

Jonathan Teda, Asbestos Lab Manager or other approved signatory

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. Reporting limit is 1% Samples analyzed by EMSL Analytical, Inc. Orlando, FL NVLAP Lab Code 101151-0



Attn:

EMSL Analytical, Inc. 5125 Adanson Street, Suite 900, Orlando, FL 32804 Phone/Fax: (407) 599-5887 / (407) 599-9063 http://www.EMSL.com orlandolab@emsl.com EMSL Order: 341504827 CustomerID: SHAW77C CustomerPO: ProjectID:

Shawn Flynn	Phone:	(407) 287-3200
Shaw/CB&I	Fax:	
1228 Winter Garden Vineland Rd	Received:	05/18/15 11:00 AM
	Analysis Date:	5/23/2015
Winter Garden, FL 34787	Collected:	5/15/2015

Project: 1543161 Bridge 170951

#### Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

			Non-A	sbestos	<u>Asbestos</u>
Sample	Description	Appearance	% Fibrous % Non-Fibrous		% Type
10-1	Gliders - Mortar	Gray		60% Quartz	None Detected
341504827-0028		Non-Fibrous		5% Ca Carbonate	
		Heterogeneous		35% Non-fibrous (other)	
10-2	Gliders - Mortar	Gray		60% Quartz	None Detected
341504827-0029		Non-Fibrous		5% Ca Carbonate	
		Heterogeneous		35% Non-fibrous (other)	
10-3	Gliders - Mortar	Gray		50% Quartz	None Detected
341504827-0030		Non-Fibrous		5% Ca Carbonate	
		Homogeneous		45% Non-fibrous (other)	
11-1	Bearing Pads-	White/Black	45% Cellulose	55% Non-fibrous (other)	None Detected
341504827-0031 Subdeck - Asphal Paper		Fibrous Homogeneous			
11-2	Bearing Pads-	White/Black	45% Cellulose	55% Non-fibrous (other)	None Detected
341504827-0032	Subdeck - Asphalt Paper	Fibrous Homogeneous			
11-3	Bearing Pads-	Brown/Black	45% Cellulose	55% Non-fibrous (other)	None Detected
341504827-0033	Subdeck - Asphalt Paper	Fibrous Homogeneous			
12-1	Expansion Joint -	Gray/Black		100% Non-fibrous (other)	None Detected
341504827-0034	Black Rubber	Non-Fibrous Homogeneous			
12-2	Expansion Joint -	Black		100% Non-fibrous (other)	None Detected
341504827-0035	Black Rubber	Non-Fibrous Homogeneous			

Analyst(s)

Lindsay Karashay (22) Manolo Hernandez (44)

Jonathan Teda, Asbestos Lab Manager or other approved signatory

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. Reporting limit is 1% Samples analyzed by EMSL Analytical, Inc. Orlando, FL NVLAP Lab Code 101151-0



EMSL Order: 341504827 CustomerID: SHAW77C CustomerPO: ProjectID:

Project: 1543161 Bridge 170951

#### Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

			Non-Asl	<u>Asbestos</u>	
Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Туре
12-3	Expansion Joint -	Gray	2% Cellulose	2% Quartz	None Detected
341504827-0036	Black Rubber	Fibrous Heterogeneous		96% Non-fibrous (other)	
			Result includes a small amount	of inseparable attached material	
13-1	Railing-Nail -	Gray/White		50% Quartz	None Detected
341504827-0037	Concrete	Non-Fibrous		10% Ca Carbonate	
		Heterogeneous		40% Non-fibrous (other)	
13-2	Railing-Nail -	Gray/White		50% Quartz	None Detected
341504827-0038	Concrete	Non-Fibrous		10% Ca Carbonate	
		Heterogeneous		40% Non-fibrous (other)	
13-3	Railing-Nail -	Gray/W hite		50% Quartz	None Detected
341504827-0039	Concrete	Non-Fibrous		15% Ca Carbonate	
		Heterogeneous		35% Non-fibrous (other)	
14-1	End Cap -	Gray/Tan/White		55% Quartz	None Detected
341504827-0040	Concrete	Non-Fibrous		10% Ca Carbonate	
		Heterogeneous		35% Non-fibrous (other)	
14-2	End Cap -	Gray/Tan/White		55% Quartz	None Detected
341504827-0041	Concrete	Non-Fibrous		10% Ca Carbonate	
		Heterogeneous		35% Non-fibrous (other)	
14-3	End Cap -	Gray/White		45% Quartz	None Detected
341504827-0042	Concrete	Non-Fibrous		15% Ca Carbonate	
		Heterogeneous		40% Non-fibrous (other)	

Analyst(s)

Lindsay Karashay (22) Manolo Hernandez (44)

1

Jonathan Teda, Asbestos Lab Manager or other approved signatory

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. Reporting limit is 1% Samples analyzed by EMSL Analytical, Inc. Orlando, FL NVLAP Lab Code 101151-0



At

EMSL Analytical, Inc. 5125 Adanson Street, Suite 900, Orlando, FL 32804 Phone/Fax: (407) 599-5887 / (407) 599-9063 http://www.EMSL.com orlandolab@emsl.com EMSL Order: 341504827 CustomerID: SHAW77C CustomerPO: ProjectID:

tn:	Shawn Flynn	Phone:	(407) 287-3200
	Shaw/CB&I	Fax:	
	1228 Winter Garden Vineland Rd	Received:	05/18/15 11:00 AM
		Analysis Date:	5/23/2015
	Winter Garden, FL 34787	Collected:	5/15/2015

Project: 1543161 Bridge 170951

#### Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

			Non-A	<u>sbestos</u>	<u>Asbestos</u>
Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Type
15-1	Curb - Concrete	Gray/W hite		50% Quartz	None Detected
341504827-0043		Non-Fibrous		10% Ca Carbonate	
		Heterogeneous		40% Non-fibrous (other)	
15-2	Curb - Concrete	Gray/White		50% Quartz	None Detected
341504827-0044		Non-Fibrous		10% Ca Carbonate	
		Heterogeneous		40% Non-fibrous (other)	
15-3	Curb - Concrete	Gray/Tan/White		45% Quartz	None Detected
341504827-0045		Non-Fibrous		15% Ca Carbonate	
		Heterogeneous		40% Non-fibrous (other)	
16-1	Deck - Concrete	Gray/White		50% Quartz	None Detected
341504827-0046		Non-Fibrous		10% Ca Carbonate	
		Heterogeneous		40% Non-fibrous (other)	
16-2	Deck - Concrete	Gray/White		45% Quartz	None Detected
341504827-0047		Non-Fibrous		10% Ca Carbonate	
		Heterogeneous		45% Non-fibrous (other)	
16-3	Deck - Concrete	Gray/White		45% Quartz	None Detected
341504827-0048		Non-Fibrous		15% Ca Carbonate	
		Heterogeneous		40% Non-fibrous (other)	
17-1	Railing-Post -	Gray/Tan		55% Quartz	None Detected
341504827-0049	Concrete	Non-Fibrous		10% Ca Carbonate	
		Heterogeneous		35% Non-fibrous (other)	

Analyst(s)

Lindsay Karashay (22) Manolo Hernandez (44)

Jonathan Teda, Asbestos Lab Manager or other approved signatory

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. Reporting limit is 1% Samples analyzed by EMSL Analytical, Inc. Orlando, FL NVLAP Lab Code 101151-0



Project: 1543161 Bridge 170951

EMSL Analytical, Inc. 5125 Adanson Street, Suite 900, Orlando, FL 32804 Phone/Fax: (407) 599-5887 / (407) 599-9063 http://www.EMSL.com orlandolab@emsl.com EMSL Order: 341504827 CustomerID: SHAW77C CustomerPO: ProjectID:

Attn:	Shawn Flynn Shaw/CB&I	Phone: Fax:	(407) 287-3200
	1228 Winter Garden Vineland Rd Winter Garden, FL 34787	Received: Analysis Date:	05/18/15 11:00 AM 5/23/2015
		Collected:	5/15/2015

#### Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

			<u>Non-A</u>	sbestos	<u>Asbestos</u>
Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Type
17-2	Railing-Post -	Gray/Tan		55% Quartz	None Detected
341504827-0050	Concrete	Non-Fibrous		10% Ca Carbonate	
		Heterogeneous		35% Non-fibrous (other)	
17-3	Railing-Post -	Gray/White		45% Quartz	None Detected
341504827-0051	Concrete	Non-Fibrous		15% Ca Carbonate	
		Heterogeneous		40% Non-fibrous (other)	
18-1	Deck - Mortar	Gray		55% Quartz	None Detected
341504827-0052		Non-Fibrous		10% Ca Carbonate	
		Heterogeneous		35% Non-fibrous (other)	
18-2	Deck - Mortar	Gray/White		55% Quartz	None Detected
341504827-0053		Non-Fibrous		10% Ca Carbonate	
		Heterogeneous		35% Non-fibrous (other)	
18-3	Deck - Mortar	Gray		55% Quartz	None Detected
341504827-0054		Non-Fibrous		10% Ca Carbonate	
		Heterogeneous		35% Non-fibrous (other)	
19-1	Reflector - Black	Black		100% Non-fibrous (other)	None Detected
341504827-0055	Adhesive Mastic	Fibrous Homogeneous			
19-2	Reflector - Black	Black		100% Non-fibrous (other)	None Detected
341504827-0056	Adhesive Mastic	Fibrous Homogeneous			

Analyst(s)

Lindsay Karashay (22) Manolo Hernandez (44)

Jonathan Teda, Asbestos Lab Manager or other approved signatory

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. Reporting limit is 1% Samples analyzed by EMSL Analytical, Inc. Orlando, FL NVLAP Lab Code 101151-0



Project: 1543161 Bridge 170951

EMSL Analytical, Inc. 5125 Adanson Street, Suite 900, Orlando, FL 32804 Phone/Fax: (407) 599-5887 / (407) 599-9063 http://www.EMSL.com orlandolab@emsl.com EMSL Order: 341504827 CustomerID: SHAW77C CustomerPO: ProjectID:

Attn:	Shawn Flynn	Phone:	(407) 287-3200
	Shaw/CB&I 1228 Winter Garden Vineland Rd	Fax:	
		Received:	05/18/15 11:00 AM
		Analysis Date:	5/23/2015
	Winter Garden, FL 34787	Collected:	5/15/2015

#### Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

				<u>Non-Asl</u>	<u>bestos</u>	<u>Asbestos</u>
Sample	Description	Appearance	%	Fibrous	% Non-Fibrous	% Type
19-3	Reflector - Black	Black			100% Non-fibrous (other)	None Detected
341504827-0057	Adhesive Mastic	Non-Fibrous Homogeneous				
20-1	Class 5 Coating -	Gray	<1%	Cellulose	60% Quartz	None Detected
341504827-0058	Black 5 Coating	Non-Fibrous			10% Ca Carbonate	
		Heterogeneous			30% Non-fibrous (other)	
20-2	Class 5 Coating -	Gray	<1%	Cellulose	60% Quartz	None Detected
341504827-0059	Class 5 Coating	Non-Fibrous			10% Ca Carbonate	
		Heterogeneous			30% Non-fibrous (other)	
20-3	Class 5 Coating -	Gray			50% Quartz	None Detected
341504827-0060	Class 5 Coating	Non-Fibrous			10% Ca Carbonate	
		Heterogeneous			40% Non-fibrous (other)	
21-1	Support Pile	White	20%	Glass	80% Non-fibrous (other)	None Detected
341504827-0061	Protective Casing - Fiberglass	Fibrous Heterogeneous				
21-2	Support Pile	White	20%	Glass	80% Non-fibrous (other)	None Detected
341504827-0062	Protective Casing - Fiberglass	Fibrous Heterogeneous				
21-3	Support Pile	Gray/Tan/White	20%	Glass	80% Non-fibrous (other)	None Detected
341504827-0063	Protective Casing - Fiberglass	Fibrous Heterogeneous				
			Inseparabl	e paint / coating layer	included in analysis	

Analyst(s)

Lindsay Karashay (22) Manolo Hernandez (44)

Jonathan Teda, Asbestos Lab Manager or other approved signatory

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. Reporting limit is 1% Samples analyzed by EMSL Analytical, Inc. Orlando, FL NVLAP Lab Code 101151-0



EMSL Order: 341504827 CustomerID: SHAW77C CustomerPO: ProjectID:

Attn:         Shawn Flynn         Phone:         (407) 287-3200           Shaw/CB&I         Fax:         Fax:         Fax:           1228 Winter Garden Vineland Rd         Received:         05/18/15 11:00 AM           Winter Garden, FL 34787         Collected:         5/23/2015	
--	--

Project: 1543161 Bridge 170951

#### Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

			Non-As	sbestos	Asbestos
Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Type
22-1	Support Pile	Gray/White		35% Quartz	None Detected
341504827-0064	Protective Casing - Sealant	Non-Fibrous		10% Ca Carbonate	
	Sealant	Heterogeneous		55% Non-fibrous (other)	
22-2	Support Pile Protective Casing -	Gray/W hite		20% Quartz	None Detected
341504827-0065				5% Ca Carbonate	
	Sealant	Heterogeneous		75% Non-fibrous (other)	
22-3	Support Pile	Gray/White	<1% Cellulose	30% Quartz	None Detected
341504827-0066	Protective Casing -	Non-Fibrous	<1% Glass	5% Ca Carbonate	
	Sealant	Heterogeneous		65% Non-fibrous (other)	

Analyst(s)

Lindsay Karashay (22) Manolo Hernandez (44)

Jonathan Teda, Asbestos Lab Manager or other approved signatory

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. Reporting limit is 1% Samples analyzed by EMSL Analytical, Inc. Orlando, FL NVLAP Lab Code 101151-0

Asbestos Bulk I EMEL Chain of EMSL Order Nu			n of (	Custody		EMSL ANALYTICAL, INC. 200 ROUTE 130 NORTH CINNAMINSON, NJ 08077	
	ISL ANALYTICAL INC. 34150				nly)	Рноле. (800) 220-3675 Fax: (856) 786-5974	
Company :	CBS	-1				Same Different	
Street: 12	128 h	inter Garden Vincland Rd		Third Party	Billing requires writt	en authorization from third party	
	Jinter			Zip/Postal Code	<u>י: 3אוגי</u>	Country: UKA-	
Report To	(Name):	Shawn FLYNN		Telephone #:	4.7-287-300	0	
Email Add	ress: 2	have flys @ this con ber: 154316/ Bridge MOA		Fax #: 467 -		Purchase Order:	
Project Na U.S. State	me/Num	ber: 1543/6/Bridge 1709	51	Please Provide		c ☐ Email able ☐ Residential/Tax Exempt	
	Samples		ne (TA	T) Options* – Plea			
3 Hour		6 Hour 24 Hour 48	Hour	72 Hour	96 Hour	1 Week 2 Week	
		gh 6 hr, please call ahead to schedule.*There form for this service Analysis completed in					
		I - Bulk (reporting limit)			<u>TEM –</u>		
		93/116 (<1%)				116 Section 2.5.5.1	
	and the summer of the	<1%) (<0 25%) 🔲 1000 (<0 1%)		NY ELAP Metho Chatfield Protoc			
		(<0 23 %) ☐ 1000 (<0 1 %) metric ☐ 400 (<0.25%) ☐ 1000 (<0 1			• •	(116 Section 2.5.5.2	
		and a second		] TEM Qualitative	10 - Contra and a contra contra the transmission of the contra cont		
		d 198.1 (fnable in NY)		TEM Qualitative via Drop Mount Prep Technique			
		d 198.6 NOB (non-friable-NY)		Other			
OSHA (		· · · · · · · · · · · · · · · · · · ·		ב			
				·	·		
Check I	or Posi	ive Stop – Clearly Identify Homoger	nous G	roup   Date Sam	ipled:		
Samplers I	Name:			Samplers Sig	inature:	······	
Sample #	HA #	Sample Locati	on	<u> </u>	M	aterial Description	
1-1		Support piles			Concrete		
1-2							
1.3	1	support piles			concrete		
2.1	2	Bent caps			Convete		
2-2	2	Bent Caps			Concerta	<u> </u>	
2-3	2	Bentcaps			concrete		
3-1	3	Sea wall			concrete	,	
3-2	3	Sea wall		;	convete	, 	
3-3	3	See wall			concrete		
4.)	4	abutment wall			convete		
				2.3	Total # o	f Samples: 66	
Relinquish	ed (Clie		Date:	يكنه المغنية بكريت	×	Time: 1100	
	Received (Lab):			5-18-15		Time: //am	
Comments	/Special	Instructions:					
·	_						



#### Asbestos Bulk Building Material Chain of Custody

EMSL ANALYTICAL, INC. 200 ROUTE 130 NORTH CINNAMINSON, NJ 08077

EMSL Order Number (Lab Use Only):

341504827

PHONE. (800) 220-3675 FAX. (856) 786-5974

Additional Pages of the Chain of Custody are only necessary if needed for additional sample information

Sample #	HA #	Sample Location	Material Description
4.2	ч	abutment wall	Constete
4.3	4	abritment wall	Conerete
5-1	5	abutment ball	malte
5.2	5	abritment wall	mater
5.3	5	abutment wall	morter
6.1	6	and bent	concet
6.2	6	End bent	conservete
6.3	6	Cnd bent	Contrit
7.1	7	Diophram	concrete
7.2	ר	Diosphram	converte
7-3	<u>ר</u>	Diaptam	Concrete
8-1	8	Bearing pado- Subarder	asphalt paper
8.2	8	Bearing pado-Subgrider Bearing pado-Subgrider	asplalt poper
8.3	٢	Bearing puds og subgridee	agglalt piper
9.1	9	guirders	Brooks concrete
9.2	9	avider	concreti
9.3	9		concrete
10.1	10	griders griders griders	morter
10,2	10	onritors	morter
(0.3	Ю	airders	moter
11.1	11	Bealing pads subdeck	apphalt paper
11.2	11	Bearing pads-subdice	asphalt papper
11.3	11	Bearing pedy Subplit	ashpattion paper
12.1	12	Crowsion joints	black nutter
*Commer	nts/Spec	ial Instructions: V	



### Asbestos Bulk Building Material Chain of Custody

EMSL Order Number (Lab Use Only):

EMSL ANALYTICAL, INC 200 ROUTE 130 NORTH CINNAMINSON, NJ 08077 PHONE (800) 220-3675 FAX: (856) 786-5974

341504827

Additional Pages of the Chain of Custody are only necessary if needed for additional sample information

Sample #	HA #	Sample Location	Material Description
p.2	n	Expansion joint	black public
2.3	n	Expansion joint Expansion print Railing rall	black subber
13-1	13	Railing gall	concrete
13.2	13	Railing - Mail	Concrete
13.3	13	initine sail	concrete
14.1	<u> </u>	End Eus	concrete
14.2	14	End cap	concréte
14,2	(4	Endcap	concrite
15.1	15	Custo	concrete
15.2	15	Cult-	concrete
15,3	15	curt	Concrete
16.1	16_	Dock	concrete
16.2	16	Der Dock	concrete
16.3	16	Deck	concrete
17.1	17	Railing-post Railing-post Railing-post	concrete
17.2	17	Railing-post	concrete
17.3	17	Railing-post	concrete
18.1	18	Deck	moter
18.7	18	Deck	morter
18.3	18	Nech	monter
19.1	19	reflector	black adhesive mastic
19.2	19	reflector	le cle martie martie
19.3	19	reflector	Black adhesiir mastic
20.1	20	Class 5 coating	Black 5 coating
Comme	nts/Spec	ial Instructions:	0



#### Asbestos Bulk Building Material Chain of Custody

EMSL Order Number (Lab Use Only).

EMSL ANALYTICAL, INC. 200 ROUTE 130 NORTH CINNAMINSON, NJ 08077 PHONE: (800) 220-3675 FAX: (856) 786-5974

341504	1827

Additional Pages of the Chain of Custody are only necessary if needed for additional sample information

Sample #	HA #	Sample Location	Material Description
20.2	20	CLASS 5 coating	class 5 coatine
20.3	20	class 5 contine	Class 5 coattine
21.1	21	support sell protochive casing	uberglass
21.2	21	support pile protective casing	When alass
21.3	21	Support pile protective casing	Liberalagi
22.)	12	support piliprotectail casing	Sealent
22.2	22	Support sill protective casire	Sealant
223	22	support pile protection case	n sealant
			<i>)</i> ~
	ľ		
*Commen	ts/Specia	al Instructions:	

Page 4 of 4 pages

#### QUALITY ASSURANCE SAMPLING

QA/QC sampling was performed in accordance with the State of Florida Asbestos Survey Procedure Manual. Four QA/QC samples (sample No. 6.4 QA/QC, No. 12.4 QA/QC, No. 18.4 QA/QC, and No. 21.4 QA/QC) were collected next to sample No. 6.3 and No. 12.3, No. 18.3 and No. 21.3 respectively. Laboratory analyses indicated that these QA/QC samples did not contain asbestos.



# **CERTIFICATE OF ANALYSIS**

Client: Shaw Environmental Inc(CBI Co)

1228 Winter Garden Vineland Rd

Winter Garden FL 34787

<b>Report Date:</b>	5/23/2015
Report No.:	363771
Project:	Bridge 170951
Project No.:	154316

Frank E. Ehrenfeld, III

Laboratory Director

#### **BULK SAMPLE ANALYSIS SUMMARY**

Client No.:	5629281 6-4 QA/QC	Description / Location:	White/Grey Cementitious End Bent	
% Asbestos	Type	% Non-Asbestos Fibrou	s Material Type	<u>% Non-Fibrous Materi</u>
None Detected	None Detected	None Detected	None Detected	100
Lab No.:	5629282	Description / Location:	Grey Rubber	
Client No.:	12-4 QA/QC		Expansion Joint	
% Asbestos	Type	% Non-Asbestos Fibrou	<u>Material</u> <u>Type</u>	% Non-Fibrous Materi
None Detected	None Detected	None Detected	None Detected	100
Lab No.: Client No.:	5629283 18-4 QA/QC	Description / Location:		
<u>% Asbestos</u>	Type	<u>% Non-Asbestos Fibrou</u>		% Non-Fibrous Materi
None Detected	None Detected	None Detected	None Detected	100
Lab No.:	5629284	Description / Location:	Off-White Fibrous	
Client No.:	21-4 QA/QC		Support Pile Protective Casin	ıg
% Asbestos	Type	% Non-Asbestos Fibrous	<u>s Material</u> <u>Type</u>	% Non-Fibrous Materia
	None Detected	90	Fibrous Glass	10

Accreditatio	ons:		NVLAP N fidential report	relates only	v to those item		does not rep	presen		ement by NIS		P, AIHA					
Analytical N	Method:			US E	PA 600/R-9	-93/116 by Po	larized Lig	ght M	licroscopy	, (ELAP 19	98.1 who	ere appli	cable)		*******		
Comments:	quantifiab present or of the opti	le under the P the client has cal microscop	% by volume is p oint Counting re s specifically req pe. Therefore, P urrently the only	egimen. Ana uested that i LM is not c	alysis include it not be analy consistently re	les all distinct se lyzed (ex. analy reliable in detect	parable laye ze until posi ing asbestos	ers in a itive in s in no	accordance v istructions). n-friable org	vith EPA 60 Small asbes	0 Method stos fibers	l. If not r s may be:	eported or c missed by P	otherwise LM due	e noted, lay to resoluti	er is either n on limitation	
Analysis P	Perform	ed By:	D. Jao						Appro	ved By:		l	R	anf	Q		

Date: 5/23/2015

- - --



9000 Commerce Parkway, Suite B • Mount Laurel, NJ 08054 Phone: 877-428-4285/856-231-9449 • Fax: 856-231-9818

# Chain of Custody –Bulk Asbestos –

Contact Informa	ation							
<b>Client Company:</b>	CB&I	<b>Project Number:</b>	154316					
Office Address:	1228 Winter Garden Vineland Rd	Project Name:	Bridge 170951					
City, State, Zip:	Orlando, FL 34787	Primary Contact:	Shawn Flynn					
Fax Number:	407-287-3201	Office Phone:	407-287-3200					
Email Address:	shawn.flynn@cbi.com	Cell Phone:	407-832-3072					
PLM Instructions: PLM: Bulk Asbestos Building Materials EPA 600 R-93/116, 1993 PLM: Bulk Asbestos Building Materials EPA 600 M-4/82-020, 1982								
<ul> <li>PLM: Bulk Asbestos Building Materials NIOSH 9002, 1985</li> <li>PLM: Bulk Asbestos Building Materials NYSDOH-ELAP 198.1, 2002</li> <li>PLM: Bulk Asbestos Building Materials NYSDOH-ELAP 198.6, 2010</li> <li>TEM: Bulk Asbestos Building Materials NYSDOH-ELAP 198.4, 2009</li> </ul>								
PLM: Point Counting       PLM: Analyze Until Positive (Positive Stop)         PC: via ELAP 198.1       AUP: by Homogenous Area as Noted         PC: 400 Points       AUP: by Material Type as Noted         PC: 800 Points *       PLM: NOB via 198.6         PC: 1600 Points *       PLM: Friable via EPA 600 2.3         If <1% by PLM, to TEM via 198.4 *								
<ul> <li>□ PLM: Instructions for Multi-Layered Samples</li> <li>□ Analyze and Report All Separable Layers per EPA 600</li> <li>□ Report Composite for Drywall Systems per NESHAP</li> <li>□ Report All Layers and Composite Where Applicable</li> <li>□ Only Analyze and Report Specifically Noted Layer</li> <li>□ If &lt;1% by PLM, Hold for Instructions</li> <li< td=""></li<></ul>								
Special Instruction	ns:							
* Additional charge and turnaround may be required ** Alternative Method (ex: EPA 600/R-04/004) may be recommended by Laboratory								
Turnaround Tin	ne							
Preliminary Results Requested Date:								
		aan Dependent. Trease in						
Chain of Custody Relinquished (Name/Organization):       Junctical Structure								
Celebrating 25 yearsone sample at a time								
		iatl.com	1-2er 0-24					

- 1 -



9000 Commerce Parkway, Suite B • Mount Laurel, NJ 08054 Phone: 877-428-4285/856-231-9449 • Fax: 856-231-9818

# Sample Log -Bulk Asbestos -

Client: CB&I

Project: Bridge 170951; project # 154316

Sampling Date/Time: MAY 12-13, 2015

	Bul	k Asbestos Sample Log	
Client Sample #	iATL #	Location/Description	Notes
6-40A/QC 12-40A/QC 18-40A/QC 21-40A/QC	5629281		
12-40A/00	5629282	Expansion is nt-black rubber	
18.4 QA/QC	5629283	Deck-morter	
21.4 QA/QC	5629284	End bent-concrete Expansion joint-black rubbe Deck-morter Support pile protective casing	
· · · · ·			


iATL - 2 -Submit Form

#### **SECTION 5**

#### CREDENTIALS FOR CONSULTANT, INSPECTOR, AND LABORATORY

			Name	License		
License Ty	pe Name	lame Type		Number/ Rank	Status/Expire	
Asbestos Business	CB&I ENVIRONMENTAL INFRASTRUCTUR INC.		Primary	ZA317 Asbsts Business	Current 11/30/2015	
Address*:	License Location	9143 7460		GHWAY JACKSO	NVILLE, FL 32256-	
	Main Address*:	4171	ESSEN LAN	E BATON ROUG	E, LA 70809	
Asbestos Business	DAVID WARNER MOSHER	1	DBA	ZA317 Asbsts Business	Current 11/30/2015	
Address*:	License Location	9143 7460		GHWAY JACKSO	NVILLE, FL 32256-	
	Main Address*:	4171	ESSEN LAN	E BATON ROUG	E, LA 70809	







#### National Voluntary Laboratory Accreditation Program



#### SCOPE OF ACCREDITATION TO ISO/IEC 17025:2005

EMSL Analytical, Inc. 5125 Adanson Street, Suite 900 Orlando, FL 32804 Dr. Blanca Cortes Phone: 407-599-5887 Fax: 407-599-9063 E-Mail: bcortes@emsl.com URL: http://www.emsl.com

#### BULK ASBESTOS FIBER ANALYSIS (PLM)

#### NVLAP LAB CODE 101151-0

 NVLAP Code
 Designation / Description

 18/A01
 EPA 600/M4-82-020; Interim Method for the Determination of Asbestos in Bulk Insulation Samples

 18/A03
 EPA 600/R-93/116; Method for the Determination of Asbestos in Bulk Building Materials


2014-07-01 through 2015-06-30

Effective dates

Main R. Mal

For the National Institute of Standards and Technology NVLAP-01S (REV. 2005-05-19)

Page 1 of 1





-211

For the National Institute of Standards and Technology

NVLAP-01C (REV. 2009-01-28)

2014-07-01 through 2015-06-30

Effective dates

N:\Clients\FDOT FILES\FDOT 1 (BDV 75)\PROJECTS\154316 (LOA 47) - SE 789 (Little Ringling Bridge) asbestos survey\5.0 Reports\Bridge 170951\154316 - Br 170951\_AsbSurv, Paint Survey\_070815 FINAL.docx



#### National Voluntary Laboratory Accreditation Program



#### SCOPE OF ACCREDITATION TO ISO/IEC 17025:2005

International Asbestos Testing Laboratories 9000 Commerce Parkway Suite B Mt. Laurel, NJ 08054 Mr. Frank E. Ehrenfeld, III Phone: 856-231-9449 Fax: 856-231-9818 E-Mail: frankehrenfeld@iatl.com URL: http://www.iatl.com

#### BULK ASBESTOS FIBER ANALYSIS (PLM)

#### NVLAP LAB CODE 101165-0

- NVLAP Code Designation / Description
- 18/A01 EPA 600/M4-82-020: Interim Method for the Determination of Asbestos in Bulk Insulation Samples
   18/A03 EPA 600/R-93/116: Method for the Determination of Asbestos in Bulk Building Materials

2014-07-01 through 2015-06-30

Effective dates

Page 1 of 1

Mprin R. Mlal

For the National Institute of Standards and Technology NVLAP-01S (REV. 2005-05-19)

#### **SECTION 6**

#### ASBESTOS OPERATIONS AND MAINTENANCE (O&M) PLAN AND RESPONSE ACTION

#### O&M PLAN AND RESPONSE ACTION FOR BRIDGE 170951 (LITTLE RINGLING BRIDGE, EASTBOUND) SR 789 OVER THE COON KEY WATERWAY SARASOTA, SARASOTA COUNTY, FLORIDA DURING CONSTRUCTION ACTIVITIES

Any regulated asbestos-containing material (RACM) must be abated in accordance with 40 CFR, Subpart M, Part 61.145, as stated in abatement specifications required by Chapter 255, FS and OSHA Standard 1926.58 for the construction industry, prior to demolition or renovation. RACM is identified as follows:

- Friable ACM
- Category I nonfriable ACM that has become friable
- Category I nonfriable ACM that will be or has been subject to sanding, grinding, cutting, or abrading
- Category II nonfriable ACM that has a high probability of becoming, or has become, crumbled, pulverized, or reduced to powder by the forces expected to act on such material

No regulated asbestos-containing materials were found at Bridge 170951 located on SR 789 over the Coon Key Waterway within the materials tested. Renovation or demolition can proceed without any asbestos containment engineering controls, and no O&M or response actions are required. However, the use of wet demolition methods is recommended.

#### End of Work Plan

#### DISCLAIMER

The services described in this report were performed consistent with generally accepted professional consulting principles and practices. No other warranty, expressed or implied, is made. These services were performed consistent with our agreement with our client. This report is solely for the use and information of our client unless otherwise noted. Any reliance on this report by a third party is at such party's sole risk.

This report is the result of a limited investigation of the referenced bridge, and every attempt has been made to discover and inventory all asbestos-containing building materials (ACBM) in the structure. However, due to the limited and nondestructive nature of the inspection, it is possible that other concealed and inaccessible suspect materials may exist. Should any additional suspect ACMs be uncovered during renovation or demolition that are not listed in this report, then those materials should be sampled and submitted for analysis.

Opinions and recommendations contained in this report apply to conditions existing when services were performed and are intended only for the client, purposes, locations, time frames, and project parameters indicated. We are not responsible for the impacts of any changes in environmental standards, practices, or regulations subsequent to performance of services. We do not warrant the accuracy of information supplied by others, nor the use of segregated portions of this report.

#### **SECTION 8**

#### METALS-BASED PAINT SURVEY REPORT

 Facility Name:
 Bridge 170951 (Little Ringling Bridge, Eastbound)

 Along SR 789 over Coon Key Waterway

Address/Location: 1.4 miles west of US 41

City, County, State: Sarasota, Sarasota County, Florida

 Owner Agency:
 Florida Department of Transportation, District 1

Date of Survey: \_\_\_\_\_ May 13, 2015

Consultant: CB&I Environmental & Infrastructure, Inc.

Consultant Address: 1228 Winter Garden Vineland Road

City, State, Zip Code: \_\_\_\_\_\_\_ Winter Garden, Florida 34787

**Telephone Number:** 407-287-3210

July 9, 2015

Shawn D. Flynn, P.G. Contract Manager

#### METALS-BASED PAINT COATING SAMPLING REPORT

CB&I Environmental & Infrastructure, Inc., (CB&I) was retained by the Florida Department of Transportation (FDOT), District 1, to collect representative samples of the paint coating system from Bridge No. 170951, located on SR 789 over the Coon Key Waterway, in Sarasota, Sarasota County, Florida.

#### Introduction

CB&I collected one sample (<u>Pile Cover Composite</u>) of the paint coatings system from the bridge, in general accordance with the sampling procedures developed by the State Materials Office, Florida Method of Test for Sampling of Structural Steel Existing Coating Systems Designation 5-564. The sample was obtained by Thomas Gregory of CB&I on May 13, 2015, and was labeled, packaged, manifested, and transported to Xenco Laboratories in Tampa, Florida. The sample was collected from a white paint located on the fiberglass pile jackets (**Figure 1** in **Section 8**). Photographic documentation is provided in **Attachment A**, **Section 8**. The paint sample was a composite from four separate pile jackets along the bridge. This composite sample was laboratory analyzed for total heavy metals cadmium, chromium, lead, and the metal zinc by United States Environmental Protection Agency (EPA) Method 6010B and by the toxicity characteristic leaching procedure (TCLP) (EPA Method 6010C) for the same for metals. A copy of the laboratory analytical report is provided **Section 4**.

#### **Sample Results**

The following is a list of the paint samples collected for total metals analysis and the reported metals concentration.

		Sample ID: Pile Cover Composite
Metals	EPA Test Method	Concentration (mg/kg)
Cadmium	6010C	2.00
Chromium	6010C	54.7
Lead	6010C	51.1
Zinc	6010C	245 I

mg/kg – milligrams per kilogram

U - Compound was analyzed for but not detected at the MDL level

The composite sample above was also laboratory analyzed by the Toxicity Characteristic Leachate Procedure (TCLP) to determine whether the painted surfaces would exceed the Environmental Protection Agency (EPA) leachability limits established in 40 CFR 261.24. Exceedance of the limits established under 40 CFR 261.24 would (upon removal) classify the material as hazardous.

		Sample ID: Pile Cover Composite	Hazardous Waste Regulatory Level per CFR 261-24			
Metals	EPA Test Method	Concentration (mg/L)	(mg/L)			
Cadmium	6010C	0.0010 I	1			
Chromium	6010C	0.0080 IV	5			
Lead	6010C	1.0570	5			
Zinc	6010C	1.24	NS			

mg/L – milligrams per liter

I – Reported value is between the laboratory MDL and the laboratory PQL

*V* – Analyte was detected in both the sample and the associated method blank

NS – No Standard

#### **Recommendations for Personnel Health and Safety**

Due to the presence of metals in the paint coating identified on the pile jackets, the contractor selected to perform the renovation or demolition of the bridge should be familiar with and comply with all parts of the Occupational Safety and Health Administration (OSHA) Construction Standard contained in 29 CFR 1926.

Since sample analysis indicates that the paint coatings present on the tested components contain metals above detectable levels, there is potential for exposure to workers. Contractors should perform renovation or demolition activities in such a way as to continue to ensure that workers on the project are not exposed to levels above the OSHA permissible exposure limits in accordance with 29 CFR Subpart Z, and to ensure that any regulated metals are not spread to uncontrolled areas.

# Recommendations for Material/Waste Handling, Transportation, and Disposal


Based on the TCLP analytical results for the sampled areas, the paint waste generated from renovation or demolition of the metal span is not required to be handled as hazardous waste. However, any paint removed during construction will need to be re-analyzed as part of the waste profiling acceptance process prior to disposal.

During the removal and handling activities, the work area should be sufficiently protected from loose or falling paint chips and residue. All paint-related waste should be containerized in United States Department of Transportation (DOT) approved containers, labeled, and properly stored.

If blast media or chemicals are used during the paint removal operations, additional testing may be required. This could change the waste classification and disposal options.

In addition to the above requirements, all personnel who handle paint chips that have been removed from the metal span shall comply with all of the requirements in 40 CFR Parts 260 through 370. This includes, but is not limited to, waste handling, container labeling, transportation, and disposal.

#### FIGURE



#### ATTACHMENT A

#### PHOTOGRAPHIC LOG

N:\Clients\FDOT FILES\FDOT 1 (BDV 75)\PROJECTS\154316 (LOA 47) - SE 789 (Little Ringling Bridge) asbestos survey\5.0 Reports\Bridge 170951\154316 - Br 170951\_AsbSurv, Paint Survey\_070815 FINAL.docx Metals-Based Paint Sampling Report

#### BRIDGE 170951 METALS-BASED PAINT SURVEY PHOTO LOG




PHOTO 1 – 5/13/15 – VIEW OF PILE COVER COMPOSITE PAINT SAMPLE LOCATED ON PILE JACKETS OVER CONCRETE SUPPORT PILES



PHOTO 2 – 5/13/15 - VIEW OF SUPPORT PILES WITH PILE JACKETS

N:\Clients\FDOT FILES\FDOT 1 (BDV 75)\PROJECTS\154316 (LOA 47) - SE 789 (Little Ringling Bridge) asbestos survey\5.0 Reports\Bridge 170951\154316 - Br 170951\_AsbSurv, Paint Survey\_070815 FINAL.docx Metals-Based Paint Sampling Report

#### ATTACHMENT B

#### LABORATORY ANALYTICAL REPORT AND CHAIN OF CUSTODY RECORD

# Analytical Report 507972

for

# **Shaw Environmental**

Project Manager: Shawn Flynn

SR 780 Over Coon Key Causeway - Bridge 170951 Sarasota, FL

154316

18-JUN-15

**Collected By: Client** 





#### 6017 Financial Dr., Norcross, GA 30071 Ph:(770) 449-8800 Fax:(770) 449-5477

Xenco-Houston (EPA Lab code: TX00122): Texas (T104704215-14-18), Arizona (AZ0765), Florida (E871002), Louisiana (03054) Oklahoma (9218)

Xenco-Atlanta (EPA Lab Code: GA00046): Florida (E87429), North Carolina (483), South Carolina (98015), Kentucky (85), DoD ( L10-135) Texas (T104704477), Louisiana (04176), USDA (P330-07-00105)

> Xenco-Lakeland: Florida (E84098) Xenco-Odessa (EPA Lab code: TX00158): Texas (T104704400-TX) Xenco-Dallas (EPA Lab code: TX01468): Texas (T104704295-TX) Xenco Phoenix (EPA Lab Code: AZ00901): Arizona (AZ0757) Xenco-Phoenix Mobile (EPA Lab code: AZ00901): Arizona (AZM757) Xenco Tucson (EPA Lab code: AZ000989): Arizona (AZ0758)



# **Table of Contents**

Cover Page	1
Cover Letter	3
Sample ID Cross Reference	4
Case Narrative	5
Certificate of Analysis (Detailed Report)	6
Explanation of Qualifiers (Flags)	8
Summary of Quality control	9
Chain of Custody	11
Sample Receipt Conformance Report	13



18-JUN-15



Project Manager: **Shawn Flynn Shaw Environmental** 1228 Winter Garden Vineland Rd. Winter Garden, FL 34787

Reference: XENCO Report No(s): 507972 SR 780 Over Coon Key Causeway - Bridge 170951 Sarasota, FL Project Address: FL

#### Shawn Flynn:

We are reporting to you the results of the analyses performed on the samples received under the project name referenced above and identified with the XENCO Report Number(s) 507972. All results being reported under this Report Number apply to the samples analyzed and properly identified with a Laboratory ID number. Subcontracted analyses are identified in this report with either the NELAC certification number of the subcontract lab in the analyst ID field, or the complete subcontracted report attached to this report.

Unless otherwise noted in a Case Narrative, all data reported in this Analytical Report are in compliance with NELAC standards. The uncertainty of measurement associated with the results of analysis reported is available upon request. Should insufficient sample be provided to the laboratory to meet the method and NELAC Matrix Duplicate and Matrix Spike requirements, then the data will be analyzed, evaluated and reported using all other available quality control measures.

The validity and integrity of this report will remain intact as long as it is accompanied by this letter and reproduced in full, unless written approval is granted by XENCO Laboratories. This report will be filed for at least 5 years in our archives after which time it will be destroyed without further notice, unless otherwise arranged with you. The samples received, and described as recorded in Report No. 507972 will be filed for 60 days, and after that time they will be properly disposed without further notice, unless otherwise arranged with you. We reserve the right to return to you any unused samples, extracts or solutions related to them if we consider so necessary (e.g., samples identified as hazardous waste, sample sizes exceeding analytical standard practices, controlled substances under regulated protocols, etc).

We thank you for selecting XENCO Laboratories to serve your analytical needs. If you have any questions concerning this report, please feel free to contact us at any time.

Respectfully

Ruriko Konuma Project Manager Recipient of the Prestigious Small Business Administration Award of Excellence in 1994. Certified and approved by numerous States and Agencies. A Small Business and Minority Status Company that delivers SERVICE and QUALITY

Houston - Dallas - Odessa - San Antonio - Tampa - Lakeland - Atlanta - Phoenix - Oklahoma - Latin America



# Sample Cross Reference 507972



#### Shaw Environmental, Winter Garden, FL

SR 780 Over Coon Key Causeway - Bridge 170951 Sarasota, FL

Sample Id	Matrix	Date Collected	Sample Depth	Lab Sample Id
Pile Cover Composite	S	05-15-15 10:00		507972-001



### CASE NARRATIVE



Client Name: Shaw Environmental Project Name: SR 780 Over Coon Key Causeway - Bridge 170951 Sarasota, FL

 Project ID:
 154316

 Work Order Number(s):
 507972

Report Date:18-JUN-15Date Received:05/18/2015

Sample receipt non conformances and comments:

Sample receipt non conformances and comments per sample:

None



Lead

Zinc

## **Certificate of Analytical Results 507972**



1

1

Ι

#### Shaw Environmental, Winter Garden, FL

SR 780 Over Coon Key Causeway - Bridge 170951 Sarasota, FL

16.7

333

0.930

0.327

mg/kg

mg/kg

05.20.15 12.44

05.20.15 12.44

Sample Id:	Pile Cover Composit	e	Matrix:	Matrix: Paint Chips Date Received:05.18.15 09.52							
Lab Sample I	d: 507972-001		Date Colle	ected: 05.1	5.15 10.00						
Analytical M	ethod: Metals, Total by	SW846 6010C				]	Prep Method: SW	3050B			
Tech:	4099						% Moisture:				
Analyst:	4150		Date Prep	: 05.1	]	Basis: Wet Weight					
Seq Number:	968527										
Parameter		Cas Number	Result	PQL	MDL	Units	Analysis Date	Flag	Dil		
Cadmium		7440-43-9	2.00	1.67	0.0667	mg/kg	05.20.15 12.44		1		
Chromium		7440-47-3	54.7	16.7	0.200	mg/kg	05.20.15 12.44		1		

51.1

245

7439-92-1

7440-66-6



Lead

Zinc

## **Certificate of Analytical Results 507972**



1

1

#### Shaw Environmental, Winter Garden, FL

SR 780 Over Coon Key Causeway - Bridge 170951 Sarasota, FL

Sample Id:	Pile Cover Composit	e	Matrix:		nt Chips		Date Received:05.18.15 09.52			
Lab Sample I	d: 507972-001	Date Col	Date Collected: 05.15.15 10.00							
Analytical Method: TCLP RCRA Metals by SW-846 1311/6010C							Prep Method: SW3010A			
Tech:	4099 % Moisture:									
Analyst:	lyst: ABA Date Prep: 05.20.15 15.56									
Seq Number:	968619									
Parameter		Cas Number	Result	PQL	MDL	Units	Analysis Date	Flag	Dil	
Cadmium		7440-43-9	0.00100	0.0100	0.000600	mg/L	05.21.15 13.28	Ι	1	
Chromium		7440-47-3	0.00800	0.100	0.000600	mg/L	05.21.15 13.28	VI	1	

0.0200

0.200

0.00660

0.00180

mg/L

mg/L

05.21.15 13.28

05.21.15 13.28

0.0570

1.24

7439-92-1

7440-66-6





#### **FLORIDA flagging criteria**

Data were reviewed by the Department Supervisor and QA Director

- Value reported is the mean (average) of two or more determinations. Α
- Results based upon colony counts outside the acceptable range. B
- Estimated value; value not accurate. All results with a "J" qualifier require comment. J
  - J1: Surrogate Recoveries exceed established QA/QC Limits
  - J2: No known QA/QC exists.
  - J3: Reported value failed to meet established QA/QC limits or the sample matrix interfered with the ability to make an accurate determination
  - J4: The data is questionable due to improper laboratory or field protocols
- **Q** Sample held beyond the accepted holding time
- **T** Value reported is less than the laboratory method detection limit. The value is reported for informational purposes, only and shall not be used in statistical analysis.
- U Compound was analyzed for but not detected at the MDL Level.
- V Analyte was detected in both the sample and the associated method blank.
- Y Laboratory analysis was from an unpreserved or improperly preserved sample. The data may not be accurate.
- Ι The reported value is between the laboratory MDL and the laboratory PQL.
- R Significant rain in the past 48 hours.
- NELAC certification not offered for this compound. +
- (Next to analyte name or method description) = Outside XENCO's scope of NELAC accreditation

Recipient of the Prestigious Small Business Administration Award of Excellence in 1994. Certified and approved by numerous States and Agencies. A Small Business and Minority Status Company that delivers SERVICE and QUALITY Houston - Dallas - San Antonio - Atlanta - Midland/Odessa - Tampa/Lakeland - Phoenix - Latin America

4143 Greenbriar Dr. Stafford, TX 77477 9701 Harry Hines Blvd , Dallas, TX 75220 5332 Blackberry Drive, San Antonio TX 78238 2505 North Falkenburg Rd, Tampa, FL 33619 12600 West I-20 East, Odessa, TX 79765 6017 Financial Drive, Norcross, GA 30071 3725 E. Atlanta Ave, Phoenix, AZ 85040

Phone	Fax
(281) 240-4200	(281) 240-4280
(214) 902 0300	(214) 351-9139
(210) 509-3334	(210) 509-3335
(813) 620-2000	(813) 620-2033
(432) 563-1800	(432) 563-1713
(770) 449-8800	(770) 449-5477
(602) 437-0330	



# QC Summary 507972



#### Shaw Environmental

SR 780 Over Coon Key Causeway - Bridge 170951 Sarasota, FL

Analytical Method: Seq Number: MB Sample Id:	<b>Metals, Total by SV</b> 968527 692735-1-BLK	W846 6010		Matrix: nple Id:	Solid 692735-1-	-BKS			ep Metho Date Pro D Sample	ep: 05.1	8050B 9.15 735-1-BSD	
Parameter	MB Result	Spike Amount	LCS Result	LCS %Rec	LCSD Result	LCSD %Rec	Limits	%RPD	RPD Limit	Units	Analysis Date	Flag
Cadmium	< 0.0200	100	89.7	90	97.1	97	75-125	8	20	mg/kg	05.20.15 12:21	
Chromium	< 0.0600	100	92.9	93	100	100	75-125	7	20	mg/kg	05.20.15 12:21	
Lead	0.530	100	89.9	90	97.6	98	75-125	8	20	mg/kg	05.20.15 12:21	
Zinc	3.62	100	102	102	101	101	75-125	1	20	mg/kg	05.20.15 12:21	

<b>Analytical Method:</b> Seq Number: Parent Sample Id:	<b>Metals, Total by SW846 60100</b> 968527 507861-002		Liquid 507861-002 D	Pr	ep Metho Date Pre	od: SW3 ep: 05.1	3050B 9.15	
Parameter	Parent Result	MD Result		%RPD	RPD Limit	Units	Analysis Date	Flag
Cadmium	1.43	1.26		13	20	mg/kg	05.20.15 12:33	
Chromium	40.6	37.7		7	20	mg/kg	05.20.15 12:33	
Lead	23100	24100		4	20	mg/kg	05.20.15 12:33	
Zinc	155	150		3	20	mg/kg	05.20.15 12:33	

<b>Analytical Method:</b> Seq Number: Parent Sample Id:	<b>Metals, Total by SV</b> 968527 507861-002	V846 6010C		Matrix: nple Id:	1	)2 S			ep Metho Date Pro D Sample	ep: 05.1	8050B 9.15 861-002 SD	
Parameter	Parent Result	Spike Amount	MS Result	MS %Rec	MSD Result	MSD %Rec	Limits	%RPD	RPD Limit	Units	Analysis Date	Flag
Cadmium	1.43	90.9	81.2	88	88.0	91	75-125	8	20	mg/kg	05.20.15 12:34	
Chromium	40.6	90.9	105	71	117	80	75-125	11	20	mg/kg	05.20.15 12:34	J
Lead	23100	90.9	23500	440	24900	1891	75-125	6	20	mg/kg	05.20.15 12:34	J
Zinc	155	90.9	189	37	260	110	75-125	32	20	mg/kg	05.20.15 12:34	J

Analytical Method: Seq Number: MB Sample Id:	<b>TCLP RCRA Meta</b> 968619 692821-1-BLK	ls by SW-8		Matrix:	Water 692821-1-	-BKS			ep Metho Date Pro D Sample	ep: 05.2	3010A 0.15 821-1-BSD	
Parameter	MB Result	Spike Amount	LCS Result	LCS %Rec	LCSD Result	LCSD %Rec	Limits	%RPD	RPD Limit	Units	Analysis Date	Flag
Cadmium	< 0.000600	2.00	2.04	102	1.98	99	80-120	3	20	mg/L	05.21.15 12:30	
Chromium	0.00240	2.00	2.04	102	1.97	99	80-120	3	20	mg/L	05.21.15 12:30	
Lead	< 0.00660	2.00	2.07	104	2.01	101	80-120	3	20	mg/L	05.21.15 12:30	
Zinc	0.00240	2.00	2.03	102	1.97	99	80-120	3	20	mg/L	05.21.15 12:30	



# QC Summary 507972



#### Shaw Environmental

SR 780 Over Coon Key Causeway - Bridge 170951 Sarasota, FL

Analytical Method: Seq Number:	TCLP RCRA Metals 968619	<b>by SW-846 1311/6010C</b> Matrix:	Solid	Pr	ep Metho Date Pro		8010A 0 15	
Parent Sample Id:	507861-001				Date I I	ср. 05.2	0.15	
Parameter	Parent Result	MD Result		%RPD	RPD Limit	Units	Analysis Date	Flag
Cadmium	0.0162	0.0162		0	20	mg/L	05.21.15 12:35	
Chromium	0.00280	0.00180		43	20	mg/L	05.21.15 12:35	JI
Lead	0.0248	0.0192		25	20	mg/L	05.21.15 12:35	JI
Zinc	0.140	0.137		2	20	mg/L	05.21.15 12:35	Ι

<b>Analytical Method:</b> Seq Number: Parent Sample Id:	<b>TCLP RCRA Meta</b> 968619 507861-001	ls by SW-8	<b>46 1311/6010C</b> Matrix: Solid MS Sample Id: 507861-001 S					Prep Method: SW3010A Date Prep: 05.20.15 MSD Sample Id: 507861-001 SD				
Parameter	Parent Result	Spike Amount	MS Result	MS %Rec	MSD Result	MSD %Rec	Limits	%RPD	RPD Limit	Units	Analysis Date	Flag
Cadmium	0.0162	2.00	1.94	96	2.03	101	80-120	5	20	mg/L	05.21.15 12:37	
Chromium	0.00280	2.00	1.95	97	2.04	102	80-120	5	20	mg/L	05.21.15 12:37	
Lead	0.0248	2.00	1.98	98	2.06	102	80-120	4	20	mg/L	05.21.15 12:37	
Zinc	0.140	2.00	2.06	96	2.16	101	80-120	5	20	mg/L	05.21.15 12:37	

<b>O</b> <sup>m</sup>
Uă
<b>F</b>
67
∠ <b>X</b> ≦.
۲ P

# CHAIN OF CUSTODY

wother of the -

Lakeland, Florida (863-646-8526)

Odessa, Texas (432-563-1800)

the Standard since 1990	1,Texas (281-240-4200)
ŝ	Stafford,Texa

Dallas Texas (214-902-0300)			Norcross, Georgia (770-449-8800)	(770-449-8600)	Tampa, Fl	Tampa, Florida (813-620-2000)
Service Center - San Antonio, Texas (210-509-3334)	WWW, XENCO, COM		Xenco Quote #	X	Xenco Job #	
			Analy	Analytical Information		Matrix Codes
Client / Reporting Information	Project information					
Company Name / Branch: CB&I Environmental and Infrastructure	12		ł			S = Soil/Sed/Solid
Company Address:	Project Location: SR 780 Over Coon Key Causeway - Bridge 170951 Sarasota FL	useway - Bridge 170951	151			GW =Ground Water DW = Drinking Water
1228 Winter Garden vinetang byg Winter Garden, FL 34787		**************************************				P = Product SW = Surface uniter
Email: Phone No:	Invoice To:					SL = Sludge
shawn.flynn@cbi.com 407-287-2310						OW ≓Ocean/Sea Water W = Wine
Project Contact: Shawn Flynn	PO Number:					10=0
Samplers's Name ThornAS CREQUIN						WW≕ Waste Water A = Air
0	Collection	Number of preserved bottles				
No. Field ID / Point of Collection	Sample Sample Depth Date Matrix bottles <u>FC</u>	NONE WEOH NªHRO¢ HSRO¢ HSRO¢ HNO3 Ycefare	Cq' Ct' Cq' Ct'			Field Comments
1 Pile cover composite	5.20/5 1000 Paint		××			
. 7						
<b>c</b> 7						лалишшин наосуу т
The second						
. по		·····				
Q						
2						
8						
σ						**************************************
10						
Turnaround Time (Business days)	Data Deliverable Information	formation		Notes:		
Same Day TAT	Levei II Std QC	Level IV (Full Data Pkg /raw data)	(raw data)			
Next Day EMERGENCY	Level III Std QC+ Forms	TRRP Level IV				
2 Day EMERGENCY	Level 3 (CLP Forms)	UST / RG -411				
3 Day EMERGENCY	TRRP Checklist			-		
TAT Starts Day received by Lab, if received by 3:00 pm	00 pm			FED-EX / UPS: Tracking#	S: Tracking #	
	CUMENTED	4GE POSSESSION, INCLUDING COURI	. ⊁	*****	<u> </u>	
Relinquished by Sampler:	S-15/5/12001	Relinquished By: 2 2 2 2 2 2	Date Time:	6-12-0	A CZ	lew XL 2
Relinquished by:		Relinquished By: 4	Date Time:	*****	eceived By:	
Relinquished by:	Date Time: Received By:	Custody Seal #	Preserved wi	Preserved where applicable	On Ice	Cooler Temp. Thermo. Corr. Factor
5 Notice: Signature of this document and relinquishment of samples constitutes a valid purchase order from client company to XENCO Laboratories and its affiliates, subcontractors and assigns XENCOs standard terms and conditions of service unless neglotiated under a fully executed client contract.	15 valid purchase order from client company to XENCO Laboratories and	its affiliates, subconfractors and assigns	ENCO's standard terms	t and conditions of ser	i i vice unless previously negiotiat	ed under a fully executed client contract.

Final 1.001

#### **UPS CampusShip: View/Print Label**

- 1. Ensure there are no other shipping or tracking labels attached to your package. Select the Print button on the print dialog box that appears. Note: If your browser does not support this function select Print from the File menu to print the label.
- 2. Fold the printed label at the solid line below. Place the label in a UPS Shipping Pouch. If you do not have a pouch, affix the folded label using clear plastic shipping tape over the entire label.

#### 3. GETTING YOUR SHIPMENT TO UPS

# UPS locations include the UPS Store<sup>®</sup>, UPS drop boxes, UPS customer centers, authorized retail outlets and UPS drivers.

Schedule a same day or future day Pickup to have a UPS driver pickup all your CampusShip packages.


#### Hand the package to any UPS driver in your area.

Take your package to any location of The UPS Store®, UPS Drop Box, UPS Customer Center, UPS Alliances (Office Depot® or Staples®) or Authorized Shipping Outlet near you. Items sent via UPS Return Services(SM) (including via Ground) are also accepted at Drop Boxes. To find the location nearest you, please visit the Resources area of CampusShip and select UPS Locations.

#### **Customers with a Daily Pickup**

Your driver will pickup your shipment(s) as usual.

#### FOLD HERE



#### https://www.campusship.ups.com/cship/create2agtion@riginPair=default\_\_\_PrintWindow... 5/15/2015



#### XENCO Laboratories Prelogin/Nonconformance Report- Sample Log-In



Client: Shaw Environmental

Date/ Time Received: 05/18/2015 09:52:00 AM

Work Order #: 507972

Acceptable Temperature Range: 0 - 6 degC Air and Metal samples Acceptable Range: Ambient

Comments

Temperature Measuring device used :

Sample Receipt Checklist	
#1 *Temperature of cooler(s)?	
#2 *Shipping container in good condition?	Yes
#3 *Samples received on ice?	N/A
#4 *Custody Seals intact on shipping container/ cooler?	Yes
#5 Custody Seals intact on sample bottles?	Yes
#6 *Custody Seals Signed and dated?	Yes
#7 *Chain of Custody present?	Yes
#8 Sample instructions complete on Chain of Custody?	Yes
#9 Any missing/extra samples?	No
#10 Chain of Custody signed when relinquished/ received?	Yes
#11 Chain of Custody agrees with sample label(s)?	Yes
#12 Container label(s) legible and intact?	Yes
#13 Sample matrix/ properties agree with Chain of Custody?	Yes
#14 Samples in proper container/ bottle?	Yes
#15 Samples properly preserved?	N/A
#16 Sample container(s) intact?	Yes
#17 Sufficient sample amount for indicated test(s)?	Yes
#18 All samples received within hold time?	Yes
#19 Subcontract of sample(s)?	No
#20 VOC samples have zero headspace (less than 1/4 inch bubble)?	N/A
#21 <2 for all samples preserved with HNO3,HCL, H2SO4? Except for samples for the analysis of HEM or HEM-SGT which are verified by the analysts.	N/A
#22 >10 for all samples preserved with NaAsO2+NaOH, ZnAc+NaOH?	N/A

#### \* Must be completed for after-hours delivery of samples prior to placing in the refrigerator

Analyst:

PH Device/Lot#:

Checklist completed by:

Dario Lagunas

Date: 05/18/2015

Checklist reviewed by:

Ruriko Konuma

Date: 05/18/2015

#### DISCLAIMER

The services described in this report were performed consistent with generally accepted professional consulting principles and practices. No other warranty, expressed or implied, is made. These services were performed consistent with our agreement with our client. This report is solely for the use and information of our client unless otherwise noted. Any reliance on this report by a third party is at such party's sole risk.

Opinions and recommendations contained in this report apply to conditions existing when services were performed and are intended only for the client, purposes, locations, time frames, and project parameters indicated. We are not responsible for the impacts of any changes in environmental standards, practices, or regulations subsequent to performance of services. We do not warrant the accuracy of information supplied by others, or the use of segregated portions of this report.

# CSER APPENDIX F

## CSER Appendix F Current Land Use Summary and Risk Assessment SR 789 MP 1.206 (Bird Key Drive) to MP 1.947 (Sarasota Harbor West)

CSER Site ID No.	EDR No.	Owner or Business	Street Address	Potential Contaminant	Facility ID No.	Database Listing(s)	Distance & Direction from Corridor	Description and Commentary	Risk
1		Jack Graham, Inc.	2 Marina Plaza	Undetermined	58-64182742		1.1 miles east	No listings or documents in Oculus database	No
2		Sarasota Co.	Bird Key Park	Vehicle fluids			MP 1.206	Parking area along north side of Bird Key. <b>Photo 2</b>	No
3		FDOT	SR 789 Bridge <b>Photo 3</b>				MP 1.416 to 1.583 (est)	Twin span of SR 789, the replacement of which is a key element of this project.	Medium
4		FDOT	SR 789 Sidewalks Photo 4 Photo 8				MP 1.583	Sidewalk improvements underway along north and south sides of SR 789 for the length of Coon Key	No
5		East	Sarasota Harbor <b>Photo 5</b>				MP 1.583 (est) to MP 1.947	Northwest side of project corridor. Eight (8) Three-story condominiums that include three (3) entries from SR 789.	No
		Sarasota Harbor							
		West							

## Current Land Use Summary and Risk Assessment

CSER Site ID No.	EDR No.	Owner or Business	Street Address	Potential Contaminant	Facility ID No.	Database Listing(s)	Distance & Direction from Corridor	Description and Commentary	Risk
6	1	Sarasota Yacht Club (SYC)	1100 John Ringling Blvd <b>Photo 6</b>	Petroleum	58-8516507	UST LUST Fin. Assure	MP 1.583 to MP 1.706 (est)	South side of SR 789; facility currently in compliance. <b>See Note No. 1</b>	Low
7	2	Plymouth Harbor on Sarasota Bay	700 John Ringling Blvd <b>Photo 7</b>	Petroleum	58-9500095	UST AST Asbestos Fin. Assure NPDES	MP 1.831 (est)	South side of SR 789; no reported historical discharges. Facility currently in compliance	Low
9	3	Harris res.	243 Robin Dr	Petroleum	58-9401473	UST LUST	1,300 feet SE of MP 1.221	300-gal home heating fuel oil tank installed in May 1994. Leak (found in 2000?) Remediated and abandoned / closed. <b>See Note No. 1</b>	No
		Foxy Lady (fmr Chevron)	481 John Ringling Blvd	Petroleum	58-9700801	Not in EDR	0.3-mile west	Gasoline & Diesel release June 1997. Comments to TSAR dated May 2020. See Note No. 1	No
		(former) Exxon	1 N. Blvd of Presidents	Petroleum	58-8520819	Not in EDR	0.4-mile west	Gasoline release dated January 1991. <b>See Note No. 1</b>	No

Notes: Select documents obtained through the FDEP Citizen's Portal (Oculus) are included in Appendix B.

### **Current Land Use Summary and Risk Assessment**

#### Summary

Risk	Number of Sites		
No	7		
Low	2		
Medium	1		
High	0		

Based on the proximity of the UST at SYC and the AST at Plymouth Harbor to the Project Corridor, neither facility represents a risk to soil and/or groundwater quality along the project corridor with any real sense of practicality. **Assessed Risk: LOW** 

The twin 2-lane concrete bridges that are each about 1,010-feet long are identified as representing a **MEDIUM** risk to environmental quality along the project corridor.

# CSER APPENDIX G



Photo 1: Project Area - Aerial View (dated January 2019).

Red arrows show extent of Project Corridor

Red Line = 1,000 feet



Photo 2A: Parking Area at Bird Key Park – CSER Site #1. View toward northeast.



Photo 2B: Parking Area at Bird Key Park – CSER Site #1. View toward southwest.



Photo 3A: Sidewalk Construction Area – CSER Site #2.



Photo 3B: Sidewalk Construction Area – CSER Site #2.



Photo 3C: Sidewalk Construction Area – CSER Site #2.



**Photo 4A:** Sarasota Harbor East condominiums – CSER Site #3.



Photo 4B: Entrance into Sarasota Harbor West condominiums (MP 1.947) – CSER Site #3.



Photo 5A: Harris Residence – CSER Site #4. Aerial of 243 Bird Drive (red arrow).



Photo 5B: Harris Residence – CSER Site #4. 243 Bird Drive.



Photo 6A: Bridge # 170022 – CSER Site #5. View is Southbound.



**Photo 6B** Bridge # 170022 – CSER Site #5.




Photo 6C: Bridge # 170951 – CSER Site #5. View is northbound.





2006 Red arrow shows location of former UST's

2009 Under demolition and re-construction



2019 (most recent available) Location of UST's shown with red oval

Photo 7A: Aerial photos of Sarasota Yacht Club (SYC) – CSER Site #6.

Source: Google Earth



Photo 7B: Entrance into Sarasota Yacht Club - CSER Site #6.



**Photo 7C:** Sarasota Yacht Club – CSER Site #6. Location of present-day UST's shown with red oval.



Photo 8A: Plymouth Harbor Retirement Community – CSER Site #7.



Photo 8B: Plymouth Harbor Retirement Community – CSER Site #7. View is northeast.



Source: Google Earth, dated Jan 2019

Photo 8C: Plymouth Harbor Retirement Community – CSER Site #7. Location of 8,000-gallon AST (red oval)



**Photo 8D:** Plymouth Harbor Retirement Community – CSER Site #7. Overview of exit from Plymouth Harbor onto and across SR 789.