Southwest Florida
Florida Department of Transportation

US 98 from south of Griffin Road to Sharon Drive 445468-1

Project Details	
Work Type	Resurfacing
Phase	Construction
Limits	south of Griffin Road to Sharon Drive
Project Start	Late 2024
City	Lakeland
County	Polk
Road	I-4 US 98
Construction Cost	$12.5 million
Estimated Completion	Mid 2026

Contact Information

Communications Team
Sandra Mancil
863-519-4116
Sandra.Mancil@dot.state.fl.us



About

US 98 from south of Griffin Road to Sharon Drive: Construction project: The FDOT is making safety improvements to US 98 from south of Griffin Road to Sharon Drive in Lakeland. The project includes the following enhancements:

- milling and resurfacing US 98 from south of Griffin Road to Sharon Drive
- repairing and improving drainage
- enhancing lighting at the intersections
- emphasizing bike lanes by painting them green to improve visibility
- adding special emphasis crosswalks at Griffin Road, Pyramid Parkway, across US 98 south of the interstate and across all the I-4 ramps
- adding pedestrian fencing in the median between Pyramid Parkway and the crosswalk south of the I-4 ramps to channel pedestrians safely to the crossings
- changing the way traffic merges from the slip lane at Pyramid Parkway onto US 98
- replacing unnecessary asphalt with green space at the intersection of Pyramid Parkway and US 98 as a traffic calming effort and for beautification
- adjusting the stop bar past the Burger King driveway to improve safety at Pyramid Parkway on the west side of US 98
- upgrading and adjusting signal equipment to improve visibility for motorists when making left turns at Griffin Road and at Crevasse Street
- adding signs on northbound US 98 identifying the I-4 ramps